#### A-8.0 CONSTRUCTION COMPONENT

The construction component of this plan is composed of the following elements:

- 1. **Section A-8.1**, Program Summary
- 2. Section A-8.2, Model Construction Program
- 3. **Section A-8.3**, Education and Training


#### A-8.1 PROGRAM SUMMARY

#### A-8.1.1 Program Overview

Construction and grading activities are a potential source of pollutants in all phases of execution. The following sections present a detailed set of guidelines to prevent or minimize the impacts of urban runoff generated by construction activities within the City of Lake Forest on receiving water bodies.

The City of Lake Forest has key staff responsible for overseeing, implementing, and enforcing the program. These staff members are identified in **Figure A-8.1** below.

Figure A-8.1



The following section outlines and describes City departments that are involved in issuing building and/or grading permits for private development projects and are responsible for inspecting these projects during construction, or that manage public works construction projects that have a potential to impact water quality.

Development Services Department - Planning Division

Contact Name: Cheryl Kuta Title: Planning Manager Telephone: 949-461-3479

The Planning Division is responsible for implementing the policies and objectives of the community as set forth in the municipality's General Plan and Zoning Ordinance. This Division also reviews proposed developments for consistency with the City's standards and policies relating to land use, and preservation of the environment, to ensure that the quality of life will be maintained or enhanced for future generations.

Development Services Department - Building and Safety Division

Contact Name: Tony Dormanesh

Title: Building Official Telephone: 949-461-3464

The Building and Safety Division ensures that all building construction in the City complies with adopted codes, and that permitting and licensing systems are efficient and serve the needs of the public, as well as the City.

Public Works Department - Engineering Division

Contact Name: Theodore Simon Title: Engineering Services Manager

Telephone: 949-461-3488

The Engineering Division is responsible for the administration of public improvement projects (typically result in construction activity). The Engineering Division ensures all construction in the public right-of-way complies with adopted codes and engineering standards.

Public Works Department - Maintenance Division

Contact Name: Luis Estevez Title: Public Works Manager Telephone: 949-461-3485

The Maintenance Division develops, builds and maintains the City's infrastructure, including streetscapes, open space, parks, athletic fields, trails, roadways, traffic signals and many miles of interconnected drainage system.

#### A-8.1.2 Program Commitments

The major program commitments and the subsections in which they are described in detail include:

- Maintain/update inventories of construction sites/construction projects (A-8.2.2);
- Prioritize fixed facilities, construction sites/construction projects (A-8.2.3);
- BMPs for construction sites/construction projects (A-8.2.4);
- Documentation requirements (A-8.2.5);
- Inspection and enforcement (A-8.2.6); and
- Education and training (A-8.3).

#### A-8.2.3 Regulatory Requirements

The Model Construction Program was developed in to fulfill the municipal activity commitments and requirements of:

- Section XV of the Santa Ana Regional Water Quality Control Board Municipal NPDES Stormwater permit, Order No. R8-2009-0030; and
- Section F.3 of the San Diego Regional Water Quality Control Board Municipal NPDES Stormwater permit, Order No. R9-2009-0002.

#### A-8.2 MODEL CONSTRUCTION PROGRAM

#### A.8.2.1 Model Program Overview

The City has incorporated the model construction program described in **DAMP Section 8.2** as the basis for this section of its Local Implementation Plan (LIP). This construction program presents requirements and guidelines for pollution prevention methods that must be used by construction site owners, developers, contractors, and other responsible parties, in order to prevent illicit discharges into the MS4, implement and maintain structural and non-structural BMPs to reduce pollutants in stormwater runoff from construction sites to the MS4, reduce construction site discharges of stormwater pollutants from the MS4 to the maximum extent practicable (MEP), and prevent construction site discharges from the MS4 from causing or contributing to a violation of water quality standards.

#### A-8.2.2 Inventory of Construction Sites

A watershed-based inventory of all construction sites has been developed. This includes all sites meeting the definition of a construction project provided in **DAMP Section 8.1.5**, including those covered by the State General Permit<sup>1</sup>, a local grading permit or a local building permit, and public works construction projects, and where activities at the site include: soil movement;

<sup>&</sup>lt;sup>1</sup> State Water Resources Control Board (SWRCB) Order No. 2009-0009-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Stormwater Runoff Associated with Construction Activity

uncovered storage of materials or wastes, such as dirt, sand or fertilizer; or exterior mixing of cementaceous products, such as concrete, mortar or stucco..

The City of Lake Forest's comprehensive construction site inventory is included in **Exhibit A-8.I**. The inventory will at a minimum be updated biannually; once in September – prior to the start of each wet season – and the second update in May. During the update process, projects for which building or grading permit(s) have expired or have been closed, and projects that have been completed, will be removed from the inventory. New projects will also be added to the inventory as they are initiated. A GIS map showing the location of the construction projects inventoried and their proximity to environmentally sensitive areas has also been included in **Exhibit A-8.I**.

#### A-8.2.3 Prioritization of Construction Sites

Construction sites/projects are prioritized into high, medium, or low categories, based on the threat to water quality in the Santa Ana Region. In the San Diego Region, construction sites/projects are prioritized based on the nature and size of the construction activity, topography, and the characteristics of soils and receiving water quality per the guidelines set forth in **DAMP Section 8.2.3.** Priorities will at a minimum be updated annually in conjunction with the annual update of the inventory.

#### A-8.2.4 BMPs for Construction Projects

All construction projects, regardless of size, are required to implement BMPs to prevent discharges into the storm drain system or watercourses. The City has established a minimum set of BMPs and other measures to be implemented at all construction sites year round. BMP implementation requirements may vary seasonally (wet and dry seasons); however, dry season BMP implementation must plan for and address unseasonal rain events that may occur during the dry season.

All private and public works projects are required, at a minimum, to implement and be protected by an effective combination of erosion and sediment controls and waste and materials management BMPs. The minimum requirements for construction sites in the Santa Ana Region are summarized in **Table A-8.1**. The minimum requirements for construction sites in the San Diego Region are summarized in **Table A-8.2**.

Table A-8.1 Minimum Requirements for Construction Sites in the Santa Ana Region

| CATEGORY                                  | MINIMUM REQUIREMENTS  |
|---|---|
| Erosion and Sediment Control              | Sediments from areas disturbed by construction shall be retained on site using an effective combination of erosion and sediment controls to the maximum extent practicable, and stockpiles of soil shall be properly contained to minimize sediment transport from the site to streets, drainage facilities or adjacent properties via runoff, vehicle tracking, or wind. |
| Waste and Materials<br>Management Control | Construction-related materials, wastes, spills or residues shall be retained on site to minimize transport from the site to streets, drainage facilities, or adjoining property by wind or runoff.  |

Table A-8.2 Minimum Requirements for Construction Sites in the San Diego Region

| CATEGORY    | MINIMUM REQUIREMENTS   |
|-------------|--|
| Management  | i. Pollution prevention where appropriate;   |
| Measures    | ii. Development and implementation of a site specific run-off  |
|             | management plan;   |
|             | iii. Minimization of areas that are cleared and graded to only the portion   |
|             | of the site that is necessary for construction;  |
|             | iv. Minimization of exposure time of disturbed soil areas;   |
|             | v. Minimization of grading during the wet season and correlation of  |
|             | grading with seasonal dry weather periods to the extent feasible;  |
|             | vi. Limitation of grading to a maximum disturbed area as determined by   |
|             | the City before either temporary or permanent erosion controls   |
|             | are implemented to prevent stormwater pollution. The City has  |
|             | the option of temporarily increasing the size of disturbed soil  |
|             | areas by a set amount beyond the maximum, if the individual site   |
|             | is in compliance with applicable stormwater regulations and the site has adequate control practices implemented to prevent                               |
|             | stormwater pollution;  |
|             | vii. Temporary stabilization and reseeding of disturbed soil areas as  |
|             | rapidly as feasible;   |
|             | viii. Wind erosion controls;   |
|             | ix. Tracking controls;   |
|             | x. Non-stormwater management measures to prevent illicit discharges  |
|             | and control stormwater pollution sources;  |
|             | xi. Waste management measures;   |
|             | xii. Preservation of natural hydrologic features where feasible;   |
|             | xiii. Preservation of riparian buffers and corridors where feasible;   |
|             | xiv. Evaluation and maintenance of all BMPs, until removed; and  |
|             | xv. Retention, reduction, and proper management of all stormwater  |
| T 1         | pollutant discharges on site to the MEP standard.  |
| Erosion and | i. Erosion prevention. Erosion prevention is to be used as the most  |
| Sediment    | important measure for keeping sediment on site during  |
| Controls    | construction;  |
|             | <ul><li>ii. Sediments controls. Sediment controls are to be used as a supplement<br/>to erosion prevention for keeping sediment on-site during</li></ul> |
|             | construction;  |
|             | i. Slope stabilization must be used on all active slopes during rain   |
|             | events regardless of the season and on all inactive slopes during  |
|             | the rainy season and during rain events in the dry season; and   |
|             | ii. Permanent revegetation or landscaping as early as feasible.  |

Enhanced BMPs

In addition to the minimum requirements for construction sites in the San Diego Region identified in **Table A-8.2** above, the City requires enhanced or additional BMPs should the project site pose an exceptional threat to water quality. In determining the potential threat, the City considers the following factors:

- a) Soil erosion potential or soil type;
- b) Site slopes;
- c) Project size and type;
- d) Sensitivity and proximity to receiving water bodies;
- e) Non-stormwater discharges;
- f) Ineffectiveness of other BMPs;
- g) Proximity and sensitivity of aquatic threatened and endangered species of concern;
- h) Known effects of Advanced Sediment Treatment (AST) chemicals; and
- i) Any other relevant factors

If an exceptional threat to water quality is determined based on the above factors, the City will require implementation of advanced treatment for sediment at construction sites (or portions thereof).

Construction BMPs

The City of Lake Forest has designated construction-specific BMPs as set forth in **DAMP Section 8.2.4.3**. **Table A-8.3**, below describes the BMPs designated for use with this LIP. Copies of the corresponding BMP fact sheets are included as **Exhibit A-8.II**.

Table A-8.3 Designated Construction BMPs

| CATEGORY                  | BMP # | BMP NAME                            |
|---------------------------|-------|-------------------------------------|
|                           | EC-1  | Scheduling                          |
|                           | EC-2  | Preservation of Existing Vegetation |
|                           | EC-3  | Hydraulic Mulch                     |
|                           | EC-4  | Hydroseeding                        |
| $\mathbb{P}^{\mathbf{s}}$ | EC-5  | Soil Binders                        |
| $\mathbf{Z}$              | EC-6  | Straw Mulch                         |
| Control BMPs              | EC-7  | Geotextiles and Mats                |
| l th                      | EC-8  | Wood Mulching                       |
| Co                        | EC-9  | Earth Dikes and Drainage Swales     |
|                           | EC-10 | Velocity Dissipation Devices        |
| Erosion                   | EC-11 | Slope Drains                        |
| Erc                       | EC-12 | Streambank Stabilization            |
|                           | EC-13 | Reserved                            |
|                           | EC-14 | Compost Blanket                     |
|                           | EC-15 | Soil Preparation/Roughening         |
|                           | EC-16 | Non-Vegetative Stabilization        |

|                             | T     | 1-4-   |
|-----------------------------|-------|--|
|                             | SE-1  | Silt Fence   |
|                             | SE-2  | Sediment Basin   |
| ွှ                          | SE-3  | Sediment Trap  |
| l H                         | SE-4  | Check Dam  |
| <b>B</b> ]                  | SE-5  | Fiber Rolls  |
| rol                         | SE-6  | Gravel Bag Berm  |
| Sediment Control BMPs       | SE-7  | Street Sweeping and Vacuuming                          |
| Į Ž                         | SE-8  | Sandbag Barrier  |
| ent                         | SE-9  | Straw Bale Barrier                                     |
| l iii                       | SE-10 | Storm Drain Inlet Protection                           |
| )ed                         | SE-11 | Active Treatment Systems                               |
| <b>J 3</b> ,                | SE-12 | Temporary Silt Dike                                    |
|                             | SE-13 | Compost Socks and Berms                                |
|                             | SE-14 | Biofilter Bags   |
| Wind                        |       |  |
| Erosion                     | WE-1  | Wind Erosion Control                                   |
| Control                     | 1177  | The Liberoit Collies                                   |
| BMPs                        | <br>  |  |
| Tracking                    | TC-1  | Stabilized Construction Entrance/ Exit                 |
| Control                     | TC-2  | Stabilized Construction Roadway                        |
| BMPs                        | TC-3  | Entrance/Outlet Tire Wash                              |
|                             | NS-1  | Water Conservation Practices                           |
|                             | NS-2  | Dewatering Operations                                  |
|                             | NS-3  | Paving and Grinding Operations                         |
| Ps                          | NS-4  | Temporary Stream Crossing                              |
| Ĭ.                          | NS-5  | Clear Water Diversion                                  |
|                             | NS-6  | Illicit Connection/Illegal Discharge Detection and     |
| Non-Stormwater Control BMPs |       | Reporting  |
| Cor                         | NS-7  | Potable Water/Irrigation                               |
| er (                        | NS-8  | Vehicle and Equipment Cleaning                         |
|                             | NS-9  | Vehicle and Equipment Fueling                          |
| l mw                        | NS-10 | Vehicle and Equipment Maintenance                      |
| Ori                         | NS-11 | Pile Driving Operations                                |
| -St                         | NS-12 | Concrete Curing  |
| lon                         | NS-13 | Concrete Finishing                                     |
| 2                           | NS-14 | Material and Equipment Use Over Water                  |
|                             | NS-15 | Structure Demolition/Removal Over or Adjacent to Water |
|                             | NS-16 | Temporary Batch Plants                                 |

|   | WM-1  | Material Delivery and Storage     |
|---|-------|-----------------------------------|
| % <sub>□</sub>  | WM-2  | Material Use                      |
| Waste Management<br>Materials Pollutior<br>Control BMPs | WM-3  | Stockpile Management              |
| igemer<br>Pollutio<br>BMPs                              | WM-4  | Spill Prevention and Control      |
| agg<br>Po<br>1 B  | WM-5  | Solid Waste Management            |
| ite Mana<br>aterials I<br>Control                       | WM-6  | Hazardous Waste Management        |
| eri<br>on   | WM-7  | Contaminated Soil Management      |
| aste<br>Iat<br>C  | WM-8  | Concrete Waste Management         |
|   | WM-9  | Sanitary/ Septic Waste Management |
|   | WM-10 | Liquid Waste Management           |

#### A-8.2.5 Documentation Requirements

The City of Lake Forest has adopted the documentation requirements provided in **DAMP Section 8.2.5**. These requirements apply equally to private development and public works projects.

Requirements for General Permit Sites

Construction sites that are subject to the General Permit are required to prepare and implement a Stormwater Pollution Prevention Plan (SWPPP) meeting the requirements of the General Permit. More information regarding the Construction General Permit can be found at the State Water Resources Control Board's website at: <a href="http://www.swrcb.ca.gov/water\_issues/programs/stormwater/constpermits.shtml">http://www.swrcb.ca.gov/water\_issues/programs/stormwater/constpermits.shtml</a>

Private Construction Projects Covered by the General Permit

The following bullets describe the process that is followed by a private construction project:

- The project owner, developer or contractor is responsible for preparing the Notice of Intent (NOI), which must be signed by the owner or person delegated authority and submitted to the State Water Resources Control Board (SWRCB) via the Stormwater Multi-Application, Reporting, and Tracking System (SMARTS). Before issuing a grading or building permit, the City will require proof of General Permit coverage (See conditions of approval **Section A-7.x.x**).
- Once the project owner, developer or contractor receives a grading or building permit (if applicable), the SWPPP must be prepared by Qualified SWPPP Developer (QSD), and signed by the responsible party and must be implemented year-round throughout the duration of the project's construction. County or District staff are not responsible for reviewing, approving or enforcing the SWPPP; these are responsibilities of the Regional Board. Inspector(s) may choose to use the SWPPP as a tool for on-site inspections.
- The City will inspect and enforce local permit(s) and ordinances, and will notify the Regional Board of non-compliance when the non-compliance meets the criteria of posing a threat to human or environmental health as discussed in **DAMP Section 8.4.6**.

Within 90 days of when construction is complete or ownership has been transferred, the discharger shall electronically file a Notice of Termination (NOT), a final site map, and photos through the SWRCB SMARTS system. Filing a NOT certifies that all General Permit requirements have been met.

Public Agency Construction Projects Covered by the General Permit

The following bullets describe the process that is followed by a public works construction project:

- The City of Lake Forest will prepare all Permit Registration Documents (PRDs) and submit it to the SWRCB through the SMARTS system.
- The SWPPP will be prepared by a QSD, before the contractor is allowed to start construction activities. It is important to note that city staff is not responsible for enforcing the SWPPP, these are responsibilities of the Regional Water Quality Control Board; but inspectors are required to become familiar with the SWPPP as it is part of the contract documents.
- During construction, the City of Lake Forest will inspect and enforce the contract documents
  and will notify the appropriate Regional Board when non-compliance meets the criteria of
  posing a threat to human or environmental health as discussed in DAMP Section 8.2.6.7.
- Once the project is completed, the City of Lake Forest will file a NOT through SMARTS.

Requirements for Other Sites

Private Construction Projects Not Covered by the General Permit

Private construction projects not covered by the General Permit, but covered under a grading permit, are required to develop Erosion and Sediment Control Plans (ESCPs). These ESCPs must show proposed locations of the erosion and sediment control BMPs that will be implemented during the construction project to comply with the minimum requirements listed in **Table A-8.1**.

Public Works Construction Projects Not Covered by the General Permit

Public agency construction projects not covered by the General Permit are required by **DAMP Section 8.2.5.2** to comply with appropriate pollution prevention control practices in accordance with the current edition of the "Green Book" Standard Specifications for Public Works Construction and the provisions of Section A-8, and shall develop and implement ESCPs. Low priority construction sites shall meet the minimum requirements listed in **Table 8-7** of **DAMP Section 8.2.4.1**.

#### A-8.2.6 Municipal Inspections and Enforcement

Inspection Responsibilities

The City of Lake Forest performs inspections of construction sites to verify that the requirements in **DAMP Section 8.2.6** are being implemented and maintained, that they appropriately comply with local permits and ordinances and the General Permit, and that they continue to protect water quality. Construction sites are inspected, according to the established priority, until construction activity is complete.

Inspection Frequencies

The City of Lake Forest inspects construction sites based upon the priority of the project. The frequency of construction site inspections in the Santa Ana Region is shown in **Table A-8.4**. The frequency of construction site inspections in the San Diego Region is shown in **Table A-8.5**.

Table A-8.4
Inspection Frequency of Construction Sites in the Santa Ana Region Based on Construction Site Priority

| Construction Site Priority See DAMP Section 8.2.3 for prioritization details   | Rainy Season<br>Inspection<br>Frequency<br>(Oct 1 - April 30) | Dry Season Inspection<br>Frequency<br>(May 1 - Sept 30) |
|--|---|---|
| High The following sites are prioritized as mandatory high:  • Any site 20 acres or larger  • Any site 1 acre or larger tributary to Clean Water Act Section 303(d) waters listed for sediment or turbidity impairments  • Any site, regardless of size, tributary to and within 500 feet of an area defined by the Ocean Plan as an Area of Special Biological Significance | Once per month  | As Needed   |
| Medium All sites between 5 and 20 acres are prioritized, at a minimum as medium priority   | Twice during the season                                       | As Needed   |
| Low  | At Least Once during the season                               | As Needed   |
| ***When BMPs or BMP maintenance is de  | eemed inadequate or ou  | t of compliance, an                                     |

inspection frequency of once every week will be maintained until BMPs and BMP maintenance are brought into compliance (regardless of site prioritization)\*\*\*

Table A-8.5
Inspection Frequency of Construction Projects in the San Diego Region Based on Construction Site Priority

| Inspection Criteria  See Section DAMP Section 8.2.3 for prioritization details. Priorities for inspecting sites must consider the nature and size of the construction activity, topography, and the characteristics of soils and receiving water quality.   | Rainy Season<br>Inspection<br>Frequency<br>(Oct 1 - April 30) | Dry Season Inspection<br>Frequency<br>(May 1 - Sept 30) |
|---|---|---|
| Construction sites within the City's jurisdiction meeting any of the following criteria:  • Any site 30 acres or larger  • Any site 1 acre or larger and tributary to a CWA section 303(d) water body segment impaired for sediment or within or directly adjacent to, or discharging directly to, the ocean or a receiving water within an ESA  • Other sites determined by the Copermittees or the Regional Board as a significant threat to water quality. | Biweekly  | Annually in August or<br>September                      |
| Construction sites with one acre or more of soil disturbance not meeting the criteria specified for 'high' priority sites   | Monthly   | As Needed   |
| Construction sites that are less than one acre in size  | As Needed   | As Needed   |

<sup>\*\*</sup> Reinspection frequencies must be determined by each Copermittee based upon the severity of deficiencies, the nature of the construction activity, and the characteristics of soils and receiving water quality. \*\*

#### Inspection Documentation Procedures

The City of Lake Forest's construction site inspection form is included in **Exhibit A-8.III**. Records of all inspections and non-compliance reporting will be retained for a period of at least five years.

#### **Enforcement Actions**

Enforcement of construction projects will be undertaken by the City of Lake Forest's inspectors and/or other staff who possess internal enforcement authority through established policies and procedures. Threat to water quality will be assessed by inspectors for construction site runoff that will not be reasonably controlled by the BMPs in place or if a failure of BMPs is resulting in the release of sediments or other pollutants. Violations observed will be documented by the inspectors.

If a significant and/or immediate threat to water quality is observed by an inspector, action will be taken to require the developer/contractor to immediately cease the discharge. **Table A-8.6** outlines the City of Lake Forest's enforcement steps that will be taken by inspectors for private construction projects and for public works construction projects. Depending on the violation, the inspector may choose to utilize contract language, a local permit, the grading ordinance or the water quality ordinance as the basis for enforcement.

Table A-8.6 Enforcement Actions for Construction Problems

| PRIVATE CONSTRUCTION PROJECTS   |             | PUBLIC WORKS CONSTRUCTION<br>PROJECTS   |
|---|-------------|---|
| Verbal Warning  |             | Verbal Warning  |
| Written Warning  Written Notice/Notice of Violation  Administrative Compliance Order  Administrative Citations or Fines  Cease and Desist Order | PROGRESSION | Written Warning  Notice of Violation  |
| Stop Work Order  Revocation of Permit(s) and/or Denial of Future Permits  | ← WARNING   | Enforcement of Contract  Stop Work Order  Withholding of Payment  Bond  Fines  Revocation of Contract |
| Civil and Criminal Court Actions  |             | Civil and Criminal Court Actions  |

City of Lake Forest approved enforcement forms used by inspection staff are provided in **Exhibit A-8.IV**.

Non-Compliance Reporting

The City of Lake Forest will consider a site non-compliant when one or more violations of local ordinances, permits, or plans exist on the site. For the purpose of this document, such a violation shall also be considered a violation of the General Construction Permit for sites subject to those requirements. If a non-compliant private construction project meets the criteria of posing a threat to human or environmental health as discussed in of the **DAMP Section 8.2.6.7**, then the appropriate Regional Board will be notified as required.

Oral notification to the Regional Board of non-compliant private construction sites that are determined to pose a threat to human or environmental health will be provided within 24-hours of the discovery of non-compliance. Such oral notification shall be followed up by a written report and submitted to the within 5 days of the incidence of non-compliance. Written notification(s) will identify the type(s) of non-compliance, describe the actions necessary to achieve compliance, and include a time schedule, subject to the modifications by the indicating when compliance will be achieved.

The City will notify the San Diego Regional Water Quality Control Board prior to the wet season, or shall include with the annual PEA, a summary of all construction sites with alleged violations. Information provided shall include, but not be limited to, the following:

- 1. WDID number if enrolled under the General Construction Permit
- 2. Site Location, including address
- 3. Current violations or suspected violations

A form for evaluating the potential impacts to human or environmental health is provided in **Exhibit A-8.V** 

#### A-8.3 EDUCATION AND TRAINING

To assist responsible municipal staff and contract staff in understanding the DAMP's Model Construction Program, annual training sessions will be conducted. In addition to Permittee sponsored training, staff may also attend training seminars or workshops related to general water quality and stormwater management during construction, conducted by other organizations. Required training for municipal employees is included in **Table A-3.2** of this LIP.

#### A-8.3.1 Training Modules

To support implementation of the Construction Program element, two construction activity training modules were developed during the Third Term Permits as described in **DAMP Appendix B, Section B-8**. The two modules are *Municipal Activities Program Management* (**DAMP Appendix B, Exhibit B-8.I**) and *Inspecting Construction Site BMPs* (**DAMP Appendix B, Exhibit B-8.II**). The modules will be substantially updated in 2010-11 to reflect the requirements of the Fourth Term Permits.

## Exhibit A-8.I

# Construction Site Inventory Spreadsheet



#### NPDES Construction Facilities Inventory - Commercial Projects SAN DIEGO CREEK / NEWPORT BAY WATERSHED (SARWQCB) Year 2009-2010

|               | Grading/             |  |                  |                |                  |       |                   |         |                     | Total           |                |  |                    |                         |                            |                          |  |   |                    |                  |  |  |          | Inspected for<br>Erosion and             |   |           |             |
|---------------|----------------------|--|------------------|----------------|------------------|-------|-------------------|---------|---------------------|-----------------|----------------|--|--------------------|-------------------------|----------------------------|--------------------------|--|---|--------------------|------------------|--|--|----------|--|---|-----------|-------------|
| Issue<br>Date | Building<br>Permit # | Project<br>Name                              | Street<br>Number | Street<br>Name | Street<br>Suffix | Suite | City              | State Z | Tract<br>Vip Number | Site<br>Acreage | WDID<br>Number | Description<br>of Project                                  | Type of<br>Project | Source<br>Activities    | Construction<br>Start Date | Construction<br>End Date | Developer<br>Name                              | Developer<br>Address  | Developer<br>Phone | Developer<br>Fax | Developer<br>Onsite Contact                                | Responsible Party or<br>Emergency Contact                  | Priority | Sediment<br>Control?                     | Inspection Date                                 | e Lat     | Lon         |
|               |                      | Baker Ranch                                  |                  | Bake           | Parkway          |       | Lake<br>Forest    | CA 92   | 630                 | 142             | 9305314995     | Commercial   | Commercial         | Grading                 | N/A                        |                          | Shea Properties                                |   |                    |                  |  | Gene Spindler<br>(949) 389-7116                            | м        | YES                                      | 10/14/2009<br>1/4/2010<br>4/7/2010              |           |             |
| 2/5/2008      | 47901                |  | 25372            | Arctic Ocean   | Drive            |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Electrical Feed<br>in Trenches<br>Demo Existing            | Commercial         |                         | 2/5/2008                   |                          | Howard Building                                | 3184-K Airway Avenue<br>Costa Mesa, CA 92626                  | (714) 438-2272     |                  | Howard Building<br>(714) 438-2272<br>Jeff Thompson         | Howard Building<br>(714) 438-2272<br>Jeff Thompson         | L        | YES                                      | 9/12/2008                                       | 33.667625 | -117.68738  |
| 5/29/2008     | 48677                | Holiday Inn                                  | 23131            | Lake Center    | Drive            |       | Lake<br>Forest    | CA 92   | 630                 | 1.145           | 6A31C351866    | Commercial &   | Commercial         | Demo &<br>Grading       | 5/22/2008                  | 5/22/2009                | SoCal Hospitality,<br>LLC                      | 12 Buellton<br>Irvine, CA 92602                               | (714) 745-6594     | (714) 242-7311   | Camco Pacific<br>(949) 251-1300                            | Camco Pacific<br>(949) 251-1300                            | М        | YES                                      | FINALED<br>9/23/2009                            | 33.627522 | -117.716815 |
| 6/11/2008     | 48806                | Holiday Inn                                  | 23131            | Lake Center    | Drive            |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | New Hotel (62,499<br>SF)                                   | Commercial         | Footings                | 6/11/2008                  |                          | Camco Pacific<br>Construction<br>Company, Inc. | 17891 Cartwright Road, Suite 100<br>Irvine, CA 92614          | (949) 251-1300     |                  | Camco Pacific<br>Construction Company<br>(949) 251-1300    | Camco Pacific<br>Construction Company<br>(949) 251-1300    |          | YES                                      | 8/14/2008<br>FINALED<br>1/21/2010               | 33 627522 | -117.716815 |
| 7/29/2008     | 49139                | PetSmart                                     | 26532            | Towne Centre   | Drive            |       | Foothill<br>Ranch | CA 92   | 610                 | < 1             | NA             | Revise Sidewalks   | Commercial         |                         | 7/29/2008                  |                          | S.T. Baggett, Inc.                             | 30302 Esperanza<br>R. Santa Margarita, CA 92688               | (949) 466-6272     |                  | S.T. Baggett, Inc.<br>(949) 466-6272                       | S.T. Baggett, Inc.<br>(949) 466-6272                       | L        | YES                                      | FINALED<br>10/23/2008                           | 33.679701 | -117.667586 |
| 9/12/2008     | 49490                | Exxon Mobil                                  | 27252            | Portola        | Parkway          |       | Foothill<br>Ranch | CA 92   | 610                 | < 1             | NA             | New Healy Tank<br>w/ CMV Enclos. &<br>Concrete Pad         | Commercial         | Footings                | 9/12/2008                  |                          | Dresser, Inc.                                  | 10329 Regis Court<br>Rancho Cucamonga, CA 91730               | (888) 606-6464     |                  | Dresser, Inc.<br>(888) 606-6464                            | Dresser, Inc.<br>(888) 606-6464                            | L        | YES                                      | 11/24/2008<br>FINALED<br>8/5/2010               | 33.672858 | -117.654996 |
| 9/30/2008     | 49617                | Comerica Bank                                | 27452            | Portola        | Parkway          |       | Foothill<br>Ranch | CA 92   | 1610                | < 1             | NA.            | Monument Sign  | Commercial         | Footings                | 9/30/2008                  |                          | Ad Impact                                      | 19772 MacArthur Boulevard, #110<br>Irvine, CA 92612           | (949) 476-0015     |                  | Ad Impact<br>(949) 476-0015                                | Ad Impact<br>(949) 476-0015                                |          | YES                                      | 12/31/2008<br>FINALED<br>7/28/2010              | 22 670796 | -117.652009 |
|               |                      | Comorca Bank                                 |                  |                |                  |       | Foothill          |         |                     | -1              | NA.            | Demo Existing<br>Building & Site                           | Commercial         | 1 ootings               |                            |                          | K&G/Foothill II, LLC                           | 250 Brooks Street   |                    |                  | Andy Stavros   | Andy Stavros   |          |  |   |           |             |
| 10/7/2008     | 49656                |  | 71               | Auto Center    | Drive            |       | Ranch             | CA 92   | 610                 | < 1             | NA             | Improvements  Mezzanine                                    | Commercial         |                         | 10/7/2008                  |                          | (Owner)  | Laguna Beach, CA 92651<br>23525 Cavanaugh Road                | (949) 376-1100     |                  | (949) 376-1100<br>Robert Magnano                           | (949) 376-1100<br>Robert Magnano                           | L        | YES                                      | 7/21/2009<br>10/22/2008<br>FINALED              | 33.676247 | -117.661046 |
| 10/21/2008    | 49748                | Schmaze Coatings                             | s 20792          | Canada         | Road             |       | Forest            | CA 92   | 630                 | < 1             | NA             | (1,580 SF)   | Commercial         | Footings                | 10/21/2008                 |                          | Robert Magnano<br>Kindness General             | Lake Forest, CA 92630   | (949) 394-0569     |                  | (949) 394-0569<br>Kindness General                         | (949) 394-0569<br>Kindness General                         | L        | YES                                      | 3/8/2010<br>2/4/2009<br>FINAL ED                | 33.659791 | -117.672798 |
| 12/22/2008    | 50080                | Blair's Towing                               | 26100            | Dimension      | Drive            |       | Forest            | CA 92   | 630                 | < 1             | NA             | (1,096 SF)<br>New Healy Tank                               | Commercial         | Footings                | 12/22/2008                 |                          | Contractors, Inc.                              | Garden Grove, CA 92840  | (714) 636-4542     |                  | (714) 636-4542   | (714) 636-4542   | L        | YES                                      | 8/6/2009<br>1/8/2009                            | 33.663277 | -117.674459 |
| 12/22/2008    | 50085                | Shell Gas                                    | 26721            | Rancho         | Parkway          |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | w/ Steel Enclos. &<br>Crash Post                           | Commercial         | Footings                | 12/22/2008                 |                          | MIT Engineering &<br>Construction, Inc.        | 3720 Oceanic Way, Suite 205<br>Oceanside, CA 92054            | (760) 721-4120     |                  | MIT Eng. & Construct.<br>(760) 721-4120                    | MIT Eng. & Construct.<br>(760) 721-4120                    | L        | YES                                      | 1/22/2009<br>2/4/2009<br>2/23/2009              | 33.672764 | -117.66597  |
| 1/5/2009      | 50122                | Damian Hickman<br>Designs                    | 26080            | Towne Centre   | Drive            |       | Foothill<br>Ranch | CA 92   | 610                 | < 1             | NA             | Mezzanine<br>(336 SF)                                      | Commercial         | Footings                | 1/5/2009                   |                          | G3 Construction &<br>Remodel                   | 8130 La Mesa Boulevard, #10<br>La Mesa, CA 91941              | (619) 328-0877     |                  | G3 Construction<br>(619) 328-0877                          | G3 Construction<br>(619) 328-0877                          | L        | YES<br>NO                                | FINALED<br>7/13/2009                            | 33.68207  | -117.674899 |
| 1/15/2009     | 50195                | Chevron                                      | 23631            | Rockfield      | Boulevard        |       | Lake<br>Forest    | CA 92   | 1630                | < 1             | NA             | Healy Tank<br>w/ Enclosure                                 | Commercial         | Footings                | 1/15/2009                  |                          | Calcraft Corporation                           | 1426 S. Willow Avenue<br>Rialto, CA 92376                     | (909) 879-2910     |                  | Calcraft Corporation<br>(909) 879-2910                     | Calcraft Corporation<br>(909) 879-2910                     | L        | (No Work<br>Activities)                  | No Work<br>Activities                           | 33.630246 | -117.71763  |
| 2/17/2009     | 50312                |  | 25892            | Towne Centre   | Drive            |       | Foothill<br>Ranch | CA 92   | 610                 | < 1             | NA             | Block Wall for<br>Generator Pad                            | Commercial         | Footings                | 2/17/2009                  |                          | Pacific Generator<br>Services                  | 8819 Nightingale Avenue<br>Fountain Valley, CA 92708          | (714) 404-1924     |                  | Richard Vanderhoven<br>Pacific Generator<br>(714) 404-1924 | Richard Vanderhoven<br>Pacific Generator<br>(714) 404-1924 |          | NO<br>(Work Activities<br>Not Initiated) | Work Activities<br>Not Initiated<br>(Extension) | 33.68207  | -117.674899 |
| 2/25/2009     | 50361                |  | 20572            | Lake Forest    | Drive            |       | Lake<br>Forest    | CA 92   | 1630                | < 1             | NA             | EVR Phase II<br>Upgrade                                    | Commercial         | Footings                | 2/25/2009                  |                          | David N. Lopez                                 | P.O. Box 2165<br>Glendora, CA 91740                           | (626) 857-0218     |                  | David Lopez<br>(626) 857-0218                              | David Lopez<br>(626) 857-0218                              | L        | YES                                      | 3/5/2009  | 33.66335  | -117.666561 |
| 3/25/2009     | 50500                | Holiday Inn                                  | 23131            | Lake Center    | Drive            |       | Lake<br>Forest    | CA 92   | 1630                | < 1             | NA             | Connection to<br>Public Sewer                              | Commercial         |                         | 3/25/2009                  |                          | Camco Pacific<br>Construction<br>Company, Inc. | 17891 Cartwright Road, Suite 100<br>Irvine, CA 92614          | (949) 251-1300     |                  | Camco Pacific<br>Construction Company<br>(949) 251-1300    | Camco Pacific<br>Construction Company<br>(949) 251-1300    | L        | YES                                      | 7/21/2009<br>FINALED<br>1/21/2010               | 33.627522 | -117.716815 |
| 4/7/2009      | 50584                | Chick-fil-A                                  | 26792            | Portola        | Parkway          |       | Foothill<br>Ranch | C4 92   | 1610                | < 1             | NA             | Addition (298 SF)<br>to Existing<br>Building               | Commercial         | Footings                | 4/7/2009                   |                          | Clark Contractors,<br>Inc.                     | 26902 Vista Terrace<br>Lake Forest, CA 92630                  | (949) 581-6577     |                  | Clark Contractors, Inc.<br>(949) 581-6577                  | Clark Contractors, Inc.<br>(949) 581-6577                  |          | YES                                      | 4/9/2009<br>FINALED<br>8/13/2009                | 33.679046 | -117.663878 |
| 4/24/2009     | 50732<br>51017       | AT&T   | 24752            |                |                  |       | Lake              | CA 92   | 1000                | < 1             | NA NA          | Cell Site  |                    |                         |                            |                          |  | 11611 Industry Street   | (951) 685-8181     |                  | STC Netcom, Inc.<br>(951) 685-8181                         | STC Netcom, Inc.<br>(951) 685-8181                         |          | YES                                      | 8/13/2009<br>FINALED                            |           | -117.698918 |
| 6/10/2009     |                      |  | 24/52            | Toledo         | Way              |       | Forest            | CA 92   | 1630                |                 | NA             | Site Demolition<br>- Remove Portion                        | Commercial         | Footings                | 6/10/2009                  |                          | STC Netcom, Inc.  Minimum Impact               | Fontana, CA 92337<br>31441SantaMargaritaPkwy.#A105            |                    |                  | Matt Elder<br>MinimumImpact Demo                           | Matt Elder<br>MinimumImpact Demo                           | L        |  | 9/2/2009<br>5/11/2009<br>FINALED                |           |             |
| 5/8/2009      | 50833                | Mercedes Benz                                | 81               | Auto Center    | Drive            |       | Ranch             | CA 92   | 610                 | < 1             | NA             | of Exist. Building<br>EVR Phase II<br>Upgrade w/ CMU       | Commercial         |                         | 5/8/2009                   |                          | Demolition Diamond Point Construction          | R. Santa Margarita, CA 92688<br>1521 Camino Los Robles        | (714) 783-3936     |                  | (714) 783-3936<br>Diamond Point<br>Construction Co.        | (714) 783-3936<br>Diamond Point<br>Construction Co.        | L        | YES                                      | 1/12/2010                                       | 33.675811 | -117.660375 |
| 5/11/2009     | 50851                | Shell Gas                                    | 23652            | Rockfield      | Boulevard        |       | Forest            | CA 92   | 630                 | < 1             | NA             | Block Enclosure  | Commercial         | Footings                | 5/11/2009                  |                          | Company  | Fullerton, CA 92833   | (714) 738-4580     |                  | (714) 738-4580<br>Shannon Kopoian                          | (714) 738-4580<br>Shannon Kopojan                          | L        | YES                                      | 5/18/2009                                       | 33.62896  | -117.716783 |
| 5/12/2009     | 50857                |  | 25301            | Trabuco        | Road             |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Monument Sign  | Commercial         | Footings                | 5/12/2009                  |                          | Promotional Signs,<br>Inc.                     | 20361 Hermana Circle<br>Lake Forest, CA 92630                 | (949) 458-1000     |                  | Promotional Signs<br>(949) 458-1000                        | Promotional Signs<br>(949) 458-1000                        | L        | YES                                      | FINALED<br>10/4/2010<br>6/29/2009               | 33.649913 | -117.689111 |
| 5/18/2009     | 50897                |  | 21682            | Lake Forest    | Drive            |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Monument Sign  | Commercial         | Footings                | 5/18/2009                  |                          | Promotional Signs,<br>Inc.<br>Process          | 20361 Hermana Circle<br>Lake Forest, CA 92630                 | (949) 458-1000     |                  | Promotional Signs<br>(949) 458-1000                        | Promotional Signs<br>(949) 458-1000                        | L        | YES                                      | FINALED<br>8/20/2009                            | 33.647282 | -117.684702 |
| 6/1/2009      | 50960                | Metro PCS                                    | 19432            | Bake           | Parkway          |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Cell Site  | Commercial         | Footings                | 6/1/2009                   |                          | Communication<br>Developers, Inc.              | 3020 W. Harvard Street<br>Santa Ana, CA 92704                 | (714) 427-6370     |                  | Process Comm.<br>(714) 427-6370                            | Process Comm.<br>(714) 427-6370                            | L        | YES                                      | FINALED<br>7/6/2009                             | 33.679894 | -117.655431 |
| 6/2/2009      | 50976                | Mercedes Benz of<br>Foothill Ranch           | f<br>81          | Auto Center    | Drive            |       | Foothill<br>Ranch | CA 92   | 1610                | 8.86            | 930C353944     | Grading  | Commercial         | Grading                 | 6/1/2009                   | 7/1/2010                 | Foothill Ranch<br>Properties                   | 1 Star Drive<br>Laguna Niguel, CA 92677                       | (949) 421-2559     |                  | Lou Drapac<br>(310) 678-8385                               | Lou Drapac<br>(310) 678-8385                               | м        | YES                                      | 6/4/2009<br>1/25/2010<br>2/24/2010              | 33.675811 | -117.660375 |
| 6/11/2009     | 51023                | Mercedes Benz of<br>Foothill Ranch           | f<br>81          | Auto Center    | Drive            |       | Foothill<br>Ranch | CA 92   | 1610                | < 1             | NA.            | New Addition to<br>Bldg. (4,959 SF) &<br>New Car Wash      | Commercial         | Footings                | 6/11/2009                  |                          | Patterson Builders                             | 2401 N. Palm Drive<br>Signal Hill, CA 90755                   | (562) 326-5400     |                  | Patterson Builders<br>(562) 326-5400                       | Patterson Builders<br>(562) 326-5400                       |          | YES                                      | 6/15/2009<br>FINALED<br>1/12/2010               | 33.675811 | -117.660375 |
|               |                      | Mercedes Benz of                             | f                |                |                  |       | Foothill          |         |                     |                 | NΔ             | Install 23 Inground  | i                  | 1 ootings               |                            |                          | Pacific Lift &<br>Equipment                    | 61 W. Mountain Street Pasadena CA 91103                       |                    |                  | Bob Porter<br>Pacific Lift&Equipment<br>(626) 255-6927     | Bob Porter Pacific Lift&Equipment (626) 255-6927           |          |  | 11/24/2009<br>FINALED                           |           |             |
| 6/18/2009     | 51075                |  | 81               | Auto Center    | Drive            |       | Foothill          | CA 92   | 610                 | < 1             | 103            |  | Commercial         |                         | 6/18/2009                  |                          | Company, Inc. Metrocell                        | 8104 Freestone Avenue   | (626) 797-4100     |                  | John Galante<br>Metrocell Construction                     | John Galante<br>Metrocell Construction                     | L        | YES                                      | 1/12/2010<br>12/22/2009<br>FINALED              | 33.675811 | -117.660375 |
| 6/19/2009     | 51082                | Verizon Wireless<br>Lake Forest<br>Gateway - | 25931            | Towne Centre   | Drive            |       | Ranch             | CA 92   | 610                 | < 1             | NA             | Cell Site<br>Exterior Remodel<br>& Site                    | Commercial         | Footings                | 6/19/2009                  |                          | Construction, Inc.                             | Santa Fe Springs, CA 90670<br>17681 Mitchell North, Suite 100 | (714) 529-1123     |                  | (562) 587-0693   | (562) 587-0693<br>SD Deacon Corp.                          | L        | YES                                      | 12/22/2009<br>7/22/2009<br>FINAL ED             | 33.68207  | -117.674899 |
| 7/2/2009      | 51156                | Building #3<br>Lake Forest                   | 23600            | Rockfield      | Boulevard        |       | Forest            | CA 92   | 630                 | < 1             | NA             | Improvements   | Commercial         |                         | 7/2/2009                   |                          | Corporation                                    | Irvine, CA 92614  | (949) 222-9060     |                  | (949) 222-9060   | (949) 222-9060   | L        | YES                                      | 11/25/2009                                      | 33.63049  | -117.718232 |
| 7/2/2009      | 51157                | Gateway -<br>Building #5                     | 23642            | Rockfield      | Boulevard        |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Exterior Remodel   | Commercial         |                         | 7/2/2009                   |                          | SD Deacon<br>Corporation                       | 17681 Mitchell North, Suite 100<br>Irvine, CA 92614           | (949) 222-9060     |                  | SD Deacon Corp.<br>(949) 222-9060                          | SD Deacon Corp.<br>(949) 222-9060                          | L        | YES                                      | 9/23/2009<br>7/21/2010                          | 33.629382 | -117.717237 |
| 7/15/2009     | 51232                |  | 19232            | Alton          | Parkway          |       | Foothill<br>Ranch | CA 92   | 610                 | < 1             | NA             | Upgrade of EVR &<br>Dispensers                             | Commercial         | Footings                | 7/15/2009                  |                          | Jonathan Dibiasi<br>(Owner)                    | 19232 Alton Parkway<br>Foothill Ranch, CA 92610               | (714) 768-3811     |                  | Jonathan Dibiasi<br>(714) 768-3811                         | Jonathan Dibiasi<br>(714) 768-3811                         | L        | YES                                      | FINALED<br>7/29/2010<br>7/21/2009               | 33.682468 | -117.66746  |
| 7/20/2009     | 51273                | Holiday Inn                                  | 23131            | Lake Center    | Drive            |       | Lake<br>Forest    | CA 92   | 630                 | < 1             | NA             | Pool / Spa   | Commercial         | Steel<br>Reinforcements | 7/20/2009                  |                          | Arroyo Pools, Inc.                             | 720 W. Katella Avenue<br>Orange, CA 92867                     | (714) 283-3035     |                  | Lester Townsend<br>Arroyo Pools, Inc.<br>(714) 283-3035    | Lester Townsend<br>Arroyo Pools, Inc.<br>(714) 283-3035    | L        | YES                                      | 7/21/2009<br>FINALED<br>1/21/2010               | 33.627522 | -117.716815 |
| 8/4/2009      | 51347                | Mercedes Benz of<br>Foothill Ranch           | f 81             | Auto Center    | Drive            |       | Foothill<br>Ranch | CA 92   | 1610                | < 1             | NA.            | Install Oil Storage<br>Tanks, Shelving &<br>Preman.CarWash |                    | Footings                | 8/4/2009                   |                          | Pacific Lift &<br>Equipment<br>Company, Inc.   | 61 W. Mountain Street<br>Pasadena, CA 91103                   | (626) 797-4100     |                  | Bob Porter<br>Pacific Lift&Equipment<br>(626) 797-4100     | Bob Porter<br>Pacific Lift&Equipment<br>(626) 797-4100     |          | YES                                      | 11/24/2009                                      |           | -117.660375 |
|               |                      | , oouni Ranch                                |                  |                |                  |       | Lake              | OR 92   |                     |                 |                | Repair   | Johnnerdal         | i ootiiigs              |                            |                          | So Cal Jetting &                               | 38368 Via Calorin   |                    |                  | Dennis Carver<br>So Cal Jetting&Plumb.                     | Dennis Carver<br>So Cal Jetting&Plumb.                     |          | NO<br>(No Work                           | EXPIRED   |           |             |
| 8/5/2009      | 51359                |  | 24301            | Muirlands      | Boulevard        |       | Forest            | CA 92   | 630                 | < 1             | NA             | Sewer Lateral  | Commercial         |                         | 8/5/2009                   |                          | Plumbing                                       | Murrieta, CA 92562<br>1384 E. Fifth Street                    | (800) 377-9400     |                  | (951) 538-4245<br>Gary Rezac<br>Swain Sign, Inc.           | (951) 538-4245<br>Gary Rezac<br>Swain Sign, Inc.           | L        | Activities)                              | 6/9/2010  | 33.629352 | -117.706112 |
| 8/11/2009     | 51388                | Holiday Inn                                  | 23131            | Lake Center    | Drive            | Ш     | Forest            | CA 92   | 630                 | < 1             | NA             | Monument Sign  | Commercial         | Footings                | 8/11/2009                  | 1                        | Swain Sign, Inc.                               | Ontario, CA 91764   | (909) 460-2530     |                  | (909) 460-2530   | (909) 460-2530   | L        | YES                                      | 9/22/2009                                       | 33.627522 | -117.716815 |

Page 1 of 2 11/10/2010

#### NPDES Construction Facilities Inventory - Commercial Projects SAN DIEGO CREEK / NEWPORT BAY WATERSHED (SARWQCB) Year 2009-2010

|               |                                  |                                    |                  |                |                  | 1 1   |                   |         |                     |                          |                |   |                    |                        |                            |                          |                                       |  |                    |                  |   |   | Ins        | pected for                      |                                |           |             |
|---------------|----------------------------------|------------------------------------|------------------|----------------|------------------|-------|-------------------|---------|---------------------|--------------------------|----------------|---|--------------------|------------------------|----------------------------|--------------------------|---------------------------------------|--|--------------------|------------------|---|---|------------|---------------------------------|--------------------------------|-----------|-------------|
| Issue<br>Date | Grading/<br>Building<br>Permit # | Project<br>Name                    | Street<br>Number | Street<br>Name | Street<br>Suffix | Suite | City              | State 2 | Tract<br>Zip Number | Total<br>Site<br>Acreage | WDID<br>Number | Description of Project                  | Type of<br>Project | Source<br>Activities   | Construction<br>Start Date | Construction<br>End Date | Developer<br>Name                     | Developer<br>Address                             | Developer<br>Phone | Developer<br>Fax | Developer<br>Onsite Contact               | Responsible Party or<br>Emergency Contact | s          | osion and<br>sediment           |                                | 1         |             |
| Date          | Fermit #                         | Name                               | Number           | Name           | Suilix           | Suite | City              | State 2 | Zip Number          | Acreage                  | Number         | Install Phase II                        | Project            | Activities             | Start Date                 | End Date                 |                                       |  | Filone             | ГdХ              | Charles E. Thomas                         | Charles E. Thomas                         | Priority ( | Control?                        | 9/2/2009                       | Lat       | Lon         |
| 8/25/2009     | 51464                            |                                    | 20731            | Lake Forest    | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | EVR<br>Carbon Canister                  | Commercial         | Footings               | 8/25/2009                  |                          | Charles E. Thomas<br>Company, Inc.    | 13701 S. Alma Avenue<br>Gardena, CA 90249        | (310) 323-6730     |                  | Company, Inc.<br>(310) 323-6730           | Company, Inc.<br>(310) 323-6730           |            | YES                             | FINALED<br>9/25/2009           | 33 661072 | -117 668658 |
| 0.20,200      |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | (11) Pilasters for<br>Swimming Pool     |                    |                        | 0.20.200                   |                          | Camco Pacific<br>Construction         | 17891 Cartwright Road, Suite 100                 | (0.0) 020 0.00     |                  | Jeff Thompson<br>Camco Pacific Const.     | Jeff Thompson<br>Camco Pacific Const.     |            |                                 | 9/15/2009<br>FINALED           |           |             |
| 8/26/2009     | 51476                            | Holiday Inn                        | 23131            | Lake Center    | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Enclosure                               | Commercial         | Footings               | 8/26/2009                  |                          | Company, Inc.                         | Irvine, CA 92614                                 | (949) 251-1300     |                  | (949) 251-1300                            | (949) 251-1300                            | L          | YES                             | 1/21/2010                      | 33.627522 | -117.716815 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | Relocate Pool,<br>Pilast.,Hardscape     |                    | Steel<br>Reinforcement | s                          |                          | Camco Pacific<br>Construction         | 17891 Cartwright Road, Suite 100                 |                    |                  | Jeff Thompson<br>Camco Pacific Const.     | Jeff Thompson<br>Camco Pacific Const.     |            |                                 | 9/15/2009                      |           |             |
| 8/27/2009     | 51483                            | Holiday Inn                        | 23131            | Lake Center    | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | & Landscape<br>Cell Site -              | Commercial         | & Footings             | 8/27/2009                  |                          | Company, Inc.                         | Irvine, CA 92614                                 | (949) 251-1300     |                  | (949) 251-1300                            | (949) 251-1300                            | L          | YES                             | 1/21/2010                      | 33.627522 | -117.716815 |
| 9/2/2009      | 51503                            |                                    | 22511 1/2        | Aspan          | Street           |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Antennas &<br>Equipment Cabs.           | Commercial         | Footings               | 9/2/2009                   |                          | Solex Contracting,<br>Inc.            | 42146 Remington Avenue<br>Temecula, CA 92590     | (951) 308-1706     |                  | Solex Contracting, Inc.<br>(951) 308-1706 | Solex Contracting, Inc.<br>(951) 308-1706 |            | YES                             | FINALED<br>10/26/2009          | 22 625052 | -117.713863 |
| 8/2/2008      | 31303                            |                                    | 22311 1/2        | Лэран          | Olleet           |       |                   | UN 32   | 2030                |                          | INO            | Equipment Gabs.                         | Commercial         | i ootiiiga             | 8/2/2008                   |                          |                                       |  | (851) 300-1700     |                  |   |   | -          | ILO                             | 10/6/2009                      | 33.033033 | -117.713003 |
| 9/25/2009     | 51660                            |                                    | 21701            | Lake Forest    | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Sewer Repair                            | Commercial         |                        | 9/25/2009                  |                          | Lozano Plumbing<br>Services, Inc.     | P.O. Box 53137<br>Riverside, CA 92517            | (951) 683-4840     |                  | Lozano Plumbing<br>(951) 683-4840         | Lozano Plumbing<br>(951) 683-4840         | L          | YES                             | FINALED<br>10/7/2009           | 33.647436 | -117.68541  |
| 9/29/2009     | 51683                            |                                    | 20792            | Canada         | Road             |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Monument Sign                           | Commercial         | Footings               | 9/29/2009                  |                          | Matt Black, LLC<br>(Owner)            | P.O. Box 50729<br>Henderson, NV 89016            | (949) 583-1448     |                  | Matt Black, LLC<br>(949) 583-1448         | Matt Black, LLC<br>(949) 583-1448         | L          | YES                             | 12/2/2009                      | 33.659791 | -117.672798 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | Repair Existing                         |                    |                        |                            |                          | Drainex Rooter &                      | 840 S. Kenmore Street                            |                    |                  | Drainex Rooter<br>& Plumbing Company      | Drainex Rooter<br>& Plumbing Company      |            |                                 | 10/19/2009<br>FINALED          |           |             |
| 10/15/2009    | 51777                            | Dragon Buffet                      | 24416            | Muirlands      | Boulevard        |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Grease Trap                             | Commercial         |                        | 10/15/2009                 |                          | Plumbing Company                      | Anaheim, CA 92804                                | (714) 995-2996     |                  | (714) 995-2996                            | (714) 995-2996                            | L          | YES                             | 10/19/2009                     | 33.627802 | -117.703453 |
|               |                                  |                                    |                  |                |                  |       | Foothill          |         |                     |                          |                | Remove Kiosk                            |                    |                        |                            |                          | One Source Security                   | 2040 Cecelia Circle                              |                    |                  | One Source Security 8<br>Sound, Inc.      | One Source Security &<br>Sound, Inc.      |            | NO<br>No Work                   | No Work                        |           |             |
| 10/19/2009    | 51787                            |                                    | 26612            | Towne Centre   | Drive            |       | Ranch             | CA 92   | 2610                | < 1                      | NA             | with ATM                                | Commercial         |                        | 10/19/2009                 |                          | & Sound, Inc.                         | Corona, CA 92880                                 | (951) 549-9870     |                  | (951) 549-9870<br>Tish Scialampo          | (951) 549-9870<br>Tish Scialampo          | L A        | Activities)                     | Activities<br>11/12/2009       | 33.677395 | -117.666283 |
| 11/3/2009     | 51900                            | Mercedes Benz of<br>Footbill Ranch | 81               | Auto Center    | Drive            |       | Foothill<br>Ranch | CA 92   | 2610                | < 1                      | NA             | Monument Sign<br>& Pole Signs           | Commercial         | Footings               | 11/3/2009                  |                          | Absolute Sign. Inc.                   | 4652 Katella Avenue Los<br>Alamitos CA 90720     | (562) 592-5838     |                  | Absolute Sign, Inc.<br>(562) 592-5838     | Absolute Sign, Inc.<br>(562) 592-5838     |            | YES                             | FINALED<br>1/5/2010            | 33 675811 | -117 660375 |
| 11/0/2005     | 01000                            | Mercedes Benz of                   | 0.               | Auto Ocinici   | Dille            |       | Footbill          | 0,1 01  | 2010                |                          |                | -                                       | Commercial         | 1 ootings              | 11/0/2000                  |                          | Pacific Lift &                        | 61 W. Mountain Street                            | (002) 002 0000     |                  | Bob Porter Pacific Lift&Equipment         | Bob Porter<br>Pacific Lift&Equipment      | -          | 120                             | 11/24/2009<br>FINALED          | 00.070011 | 111.000070  |
| 11/16/2009    | 51995                            | Foothill Ranch                     | 81               | Auto Center    | Drive            |       | Ranch             | CA 92   | 2610                | < 1                      | NA             | Install 1 Alignment<br>Lift             | Commercial         |                        | 11/16/2009                 |                          | Equipment<br>Company, Inc.            | Pasadena, CA 91103                               | (626) 797-4100     |                  | (626) 797-4100                            | (626) 797-4100                            | L          | YES                             | 1/12/2010                      | 33.675811 | -117.660375 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | Install Generator<br>(30 KW) with 499   |                    |                        |                            |                          |                                       | 9836 Argyle Drive                                |                    |                  | Matt Vigil<br>Milestone Wireless          | Matt Vigil<br>Milestone Wireless          |            |                                 | 9/20/2010                      |           |             |
| 11/19/2009    | 52047                            |                                    | 25421            | Trabuco        | Road             |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Gal. PropaneTank                        | Commercial         | Footings               | 11/19/2009                 |                          | Milestone Wireless Matt Black 11 C    | Huntington Beach, CA 92646<br>20792 Canada Road  | (562) 889-7925     |                  | (562) 889-7925<br>Matt Black LLC          | (562) 889-7925<br>Matt Black 11 C         | L          | YES                             | 10/5/2010                      | 33.648325 | -117.686574 |
| 11/24/2009    | 52070                            |                                    | 20792            | Canada         | Road             |       | Forest            | CA 92   | 2630                | < 1                      | NA             | (300 SF)                                | Commercial         | Footings               | 11/24/2009                 |                          | (Owner)                               | Lake Forest, CA 92630                            | (949) 583-1448     |                  | (949) 583-1448<br>Kelvin Le               | (949) 583-1448<br>Kelvin Le               | L          | YES                             | 12/1/2009                      | 33.659791 | -117.672798 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | Existing Canopy &                       |                    |                        |                            |                          | Western States                        | 4887 E. La Palma Ave., #707                      |                    |                  | Western States Const.                     | Western States Const.                     |            |                                 | 2/3/2010                       |           |             |
| 11/30/2009    | 52103                            |                                    | 22942            | Ridge Route    | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | U.S.T.<br>Installation of               | Commercial         |                        | 11/30/2009                 |                          | Construction, Inc.                    | Anaheim, CA 92807                                | (714) 695-9300     |                  | (714) 487-7173<br>West Coast Ind.         | (714) 487-7173<br>West Coast Ind.         | L          | YES                             | 3/8/2010                       | 33.629746 | -117.703286 |
| 2/2/2010      | 52452                            | LCOA                               | 20322            | Windrow        | Drive            |       | Lake<br>Forest    | CA 02   | 2620                | -1                       | NΔ             | Cooling Tower<br>System                 | Commercial         | Footings               | 2/2/2010                   |                          | West Coast Ind.<br>Services, Inc.     | 5959 Republic Street<br>Riverside, CA 92504      | (951) 324-8081     |                  | Services, Inc.<br>(951) 324-8081          | Services, Inc.<br>(951) 324-8081          |            | YES                             | 2/23/2010                      | 33.667777 | -117 650221 |
| 2/2/2010      | 32432                            | LCOA                               | 20022            | willdlow       | Dilve            |       | Lake              | UN 32   | 2030                | ` '                      | INO            | Prefab. Walk-in<br>Cooler / Freezer     | Commercial         | i ootiiiga             | 2/2/2010                   |                          | Aire Rite AC &                        | 15122 Bolsa Chica Street                         | (851) 324-0001     |                  | David Langston<br>Aire Rite AC & Refrig.  | David Langston                            |            | ILS                             | 3/29/2010<br>FINALED           | 33.00/1// | -117.039231 |
| 2/8/2010      | 52482                            |                                    | 25               | Empire         | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | (3,200 SF)                              | Commercial         |                        | 2/8/2010                   |                          | Refrigeration, Inc.                   | Huntington Beach, CA 92649                       | (714) 895-2338     |                  | (714) 895-2338 x)113                      | (714) 895-2338 x)113                      | L          | YES                             | 4/29/2010                      | 33.66265  | -117.695743 |
|               |                                  | Skewers                            |                  |                |                  |       | Lake              |         |                     |                          |                |   |                    |                        |                            |                          | Magee Enterprises                     | 1201 Huntridge Road                              |                    |                  | Magee Enterprises                         | Magee Enterprises                         |            |                                 | 3/26/2010<br>FINALED           |           |             |
| 2/18/2010     | 52558                            | Restaurant                         | 24531            | Trabuco        | Road             |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Grease Interceptor                      | Commercial         |                        | 2/18/2010                  |                          | Contractors                           | Santa Ana, CA 92705                              | (714) 505-1811     |                  | (714) 505-1811<br>Brennan Chavez          | (714) 505-1811<br>Brennan Chavez          | L          | YES<br>NO                       | 4/13/2010<br>Work Activities   | 33.654901 | -117.701989 |
| 3/9/2010      | 1133                             | T-Mobile                           | 20696            | Danana.        | Lane             |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Cell Site                               | Commercial         |                        | 3/9/2010                   |                          | T-Mobile<br>(Owner)                   | 3 MacArthur Place, #1100<br>Santa Ana, CA 92707  | (714) 204-2018     |                  | T-Mobile<br>(714) 204-2018                | T-Mobile<br>(714) 204-2018                |            | ork Activities<br>of Initiated) | Not Initiated<br>(Extension)   | 33.66187  | -117.66275  |
| 3/9/2010      | 1133                             | 1-MODIIE                           | 20090            | Regency        | Lane             |       |                   | CA 92   | 2030                | < 1                      | INA            | Sewer & Waste for                       | Commercial         |                        | 3/9/2010                   |                          | Brownco                               |  | (714) 204-2016     |                  | Mike Campbell                             | Mike Campbell                             | L NO       | ot minateu)                     | 3/30/2010                      | 33.00107  | -117.00275  |
| 3/22/2010     | 1225                             |                                    | 25392            | Commercentre   | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Tenant<br>Improvement                   | Commercial         |                        | 3/22/2010                  |                          | Construction<br>Company, Inc.         | 1000 E. Katella Avenue<br>Anaheim, CA 92805      | (714) 935-9600     |                  | Brownco Construction<br>(714) 935-9600    | Brownco Construction<br>(714) 935-9600    | L          | YES                             | FINALED<br>9/2/2010            | 33.66564  | -117.686735 |
|               |                                  |                                    |                  | Spectrum       |                  |       | Lake              |         |                     |                          |                | Install New<br>(60 KVA)                 |                    |                        |                            |                          |                                       | 26804 Vista Terrace Lake                         |                    |                  | Sandy Boyd<br>Current Electric            | Sandy Boyd<br>Current Electric            |            |                                 | 5/21/2010<br>FINALED           |           |             |
| 3/29/2010     | 1250                             |                                    | 12               | Pointe         | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Generator                               | Commercial         | Footings               | 3/29/2010                  |                          | Current Electric                      | Forest, CA 92630                                 | (949) 588-3777     |                  | (949) 588-3777<br>Inland Valley           | (949) 588-3777<br>Inland Valley           | L          | YES<br>NO                       | 5/21/2010<br>Work Activities   | 33.66079  | -117.692979 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                |   |                    |                        |                            |                          | Inland Valley                         | 18382 Slover Avenue                              |                    |                  | Construction (909)                        | Construction (909)                        |            | rk Activities                   | Not Initiated                  |           |             |
| 4/15/2010     | 1360                             | Sprint                             | 26005            | Dimension      | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Cell Site                               | Commercial         |                        | 4/15/2010                  |                          | Construction                          | Bloomington, CA 92316                            | (909) 875-2112     |                  | 875-2112<br>Inland Valley                 | 875-2112<br>Inland Valley                 |            | nt Initiated)                   | (Extension)<br>Work Activities | 33.664529 | -117.674871 |
| 4/26/2010     | 1399                             | Sprint                             | 25791            | Commercentre   | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Cell Site                               | Commercial         |                        | 4/26/2010                  |                          | Inland Valley<br>Construction         | 18382 Slover Avenue<br>Bloomington, CA 92316     | (909) 875-2112     |                  | Construction (909)<br>875-2112            | Construction (909)<br>875-2112            |            | ork Activities<br>of Initiated) | Not Initiated<br>(Extension)   | 33.664578 | -117 676217 |
| 4/20/2010     | 1000                             | Орин                               | 20/01            | Commercente    | Divid            |       | Lake              | 0,1     | 2000                |                          | 14.            | OUII ONO                                | Commorcial         |                        | 4/20/2010                  |                          | Inland Valley                         | 18382 Slover Avenue                              | (000) 010 2112     |                  | Inland Valley<br>Construction (909)       | Inland Valley                             |            | NO<br>No Work                   | No Work                        | 00.004010 | 111.070211  |
| 5/17/2010     | 1486                             | Clearwire                          | 22541            | Aspan          | Street           |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Cell Site                               | Commercial         |                        | 5/17/2010                  |                          | Construction                          | Bloomington, CA 92316                            | (909) 875-2112     |                  | 875-2112                                  | 875-2112                                  | L A        | Activities)                     | Activities                     | 33.634602 | -117.714506 |
|               |                                  |                                    |                  |                |                  |       | Foothill          |         |                     |                          |                | Foundation - Tuff                       |                    |                        |                            |                          | Ted Sage                              | 19811 Pauling                                    |                    |                  | Ted Sage                                  | Ted Sage                                  |            |                                 | 6/9/2010<br>FINALED            |           |             |
| 5/24/2010     | 1579                             |                                    | 19811            | Pauling        |                  |       | Ranch             | CA 92   | 2610                | < 1                      | NA             | Shed (12 x 20)                          | Commercial         | Footings               | 5/24/2010                  |                          | (Owner)                               | Foothill Ranch, CA 92610                         | (949) 581-4406     |                  | (949) 581-4406<br>Kelvin Le               | (949) 581-4406<br>Kelvin Le               | L          | YES                             | 6/14/2010                      | 33.674728 | -117.653357 |
| 5/20/2010     | 1647                             |                                    | 22942            | Ridge Route    | Drive            |       | Lake<br>Forest    | CA 92   | 2620                | < 1                      | NA             | Precise Grading<br>(.77 Acre)           | Commercial         | Grading                | 5/20/2010                  |                          | Western States<br>Engineering         | 4887 E. La Palma Ave., #707<br>Anaheim, CA 92807 | (714) 693-9300     |                  | Western States Eng.<br>(714) 693-9300     | Western States Eng.<br>(714) 693-9300     |            | YES                             | 5/25/2010<br>6/8/2010          | 33.629746 | -117.703286 |
| 3/20/2010     | 1047                             |                                    | 22342            | rriage rroate  | Dilve            |       |                   | UN 32   | 2030                |                          | INO            | Demo Roof                               | Commercial         | Glauling               | 3/20/2010                  |                          | Lake Forest                           |  | (714) 083-8300     |                  | Lake Forest Community                     | Lake Forest Community                     |            | NO                              |                                | 33.023740 | -117.703200 |
| 6/1/2010      | 1698                             |                                    | 22921            | Ridge Route    | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | & Canopy<br>(1,000 SF)                  | Commercial         |                        | 6/1/2010                   |                          | Community Assn.<br>(Owner)            | 22921 Ridge Route Drive<br>Lake Forest, CA 92630 | (949) 837-6100     |                  | Assn. (949) 837-<br>6100                  | Assn. (949) 837-<br>6100                  |            | No Work<br>Activities)          | No Work<br>Activities          | 33.630195 | -117.70334  |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | New Rack<br>SupportCatwalk &            |                    |                        |                            |                          | Faithco Building                      | 26582 Shane Drive                                |                    |                  | Randy Kirchner<br>Faithco Building Corp.  | Randy Kirchner<br>Faithco Building Corp.  |            |                                 | 7/1/2010<br>FINALED            |           |             |
| 6/24/2010     | 1707                             | Intertek                           | 25791            | Commercentre   | Drive            |       | Forest            | CA 92   | 2630                | < 1                      | NA             | Platform (877 SF)<br>New Commercial     | Commercial         | Footings               | 6/24/2010                  |                          | Corporation                           | Lake Forest, CA 92630                            | (949) 305-2120     |                  | (949) 305-2120<br>Kelvin Le               | (949) 305-2120<br>Kelvin Le               | L          | YES                             | 8/5/2010                       | 33.664578 | -117.676217 |
|               |                                  |                                    |                  |                |                  |       | Lake              |         |                     |                          |                | Retail Building                         |                    |                        |                            |                          | Western States                        | 4887 E. La Palma Ave., #707                      |                    |                  | Western States Eng.                       | Western States Eng.                       |            |                                 |                                |           |             |
| 6/18/2010     | 1770                             |                                    | 22942            | Ridge Route    | Drive            | +     | Forest            | CA 92   | 2630                | < 1                      | NA             | (5,395 SF)                              | Commercial         | Footings               | 6/18/2010                  |                          | Engineering                           | Anaheim, CA 92807                                | (714) 693-9300     |                  | (714) 693-9300<br>Hans Wett               | (714) 693-9300<br>Hans Wett               | L          | YES                             | 7/2/2010                       | 33.629746 | -117.703286 |
| 6/14/2010     | 1777                             | Karem Aircraft                     | 1                | Capital        | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | < 1                      | NA             | Dust Collector Pad<br>(Foundation Only) | Commercial         | Footings               | 6/14/2010                  |                          | Kindness General<br>Contractors, Inc. | 12891 Nelson Street<br>Garden Grove, CA 92840    | (714) 636-4542     |                  | Kindness Gen.Cont.<br>(714) 636-4542      | Kindness Gen.Cont.<br>(714) 636-4542      | L          | YES                             | 6/16/2010                      | 33.66208  | -117.696651 |
|               |                                  |                                    |                  |                |                  | H     | Lake              |         |                     |                          |                | New Commercial<br>Retail Building       |                    |                        | 5                          |                          | Western States                        | 4887 F. La Palma Ave. #707                       | ,                  |                  | Kelvin Le<br>Western States Eng           | Kelvin Le<br>Western States Eng           |            |                                 |                                |           |             |
| 6/18/2010     | 1784                             |                                    | 24381            | Muirlands      | Boulevard        |       | Forest            | CA 92   | 2630                | < 1                      | NA             | (3,005 SF)                              | Commercial         | Footings               | 6/18/2010                  |                          | Engineering                           | 4887 E. La Palma Ave., #707<br>Anaheim, CA 92807 | (714) 693-9300     |                  | (714) 693-9300                            | (714) 693-9300                            | L          | YES                             | 7/2/2010                       | 33.628893 | -117.705347 |
|               |                                  |                                    |                  |                |                  |       | Foothill          |         |                     |                          |                | Generator<br>Enclosure (408             |                    |                        |                            |                          |                                       | 1203 W. Shelly Court                             |                    |                  | George J. Hanna<br>Hanna Construction     | George J. Hanna<br>Hanna Construction     |            |                                 | 7/7/2010<br>FINALED            |           |             |
| 6/24/2010     | 1875                             |                                    | 19650            | Pauling        |                  | +     | Ranch             | CA 92   | 2610                | < 1                      | NA             | SF)                                     | Commercial         | Footings               | 6/24/2010                  |                          | Hanna Construction                    | Orange, CA 92868                                 | (714) 633-8200     |                  | (714) 633-8200<br>Carrillo Disposal       | (714) 633-8200<br>Carrillo Disposal       | L          | YES                             | 8/13/2010                      | 33.675865 | -117.650432 |
| l             | 1908                             | America's Best<br>Value Inn        | 23150            | Lake Center    | Drive            |       | Lake<br>Forest    | CA 92   | 2630                | <1                       | NA             | Demo 3 Buildings<br>(44,361 SF)         | Commercial         |                        | 6/30/2010                  |                          | Carrillo Disposal<br>Company, Inc.    | 1448 N. Red Gum Street, #C<br>Anaheim, CA 92806  | (714) 392-5040     |                  | Company, Inc.<br>(714) 392-5040           | Company, Inc.<br>(714) 392-5040           |            | YES                             | 7/6/2010                       | 33 627200 | -117 717045 |
| 6/30/2010     |                                  |                                    |                  |                |                  | 1 1   | . 01000           | UA 94   |                     |                          |                |   |                    |                        |                            |                          |                                       |  |                    |                  |   |   |            |                                 |                                |           | 117.717043  |

Page 2 of 2 11/10/2010

#### NPDES Construction Facilities Inventory - Residential Projects SAN DIEGO CREEK / NEWPORT BAY WATERSHED (SARWQCB) Year 2009-2010

|               |                |         |        |              |        |          |                    |           |       |               |        |   |                    |                         |              |                          | I                                       |   |   | 1         | I   | I  |          | Inspected for        | 1                  |           |             |
|---------------|----------------|---------|--------|--------------|--------|----------|--------------------|-----------|-------|---------------|--------|---|--------------------|-------------------------|--------------|--------------------------|---|---|---|-----------|---|--|----------|----------------------|--------------------|-----------|-------------|
| leave         | Duitding       | Project | Street | Street       | Street |          |                    |           | Tract | Total<br>Site | WDID   | Description   | Time of            | Caaa                    | Construction | Canatanatian             | Developer                               | Davidanas   | Davelanes                               | Developer | Developer                                 | Responsible Party or                     |          | Erosion and          |                    |           |             |
| Issue<br>Date | Permit #       | Name    | Number | Name         | Street | Suite    | City               | State Zip |       | Acreage       | Number | of Project  | Type of<br>Project | Source<br>Activities    | Start Date   | Construction<br>End Date | Name Name                               | Address   | Developer<br>Phone                      | Fax       | Onsite Contact                            | Emergency Contact                        | Priority | Sediment<br>Control? | Inspection<br>Date | Lat       | Lon         |
|               |                |         |        |              |        |          | Lako               |           |       |               |        |   |                    |                         |              |                          | Down Company                            | 3233 Grand Avenue, #N276                                  |   |           | Kelly Down<br>Down Co. Construction       | Kelly Down<br>Down Co. Construction      |          |                      |                    |           |             |
| 7/13/2009     | 51206          |         | 22482  | Lake Forest  | Lane   |          | Forest             | CA 9263   | 0     | < 1           | NA     | Room Addition (96 SF)                               | Residential        | Footings                | 7/13/2009    |                          | Construction, Inc.                      | Chino Hills, CA 91709                                     | (949) 307-3050                          | o         | (949) 307-3050                            | (949) 307-3050                           | L        | YES                  | 7/31/2009          | 33.635906 | -117.707201 |
| 7/20/2009     | 51254<br>51381 |         | 25     | Blazewood    |        |          | Foothill<br>Ranch  | CA 9261   | 0     | < 1           | NA     | Room Additions (445 SF)                             | Residential        | Footings                | 7/20/2009    |                          | Chi Thanh Dang<br>(Homeowner)           | 25 Blazewood<br>Foothill Ranch, CA 92610                  | (949) 305-8728                          | 3         | Chi Thanh Dang<br>(949) 305-8728          | Chi Thanh Dang<br>(949) 305-8728         | L        | YES                  | 8/14/2009          | 33.685593 | -117.668301 |
| 7/20/2009     | 51256          |         | 21805  | Ticonderoga  | Lane   |          | Lake<br>Forest     | CA 9263   |       | < 1           | NA     | Room Additions (220 SF) &<br>Patio Cover & Balcony  | Residential        | Footings                | 7/20/2009    |                          | Jennison Mulvaney<br>(Homeowner)        | 21805 Ticonderoga Lane<br>Lake Forest, CA 92630           | (949) 933-0562                          |           | Jennison Mulvaney<br>(949) 933-0562       | Jennison Mulvaney<br>(949) 933-0562      |          | YES                  | 8/12/2009          | 33.6459   | -117.703358 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        |   |                    |                         |              |                          | Andrew R. Gizara                        | 24471 Corta Cresta Drive                                  |   | 2         | Andrew R. Gizara                          | Andrew R. Gizara                         | L        |                      |                    |           |             |
| 7/21/2009     | 51279          |         | 24471  | Corta Cresta | Drive  |          | Forest<br>Foothill | CA 9263   | 0     | < 1           | NA     | Room Additions (183 SF)                             | Residential        | Footings                | 7/21/2009    |                          | (Homeowner)<br>Berg Family              | Lake Forest, CA 92630<br>11 San Angelo                    | (949) 457-0751                          | 1         | (949) 457-0751<br>Berg Family             | (949) 457-0751<br>Berg Family            | L        | YES                  | 7/28/2009          | 33.627845 | -117.702078 |
| 7/28/2009     | 51310          |         | 11     | San Angelo   |        |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Room Addition (91 SF)<br>Retaining Wall (32 LF)     | Residential        | Footings                | 7/28/2009    |                          | (Homeowner)<br>Mark Pappas              | Foothill Ranch, CA 92610<br>43 Montecilo                  | (949) 455-1374                          | 1         | (949) 455-1374<br>Mark Pappas             | (949) 455-1374<br>Mark Pappas            | L        | YES                  | 9/8/2009           | 33.690757 | -117.669954 |
| 7/30/2009     | 51329          |         | 43     | Montecilo    |        |          | Ranch              | CA 9261   | 0     | < 1           | NA     | & Patio Covers (354 SF)                             | Residential        | Footings                | 7/30/2009    |                          | (Homeowner)                             | Foothill Ranch, CA 92610                                  | (949) 702-1167                          | 7         | (949) 702-1167                            | (949) 702-1167                           | L        | YES                  | 8/11/2009          | 33.689877 | -117.669965 |
| 7/30/2009     | 51334          |         | 24176  | Jagger       | Street |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Demo Spa  | Residential        |                         | 7/30/2009    |                          | Mike Westerland<br>(Homeowner)          | 24176 Jagger Street<br>Lake Forest, CA 92630              | (949) 581-5643                          | 3         | Mike Westerland<br>(949) 581-5643         | Mike Westerland<br>(949) 581-5643        | L        | YES                  | 7/31/2009          | 33.628562 | -117.708608 |
|               |                |         |        |              |        |          | Foothill           |           |       |               |        |   |                    | Steel                   |              |                          | King Pool Design                        | 16728 Daisy Avenue  |   |           | Craig King<br>King Pool Design            | Craig King<br>King Pool Design           |          |                      |                    |           |             |
| 8/5/2009      | 51365          |         | 7      | Avance       | Lane   |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements          | 8/5/2009     |                          | & Consulting                            | Fountain Valley, CA 92708                                 | (714) 448-6106                          | 6         | (714) 448-6106                            | (714) 448-6106                           | L        | YES                  | 8/18/2009          | 33.687121 | -117.653705 |
| 8/12/2009     | 51402          |         | 22176  | Tama         | Drive  |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Aluminum<br>Patio Enclosure (112 SF)                | Residential        | Footings                | 8/12/2009    |                          | Crown Construction                      | 1205 N. Knolwood Circle<br>Anaheim, CA 92801              | (714) 761-0060                          | 0         | (714) 761-0060                            | (714) 761-0060                           | L        | YES                  | 8/14/2009          | 33.640969 | -117.698139 |
| 8/20/2009     | 51444          |         | 23482  | Cavanaugh    | Road   |          | Lake<br>Forest     | CA 9263   | 0     | ۷ 1           | NA     | Room Additions (252 SF)                             | Residential        | Footings                | 8/20/2009    |                          | Divine Developers,<br>Inc.              | 4872 Topanga Cyn. Blvd., #355<br>Woodland Hills, CA 91364 | (800) 984-5518                          |           | Divine Developers, Inc.<br>(800) 984-5518 | Divine Developers, Inc<br>(800) 984-5518 |          | YES                  | 8/24/2009          | 33.621624 | -117.704582 |
|               |                |         |        |              | Road   |          | Lake               |           |       |               |        |   |                    |                         |              |                          |   | 28781 Prudente  | , |           | Costello Construction                     | Costello Construction                    |          |                      |                    |           |             |
| 8/25/2009     | 51460          |         | 25661  | Horse Shoe   |        |          | Forest<br>Lake     | CA 9263   | 0     | < 1           | NA     | Room Additions (213 SF)<br>Sewer Repair -           | Residential        | Footings                | 8/25/2009    |                          | Costello Construction                   | Mission Viejo, CA 92692<br>740 N. Hariton Street          | (949) 768-4292                          | 2         | (949) 768-4292<br>Rescue Rooter           | (949) 768-4292<br>Rescue Rooter          | L        | YES                  | 8/27/2009          | 33.63845  | -117.682982 |
| 9/8/2009      | 51515          |         | 22591  | Charwood     | Circle |          | Forest             | CA 9263   | 0     | < 1           | NA     | Repair of Disposal System                           | Residential        |                         | 9/8/2009     |                          | Rescue Rooter                           | Orange, CA 92868  | (714) 964-1538                          | 3         | (714) 964-1538<br>Robin Helms             | (714) 964-1538<br>Robin Helms            | L        | YES                  | 9/9/2009           | 33.635324 | -117.697569 |
|               |                |         |        |              |        |          | Lake               |           |       | _             |        |   |                    | Steel                   |              |                          |   | 21572 Midcrest Drive                                      |   |           | Helms Pool & Spa                          | Helms Pool & Spa                         |          |                      |                    |           |             |
| 9/9/2009      | 51529          |         | 24586  | Via Tequila  |        |          | Forest             | CA 9263   | 0     | < 1           | NA     | Pool / Spa Remodel                                  | Residential        | Reinforcements          | 9/9/2009     |                          | Helms Pool & Spa                        | Lake Forest, CA 92630                                     | (949) 583-0544                          | 1         | (949) 929-2411<br>Stephen R. Freese       | (949) 929-2411<br>Stephen R. Freese      | L        | YES                  | 9/11/2009          | 33.652834 | -117.701995 |
| 9/15/2009     | 51561          |         | 25111  | Steinway     | Circle |          | Lake               | CA 9263   | 0     | -1            | NA     | Patio Enclosure (198 SF)                            | Residential        | Footings                | 9/15/2009    |                          | Capistrano<br>Sunrooms                  | 26332 Paseo Toscana<br>SanJuan Capistrano, CA 92675       | (949) 307-9653                          |           | Capistrano Sunrooms<br>(949) 307-9653     | Capistrano Sunrooms<br>(949) 307-9653    |          | VES                  | 10/5/2009          | 33.6316   | -117.691817 |
|               |                |         | 20111  |              | Onoic  |          | Lake               | 071 0200  |       | - ` '         |        |   | recorderna         |                         |              |                          | Gregory S. Picard                       | 25032 Rudolph Circle                                      |   |           | Gregory S. Picard                         | Gregory S. Picard                        |          | 120                  |                    |           |             |
| 9/17/2009     | 51592          |         | 25032  | Rudolph      | Circle |          | Forest<br>Lake     | CA 9263   | 0     | < 1           | NA     | Room Addition (64 SF)                               | Residential        | Footings<br>Steel       | 9/17/2009    |                          | (Homeowner)<br>Swan Pools of            | Lake Forest, CA 92630<br>24512 Bridger Road               | (949) 951-4376                          | 5         | (949) 951-4376<br>Swan Pools              | (949) 951-4376<br>Swan Pools             | L        | YES                  | 10/19/2009         | 33.631606 | -117.693656 |
| 9/22/2009     | 51628          |         | 21762  | Newvale      | Drive  |          | Forest<br>Lake     | CA 9263   | 0     | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements<br>Steel | 9/22/2009    |                          | Southern California<br>California Pools | Lake Forest, CA 92630<br>970 N. Tustin Avenue, #200       | (949) 859-8466                          | 3         | (949) 859-8466<br>California Pools &Spas  | (949) 859-8466<br>California Pools &Spas | L        | YES                  | 11/6/2009          | 33.647035 | -117.681742 |
| 9/28/2009     | 51664          |         | 24662  | Evereve      | Circle |          | Forest             | CA 9263   | 0     | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements          | 9/28/2009    |                          | & Spas                                  | Anaheim, CA 92807   | (714) 575-9286                          | 3         | (714) 575-9286                            | (714) 575-9286                           | L        | YES                  | 10/23/2009         | 33.633416 | -117.698678 |
|               |                |         |        |              |        |          | Foothill           |           |       |               |        |   |                    | Steel                   |              |                          |   | 25652 Taladro, Suite F                                    |   |           | Dave Leese<br>Pebble Beach Pools          | Dave Leese<br>Pebble Beach Pools         |          |                      |                    |           |             |
| 9/30/2009     | 51691          |         | 1      | Esternay     | Drive  |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements          | 9/30/2009    |                          | Pebble Beach Pools                      | Mission Viejo, CA 92691<br>1203 Charco                    | (949) 768-5435                          | 5         | (949) 768-5435<br>Halton Corporation      | (949) 768-5435<br>Halton Corporation     | L        | YES                  | 10/19/2009         | 33.687437 | -117.657017 |
| 10/5/2009     | 51711          |         | 10     | Alonda       |        |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Room Addition (96 SF)                               | Residential        | Footings                | 10/5/2009    |                          | Halton Corporation                      | San Clemente, CA 92673                                    | (949) 600-5770                          | o         | (949) 600-5770                            | (949) 600-5770                           | L        | YES                  | 10/22/2009         | 33.690333 | -117.667352 |
| 10/13/2009    | 51758          |         | 21982  | Cayuga       | Lane   |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Room Additions (247 SF) &<br>Balcony (45 SF)        | Residential        | Footings                | 10/13/2009   |                          | Mr. & Mrs. Margolis<br>(Homeowner)      | 21982 Cayuga Lane<br>Lake Forest, CA 92630                | (949) 770-9017                          | 7         | Mr. Margolis<br>(949) 770-9017            | Mr. Margolis<br>(949) 770-9017           | L        | YES                  | 10/28/2009         | 33.643231 | -117.704274 |
| 10/21/2009    | 51818          |         | 24656  | Shadowfax    | Drive  |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Room Additions (586 SF)                             | Residential        | Footings                | 10/21/2009   |                          | Brian Burns<br>(Homeowner)              | 24656 Shadowfax Drive<br>Lake Forest, CA 92630            | (562) 665-0646                          |           | Brian Burns<br>(562) 665-0646             | Brian Burns<br>(562) 665-0646            |          | YES                  | 11/5/2009          | 33.635427 | -117.699512 |
| 10/21/2003    | 31010          |         | 24030  | Siladowiax   | Dilve  |          |                    | CA 9203   |       | \ I           | INA    |   | Residential        | 1 doulings              | 10/21/2003   |                          | (Homeowner)                             |   | (302) 003-0040                          |           | Moira Boynton                             | Moira Boynton                            |          | ILO                  | 11/3/2003          | 33.033427 | -117.000012 |
| 10/29/2009    | 51866          |         | 21641  | Canada       | Road   |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Upgrades to Existing<br>Monument Signs              | Residential        | Footings                | 10/29/2009   |                          | Gannon Design                           | 360 S. Glassell Street, Suite A<br>Orange, CA 92866       | (714) 538-5591                          | 1         | Gannon Design<br>(714) 538-5591           | Gannon Design<br>(714) 538-5591          | L        | YES                  | 9/29/2010          | 33.650113 | -117.682144 |
|               |                |         |        |              |        |          | Foothill           |           |       |               |        |   |                    | Steel                   |              |                          | King Pool Design                        | 16728 Daisy Avenue  |   |           | Craig King<br>King Pool Design            | Craig King<br>King Pool Design           |          |                      |                    |           |             |
| 10/29/2009    | 51873          |         | 67     | Parrell      | Avenue |          | Ranch              | CA 9261   | o     | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements          | 10/29/2009   |                          | & Consulting                            | Fountain Valley, CA 92708                                 | (714) 448-6106                          | 3         | (714) 448-6106                            | (714) 448-6106                           | L        | YES                  | 11/3/2009          | 33.683724 | -117.650494 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        |   |                    |                         |              |                          |   | 5325 E. Hunter Avenue                                     |   |           | Summer Howerton<br>Outdoor Dimensions     | Summer Howerton<br>Outdoor Dimensions    |          |                      |                    |           |             |
| 11/3/2009     | 51893          |         | 22159  | Rimhurst     | Drive  |          | Forest             | CA 9263   | 0     | < 1           | NA     | Monument Sign                                       | Residential        | Footings                | 11/3/2009    |                          | Outdoor Dimensions                      | Anaheim, CA 92807   | (714) 578-9555                          | 5         | (714) 578-9555<br>Mike Sanchez            | (714) 578-9555<br>Mike Sanchez           | L        | YES                  | 12/15/2009         | 33.640283 | -117.681492 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        | Demo Deck, Reconstruct                              |                    |                         |              |                          | MS Landscape &                          | 10951 Court Avenue  |   |           | MS Landscape & Gdn.                       | MS Landscape & Gdn.                      |          |                      |                    |           |             |
| 11/3/2009     | 51895          |         | 25272  | Dayton       | Drive  |          | Forest             | CA 9263   | 0     | < 1           | NA     | New Deck & Prefab. Spa                              | Residential        | Footings                | 11/3/2009    |                          | Garden Service, Inc.                    | Stanton, CA 90680   | (714) 761-5069                          | 9         | (714) 761-5069<br>Mike Delmont            | (714) 761-5069<br>Mike Delmont           | L        | YES                  | 12/7/2009          | 33.642354 | -117.690491 |
| 11/3/2009     | 51898          |         | 21272  | Valewood     |        |          | Lake<br>Forest     | CA 9263   | 0     | د 1           | NA     | Pool / Spa  | Residential        | Steel<br>Reinforcements | 11/3/2009    |                          | Crystal Cove Pools &<br>Spas            | 33 Via Garona<br>San Clemente, CA 92673                   | (949) 706-0495                          |           | Crystal Cove Pools<br>(949) 706-0495      | Crystal Cove Pools<br>(949) 706-0495     |          | YES                  | 12/10/2009         | 33.654075 | -117 681523 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        |   |                    |                         |              |                          | Divine Developers,                      | 4872 Topanga Cyn. Blvd., #355                             | , |           | Divine Developers, Inc.                   | Divine Developers, Inc.                  |          |                      |                    |           |             |
| 11/4/2009     | 51905          |         | 23482  | Cavanaugh    | Road   |          | Forest<br>Lake     | CA 9263   | 0     | < 1           | NA     | Room Additions (10 SF)                              | Residential        | Footings                | 11/4/2009    |                          | Inc.<br>Manuel Magana                   | Woodland Hills, CA 91364<br>24171 Hurst Drive             | (800) 985-5518                          | 3         | (800) 985-5518<br>Manuel Magana           | (800) 985-5518<br>Manuel Magana          | L        | YES                  | 12/30/2009         | 33.621624 | -117.704582 |
| 11/4/2009     | 51908          |         | 24171  | Hurst        | Drive  |          | Forest             | CA 9263   | 0     | < 1           | NA     | Room Addition (196 SF)                              | Residential        | Footings                | 11/4/2009    |                          | (Homeowner)<br>Susan I. Sandow          | Lake Forest, CA 92630<br>21831 Eveningside Lane           | (949) 916-1929                          | 9         | (949) 916-1929<br>Susan I. Sandow         | (949) 916-1929<br>Susan I. Sandow        | L        | YES                  | 11/18/2009         | 33.627935 | -117.708407 |
| 11/9/2009     | 51953          |         | 21831  | Eveningside  | Lane   |          | Forest             | CA 9263   | 0     | < 1           | NA     | Demo of Fire Damage                                 | Residential        |                         | 11/9/2009    |                          | (Homeowner)                             | Lake Forest, CA 92630                                     | (949) 280-8005                          | 5         | (949) 280-8005                            | (949) 280-8005                           | L        | YES                  | 4/14/2010          | 33.645665 | -117.699217 |
| 12/4/2009     | 52132          |         | 21762  | Eveningside  | Lane   |          | Lake<br>Forest     | CA 9263   | 0     | < 1           | NA     | Room Addition (198 SF)                              | Residential        | Footings                | 12/4/2009    |                          | Coppola<br>Construction                 | 21842 Bass Lake Circle<br>Lake Forest, CA 92630           | (949) 282-9881                          | 1         | Coppola Construction<br>(949) 282-9881    | Coppola Construction<br>(949) 282-9881   | L        | YES                  | 12/9/2009          | 33.646532 | -117.699168 |
| 12/8/2009     | 52159          |         | 24212  | Ontario      | Lane   |          | Lake               | CA 9263   | 0     | -1            | NA     | Sound Walls, Stone<br>Columns & Patio               | Residential        | Footings                | 12/8/2009    |                          | David L. Cole<br>(Homeowner)            | 24212 Ontario Lane<br>Lake Forest CA 92630                | (949) 830-6499                          |           | David L. Cole<br>(714) 724-6604           | David L. Cole<br>(714) 724-6604          |          | YES                  | 12/22/2009         | 33 647511 | -117 708419 |
|               |                |         |        |              |        |          | Lake               |           |       | - ` '         |        |   |                    |                         |              |                          | John R. Clabaugh                        | 25172 Cineria Way   | (0.10) 000 0.10                         |           | John R. Clabaugh                          | John R. Clabaugh                         | -        |                      |                    |           |             |
| 12/29/2009    | 52259          |         | 25172  | Cineria      | Way    |          | Forest<br>Lake     | CA 9263   | U     | < 1           | NA     | Room Additions (380 SF)                             | Residential        | Footings                | 12/29/2009   |                          | (Homeowner)<br>Gregory Delany           | Lake Forest, CA 92630<br>24091 Eaglemont Avenue           | (949) 770-1166                          | 5         | (949) 466-9933<br>Gregory Delany          | (949) 466-9933<br>Gregory Delany         | L        | YES                  | 1/6/2010           | 33.63842  | -117.691868 |
| 1/14/2010     | 52348          |         | 24091  | Eaglemont    | Avenue |          | Forest             | CA 9263   | 0     | < 1           | NA     | Storage Shed (200 SF)<br>Room Addition (182 SF)     | Residential        | Footings                | 1/14/2010    |                          | (Homeowner)<br>Susan I Sandow           | Lake Forest, CA 92630<br>21831 Eveningside Lane           |   |           | (Homeowner)<br>Susan I. Sandow            | (Homeowner)<br>Susan I. Sandow           | L        | YES                  | 2/3/2010           | 33.619625 | -117.708461 |
| 1/27/2010     | 52410          |         | 21831  | Eveningside  | Lane   |          | Forest             | CA 9263   | 0     | < 1           | NA     | & Fire Repairs (1,700 SF)                           | Residential        | Footings                | 1/27/2010    |                          | (Homeowner)                             | Lake Forest, CA 92630                                     | (949) 280-8005                          | 5         | (949) 280-8005                            | (949) 280-8005                           | L        | YES                  | 3/18/2010          | 33.645665 | -117.699217 |
|               |                |         |        |              |        |          | Foothill           |           |       |               |        | Room Additions (702 SF)                             |                    |                         |              |                          | RD McCray                               | 26741 Portola Pkwy., 1E#279                               |   |           | RD McCray<br>Construction, Inc.           | RD McCray<br>Construction, Inc.          |          |                      |                    |           |             |
| 1/28/2010     | 52426          |         | 33     | Marseille    | Way    |          | Ranch              | CA 9261   | 0     | < 1           | NA     | & Loft Addition (160 SF)                            | Residential        | Footings                | 1/28/2010    |                          | Construction, Inc.                      | Foothill Ranch, CA 92610                                  | (949) 279-7231                          | 1         | (949) 279-7231<br>Dave Clever             | (949) 279-7231<br>Dave Clever            | L        | YES                  | 2/4/2010           | 33.684236 | -117.653279 |
|               |                |         |        |              |        |          | Foothill           |           |       |               |        |   |                    |                         |              |                          | All-Pro Contracting,                    | 5753-G E. Santa Ana Cyn. Rd.                              |   |           | All-Pro Contracting                       | All-Pro Contracting                      |          |                      |                    |           |             |
| 2/2/2010      | 52447          |         | 59     | Parrell      | Avenue |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Room Addition (325 SF)<br>Room Additions (724 SF) & | Residential        | Footings                | 2/2/2010     |                          | Inc.                                    | Anaheim, CA 92807<br>26 Parrell Avenue                    | (714) 779-1102                          | 2         | (714) 779-1102<br>Vaughn Construction     | (714) 779-1102<br>Vaughn Construction    | L        | YES                  | 3/18/2010          | 33.684029 | -117.65062  |
| 2/18/2010     | 52560          |         | 27     | Coca         |        |          | Ranch              | CA 9261   | 0     | < 1           | NA     | Balcony/ Patio/ Trellis                             | Residential        | Footings                | 2/18/2010    |                          | Vaughn Construction                     | Foothill Ranch, CA 92610                                  | (949) 742-4358                          | 3         | (949) 742-4358<br>Dafna Lahav             | (949) 742-4358<br>Dafna Lahav            | L        | YES                  | 3/4/2010           | 33.689314 | -117.667901 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        |   |                    |                         |              |                          | High Star                               | 18375 Ventura Boulevard, #206                             |   |           | High Star Construction                    | High Star Construction                   |          |                      |                    |           |             |
| 3/15/2010     | 1086           |         | 22152  | Pheasant     | Street | $\vdash$ | Forest<br>Lake     | CA 9263   | 0     | < 1           | NA     | Room Additions (575 SF)                             | Residential        | Footings                | 3/15/2010    |                          | Construction, Inc. Donna Wright         | Tarzana, CA 91356<br>24266 Ontario Lane                   | (888) 272-6868                          | 3         | (310) 883-5515<br>Donna Wright            | (310) 883-5515<br>Donna Wright           | L        | YES                  | 3/30/2010          | 33.642    | -117.705641 |
| 3/15/2010     | 1092           |         | 24266  | Ontario      | Lane   |          | Forest             | CA 9263   | 0     | < 1           | NA     | Room Additions (462 SF)                             | Residential        | Footings                | 3/15/2010    |                          | (Homeowner)                             | Lake Forest, CA 92630                                     | (949) 494-1646                          | 3         | (949) 494-1646<br>Fermin Diaz             | (949) 494-1646<br>Fermin Diaz            | L        | YES                  | 3/22/2010          | 33.647203 | -117.708025 |
|               |                |         |        |              |        |          | Lake               |           |       |               |        |   |                    |                         |              |                          | Fermin Diaz                             | 3832 Dawes Street   |   |           | General Contractor                        | General Contractor                       |          |                      |                    |           |             |
| 3/3/2010      | 1097           |         | 25912  | Tipperary    | Lane   | $\vdash$ | Forest             | CA 9263   | 0     | < 1           | NA     | Room Addition (191 SF)                              | Residential        | Footings                | 3/3/2010     |                          | General Contractor                      | Riverside, CA 92503                                       | (951) 217-8363                          | 3         | (951) 217-8363<br>Roger Stalmer           | (951) 217-8363<br>Roger Stalmer          | L        | YES                  | 3/22/2010          | 33.649358 | -117.67916  |
| 0/4/5         |                |         | 044==  | total 1      | 51     |          | Lake               |           |       |               |        | D   | B                  | Steel                   | 0/4/         |                          | California Pools                        | 970 N. Tustin Avenue, #200                                | (74.0) 577                              |           | California Pools&Spas                     | California Pools&Spas                    |          |                      | 0/40/              | 00.0      |             |
| 3/4/2010      | 1113           |         | 24472  | Jutewood     | Place  | $\vdash$ | Forest<br>Lake     | CA 9263   |       | < 1           | NA     | Pool / Spa  | Residential        | Reinforcements          | 3/4/2010     |                          | & Spas                                  | Anaheim, CA 92807<br>3602 E. Coast Highway                | (714) 575-9286                          |           | (714) 575-9286<br>Saber                   | (714) 575-9286<br>Saber                  | -        | YES                  | 3/18/2010          | 33.625762 |             |
| 3/11/2010     | 1155           |         | 24477  | Copper Cliff | Court  |          | Forest             | CA 9263   | 0     | < 1           | NA     | Slab & Foundation Repairs                           | Residential        |                         | 3/11/2010    |                          | Saber                                   | Corona Del Mar, CA 92625                                  | (800) 922-2488                          | 3         | (800) 922-2488                            | (800) 922-2488                           | L        | YES                  | 3/18/2010          | 33.649034 | -117.703368 |

Page 1 of 2 11/10/2010

#### NPDES Construction Facilities Inventory - Residential Projects SAN DIEGO CREEK / NEWPORT BAY WATERSHED (SARWQCB) Year 2009-2010

|           |          |         |        |                |        |          |                   |       | 1 1   |        |         |        |                            |              |                |            |              |                     |  |                 |           |                                      |                                      | Ins        | spected for |            |           |               |
|-----------|----------|---------|--------|----------------|--------|----------|-------------------|-------|-------|--------|---------|--------|----------------------------|--------------|----------------|------------|--------------|---------------------|--|-----------------|-----------|--------------------------------------|--------------------------------------|------------|-------------|------------|-----------|---------------|
|           |          |         |        |                |        |          |                   |       |       |        | Total   |        |                            |              |                |            |              |                     |  |                 |           |                                      |                                      |            | osion and   |            |           |               |
| Issue     | Building | Project | Street | Street         | Street |          |                   |       |       | Tract  | Site    | WDID   | Description                | Type of      | Source         |            | Construction | Developer           | Developer                                | Developer       | Developer | Developer                            | Responsible Party or                 | 8          | Sediment    | Inspection |           |               |
| Date      | Permit # | Name    | Number | Name           | Suffix | Suite    | City              | State | Zip   | Number | Acreage | Number | of Project                 | Project      | Activities     | Start Date | End Date     | Name                | Address                                  | Phone           | Fax       | Onsite Contact                       | <b>Emergency Contact</b>             | Priority ( | Control?    | Date       | Lat       | Lon           |
|           |          |         |        |                |        |          |                   |       |       |        |         |        | Private Sewer Liner Repair |              |                |            |              |                     |  |                 |           | David Carpenter                      | David Carpenter                      |            |             |            |           | $\overline{}$ |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        | (4" Lateral in             |              |                |            |              | Roto Rooter         | 1183 N. Kramer Place                     |                 |           | Roto Rooter Plumbing                 | Roto Rooter Plumbing                 |            |             |            |           |               |
| 3/17/2010 | 1199     |         | 25062  | Calle Madera   |        |          | Forest            | CA    | 92630 |        | < 1     | NA     | Existing 4" Sewer)         | Residential  |                | 3/17/2010  |              | Plumbing            | Anaheim, CA 92806                        | (714) 476-3603  |           | (714) 476-3603                       | (714) 476-3603                       | L          | YES         | 3/18/2010  | 33.654096 | -117.692806   |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        |                            |              | Steel          |            |              | Courtney Zwahlen    | 22195 Apache Drive                       |                 |           | Courtney Zwahlen                     | Courtney Zwahlen                     |            |             |            |           |               |
| 3/30/2010 | 1264     |         | 22195  | Apache         | Drive  |          | Forest            | CA    | 92630 |        | < 1     | NA     | Pool / Spa                 | Residential  | Reinforcements | 3/30/2010  |              | (Homeowner)         | Lake Forest, CA 92630                    | (949) 228-6940  |           | (949) 228-6940                       | (949) 228-6940                       | L          | YES         | 4/19/2010  | 33.640488 | -117.688011   |
|           |          |         |        |                |        |          |                   |       |       |        |         |        |                            |              |                |            |              |                     |  |                 |           | Lee Nguyen                           | Lee Nguyen                           |            |             |            |           |               |
| 4/40/0040 | 4000     |         | 0.4400 | 0              | D      |          | Lake              |       | 00000 |        |         |        | D 4 44% (000 0F)           | D            | F              | 4/40/0040  |              | 1                   | 901 S. Bristol Street, #B157             | (744) 704 7470  |           | Lee's Construction                   | Lee's Construction                   |            | \/F0        | 5/7/0040   | 00.004000 | 447 704400    |
| 4/12/2010 | 1003     |         | 24402  | Overlake       | Drive  |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Additions (299 SF)    | Residential  | Footings       | 4/12/2010  |              | Lee's Construction  | Santa Ana, CA 92703                      | (714) 724-7176  |           | (714) 724-7176<br>Mike Jesse         | (714) 724-7176<br>Mike Jesse         | L          | YES         | 5/7/2010   | 33.634222 | -117.704432   |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        |                            |              |                |            |              | Mike Jesse          | 29112 Canvon Vista                       |                 |           | Mike Jesse<br>Mike Jessee Const.     | Mike Jesse Const.                    |            |             |            |           |               |
| 4/26/2010 | 1170     |         | 22847  | Ridge Route    | Drive  |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Addition (280 SF)     | Residential  | Footings       | 4/26/2010  |              | Construction        | Trabuco Canyon, CA 92679                 | (0.40) 221-5665 |           | (949) 331-5665                       | (949) 331-5665                       |            | YES         | 6/29/2010  | 33.631707 | -117 701990   |
| 4/20/2010 | 1170     |         | 22047  | reage reduce   | Dilve  |          | 101630            | UA    | 32030 |        |         | INC    | Room Addition (200 St.)    | residential  | i oonigs       | 4/20/2010  |              | Construction        | Trabuco Carryon, CA 92079                | (848) 331-3003  |           | Joel Siperek                         | Joel Siperek                         | -          | ILU         | 0/23/2010  | 33.031707 | -117.701003   |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        |                            |              |                |            |              | Select Trenchless   | 283 Winfield Circle                      |                 |           | Select Trenchless                    | Select Trenchless                    |            |             |            |           |               |
| 4/21/2010 | 1392     |         | 22511  | Woodcrest      | Circle |          | Forest            | CA    | 92630 |        | < 1     | NA     | Sewer Repair               | Residential  |                | 4/21/2010  |              | Pipelines           | Corona, CA 92880                         | (951) 736-0345  |           | (951) 736-0345                       | (951) 736-0345                       | L          | YES         | 4/22/2010  | 33.636256 | -117.697292   |
|           |          |         |        |                |        |          |                   |       |       |        |         |        | Retaining Wall (138 SF)    |              |                |            |              |                     |  |                 |           | Scott Krufal                         | Scott Krufal                         |            |             |            |           |               |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        | &                          |              |                |            |              |                     | 221 Avenue Serra                         |                 |           | KC, Inc.                             | KC, Inc.                             |            |             |            |           |               |
| 4/26/2010 | 1462     |         | 22676  | Shady Grove    | Circle |          | Forest            | CA    | 92630 |        | < 1     | NA     | FreestandingWall(276 SF)   | Residential  | Footings       | 4/26/2010  |              | KC, Inc.            | San Clemente, CA 92672                   | (949) 369-0740  |           | (949) 369-0740                       | (949) 369-0740                       | L          | YES         | 5/5/2010   | 33.633861 | -117.696684   |
|           |          |         |        |                |        |          |                   |       |       |        |         |        | Retaining Wall (210 SF)    |              |                |            |              |                     |  |                 |           | Scott Krufal                         | Scott Krufal                         |            |             |            |           |               |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        | &                          |              |                |            |              |                     | 221 Avenue Serra                         |                 |           | KC, Inc.                             | KC, Inc.                             |            |             |            |           |               |
| 4/26/2010 | 1463     |         | 22642  | Shady Grove    | Circle |          | Forest            | CA    | 92630 |        | < 1     | NA     | FreestandingWall(420 SF)   | Residential  | Footings       | 4/26/2010  |              | KC, Inc.            | San Clemente, CA 92672                   | (949) 369-0740  |           | (949) 369-0740                       | (949) 369-0740                       | L          | YES         | 5/5/2010   | 33.633986 | -117.696397   |
| 4/28/2010 | 1464     |         | 25     | Coca           |        |          | Foothill<br>Ranch | CA    | 92610 |        | < 1     | NA     | Room Additions (896 SF)    | Residential  | F              | 4/28/2010  |              | John T. Ertz. Inc.  | 27 Partierre<br>Foothill Ranch, CA 92610 | (949) 254-9194  |           | John T. Ertz, Inc.<br>(949) 254-9194 | John T. Ertz, Inc.<br>(949) 254-9194 |            | YES         | 5/4/2010   | 33.689256 | 447.007000    |
| 4/28/2010 | 1464     |         | 25     | Coca           |        |          | Lake              | CA    | 92610 |        | < 1     | NA     | Room Additions (896 SF)    | Residential  | Footings       | 4/28/2010  |              | John I. Ertz, Inc.  | P.O. Box 31                              | (949) 254-9194  |           | Del-West Builders                    | Del-West Builders                    | L          | YES         | 5/4/2010   | 33.689256 | -117.667828   |
| 5/3/2010  | 1491     |         | 24942  | Singingwoods   | Drive  |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Additions (179 SF)    | Residential  | Footings       | 5/3/2010   |              | Del-West Builders   | Trabuco Canvon, CA 92678                 | (714) 813-5900  |           | (714) 813-5900                       | (714) 813-5900                       |            | YES         | 5/10/2010  | 33.637119 | -117 605296   |
| 3/3/2010  | 1401     |         | 24042  | Sirigirigwoods | Dilve  |          | Lake              | UA    | 32030 |        |         | INC    | (179 SI)                   | residential  | Steel          | 3/3/2010   |              | Steve Dalat         | 23236 Cavanaugh Road                     | (714) 013-3300  |           | Steve Dalat                          | Steve Dalat                          | -          | ILO         | 3/10/2010  | 33.037113 | 117.033200    |
| 5/4/2010  | 1501     |         | 23236  | Cavanaugh      | Road   |          | Forest            | CA    | 92630 |        | < 1     | NA     | Pool / Spa                 | Residential  | Reinforcements | 5/4/2010   |              | (Homeowner)         | Lake Forest, CA 92630                    | (949) 981-6156  |           | (949) 981-6156                       | (949) 981-6156                       | 1          | YES         | 6/3/2010   | 33.624557 | -117 701647   |
|           |          |         |        |                | 11000  |          | Lake              |       |       |        |         |        |                            |              | Steel          |            |              | (                   | 22600 Lambert Street, #E-1104            | (0.0) 00. 0.00  |           | Mission Pools                        | Mission Pools                        | -          |             |            |           |               |
| 5/5/2010  | 1511     |         | 21846  | Tumbleweed     | Circle |          | Forest            | CA    | 92630 |        | < 1     | NA     | Pool / Spa                 | Residential  | Reinforcements | 5/5/2010   |              | Mission Pools       | Lake Forest, CA 92630                    | (949) 588-0100  |           | (949) 588-0100                       | (949) 588-0100                       | L          | YES         | 6/15/2010  | 33.645096 | -117.684053   |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        |                            |              |                |            |              |                     | 666 1/2 E. Sacramento Street             |                 |           | Kenneth LaMonica                     | Kenneth LaMonica                     |            |             |            |           |               |
| 5/18/2010 | 1596     |         | 21641  | Treeline       | Lane   |          | Forest            | CA    | 92630 |        | < 1     | NA     | Retaining Wall (87' x 3')  | Residential  | Footings       | 5/18/2010  |              | Kenneth LaMonica    | Altadena, CA 91001                       | (626) 354-5214  |           | (626) 354-5214                       | (626) 354-5214                       | L          | YES         | 5/19/2010  | 33.649402 | -117.686674   |
|           |          |         |        |                |        |          |                   |       |       |        |         |        |                            |              |                |            |              |                     |  |                 |           | John Mannix                          | John Mannix                          |            |             |            |           |               |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        | Room Additions (450 SF) &  |              |                |            |              |                     | 34559 Calle Portola                      |                 |           | Mannix Construction                  | Mannix Construction                  |            |             |            |           |               |
| 5/24/2010 | 1638     |         | 25022  | Owens Lake     | Circle |          | Forest            | CA    | 92630 |        | < 1     | NA     | Patio Cover (150 SF)       | Residential  | Footings       | 5/24/2010  |              | Mannix Construction | Capistrano Beach, CA 92624               | (949) 291-3715  |           | (949) 291-3715                       | (949) 291-3715                       | L          | YES         | 6/3/2010   | 33.646901 | -117.693779   |
|           |          |         |        |                |        |          | Lake              |       |       |        |         |        | Room Additions (165 SF) &  |              |                |            |              |                     | 3969 Nobel Drive, #269                   |                 |           | Dominic Amato                        | Dominic Amato                        |            |             |            |           |               |
| 6/1/2010  | 1642     |         | 25132  | Carolwood      |        |          | Forest            | CA    | 92630 |        | < 1     | NA     | Wood Deck (152 SF) &       | Residential  | Footings       | 6/1/2010   |              | Dominici Design     | San Diego, CA 92122                      | (949) 306-1737  |           | Dominici Design<br>((949) 306-1737   | Dominici Design<br>((949) 306-1737   |            | YES         | 6/9/2010   | 33.637407 | 447 600074    |
| 6/1/2010  | 1042     |         | 23132  | Carolwood      |        |          | Lake              | CA    | 92630 |        | 5 1     | INA    | W000 Deck (192 SF)         | Residential  | rounigs        | 6/1/2010   |              | Spencer Lowrey      | 21891 Sioux Drive                        | (949) 300-1737  |           | Spencer Lowrey                       | Spencer Lowrey                       | L          | TES         | 6/9/2010   | 33.03/40/ | 117.092371    |
| 6/2/2010  | 1711     |         | 21891  | Sioux          | Drive  |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Additions (422 SF)    | Residential  | Footings       | 6/2/2010   |              | (Homeowner)         | Lake Forest, CA 92630                    | (949) 380-8770  |           | (949) 380-8770                       | (949) 380-8770                       |            | YES         | 6/4/2010   | 33 645163 | -117 686965   |
| 0/2/2010  | .,,,,    |         | 21001  | Oloux          | Dille  |          | Lake              | O/ C  | ULUUU |        |         | 101    | TOOM FROM THE CITY         | recordential | i counge       | 0/2/2010   |              | William Bigatti     | 23822 Boeing Lane                        | (040) 000 0110  |           | William Bigatti                      | William Bigatti                      |            | 120         | 0.42010    | 00.040100 | 117.000000    |
| 6/28/2010 | 1712     |         | 23822  | Boeing         | Lane   |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Additions (718 SF)    | Residential  | Footings       | 6/28/2010  | 1            | (Homeowner)         | Lake Forest, CA 92630                    | (949) 916-9016  |           | (949) 916-9016                       | (949) 916-9016                       | L          | YES         | 7/22/2010  | 33.627942 | -117.715345   |
|           |          |         |        | Calle El Toro  |        |          | Lake              |       |       |        |         |        |                            |              |                |            |              | Angelica Herrera    | 24721 Calle El Toro Grande               |                 |           | Angelica Herrera                     | Angelica Herrera                     |            |             |            |           |               |
| 6/3/2010  | 1724     |         | 24721  | Grande         |        |          | Forest            | CA    | 92630 |        | < 1     | NA     | Room Additions (486 SF)    | Residential  | Footings       | 6/3/2010   |              | (Homeowner)         | Lake Forest, CA 92630                    | (949) 855-6315  |           | (949) 855-6315                       | (949) 855-6315                       | L          | YES         | 7/7/2010   | 33.629947 | -117.698154   |
|           |          |         |        |                |        | IT       | Lake              |       |       |        |         | 1      | Demo Single Family         |              |                |            |              |                     | 24711 Rollingwood Drive                  |                 |           | Gregg S. Linn                        | Gregg S. Linn                        | Т          |             |            |           |               |
| 6/16/2010 | 1804     |         | 24712  | Rollingwood    | Road   |          | Forest            | CA    | 92630 |        | < 1     | NA     | Dwelling (2,611 SF)        | Residential  |                | 6/16/2010  |              | Gregg S. Linn       | Lake Forest, CA 92630                    | (949) 455-9391  |           | (949) 455-9391                       | (949) 455-9391                       | L          | YES         | 6/23/2010  | 33.636773 | -117.70012    |
|           |          |         |        |                |        |          |                   |       |       |        |         |        |                            |              |                |            |              |                     |  |                 |           | Roger Stalmer                        | Roger Stalmer                        |            |             |            |           |               |
| 0/00/00:- | 4050     |         | 04546  | 16- B-14- :    |        |          | Lake              | -     | 0000- |        |         |        | D I / O                    | B            | Steel          | 0/00/004 - | l            | California Pools    | 970 N. Tustin Avenue, #200               | (744) 575 6     |           | California Pools&Span                |                                      |            | VE0         | 7/0/0045   | 00.04000: | 447.000-      |
| 6/23/2010 | 1858     |         | 21546  | Via Del Angel  |        | $\vdash$ | Forest            | CA    | 92630 |        | < 1     | NA     | Pool / Spa                 | Residential  | Reinforcements | 6/23/2010  | ļ            | & Spas              | Anaheim, CA 92807                        | (714) 575-9286  |           | (714) 575-9286<br>Roger Stalmer      | (714) 575-9286<br>Roger Stalmer      | L          | YES         | 7/6/2010   | 33.649621 | -117.69951    |
| 1         |          |         |        |                |        |          | Lake              |       |       |        |         |        |                            | l            | Steel          |            | l            | California Pools    | 970 N. Tustin Avenue, #200               |                 |           | California Pools&Spar                |                                      |            |             | J          |           | J             |
| 6/23/2010 | 1860     |         | 21342  | Calle Sendero  |        |          | Forest            | CA    | 92630 |        | < 1     | NA     | Pool / Spa                 | Residential  | Reinforcements | 6/23/2010  | 1            | & Spas              | Anaheim, CA 92807                        | (714) 575-9286  |           | (714) 575-9286                       | (714) 575-9286                       |            | YES         | 7/12/2010  | 33.653302 | -117 601120   |
| G/20/2010 |          |         | 2.042  | Cuit Selluelo  | 1      | 1 1      |                   |       | 02000 |        |         | 1      | Land of the                |              |                | G-20/2010  | 1            |                     | ,  | (1.17) 010-0200 | l .       | , ,                                  | , ,                                  | -          |             | 2010       | 00.000002 |               |

Page 2 of 2 11/10/2010

# NPDES Construction Facilities Inventory - Commercial Projects ALISO CREEK WATERSHED (SDRWQCB) Year 2009-2010

|               |                                  |                                      |                  |                     |                  | _     |                  |       |       |                 |                          |                |  |                    |                      |                            |                          |  |  |                    |                  |  |   |          | Inspected for                            |   |           |             |
|---------------|----------------------------------|--------------------------------------|------------------|---------------------|------------------|-------|------------------|-------|-------|-----------------|--------------------------|----------------|--|--------------------|----------------------|----------------------------|--------------------------|--|--|--------------------|------------------|--|---|----------|--|---|-----------|-------------|
| Issue<br>Date | Grading/<br>Building<br>Permit # | Project<br>Name                      | Street<br>Number | Street<br>Name      | Street<br>Suffix | Suite | City             | State | Zip   | Tract<br>Number | Total<br>Site<br>Acreage | WDID<br>Number | Description of Project   | Type of<br>Project | Source<br>Activities | Construction<br>Start Date | Construction<br>End Date | Developer<br>Name                                | Developer<br>Address                                   | Developer<br>Phone | Developer<br>Fax | Developer<br>Onsite Contact  | Responsible Party or<br>Emergency Contact                   | Priority | Erosion and<br>Sediment<br>Control?      | Inspection Date                                 | e Lat     | Lon         |
|               |                                  | Saddleback Church<br>- Quarry Site   | 1                | Rocky               | Road             |       | Lake<br>Forest   | CA    | 92630 |                 |                          | 930C334509     | Former Quarry  |                    | Grading              | 1/15/2005                  |                          | Saddleback Church                                | 1 Saddleback Parkway<br>Lake Forest, CA 92630          |                    |                  |  |   | м        | YES                                      | 10/14/2009<br>1/4/2010                          | 33.664895 | -117.652359 |
| 11/3/2004     | 36436                            | OCFA<br>- Fire Station #19           | 23022            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | 0.803                    | N/A            | Fire Station   |                    | Grading              | 11/8/2004                  | 10/15/2005               | Orange County<br>Fire Authority                  | 180 S. Water Street<br>Orange, CA 92866                | (714) 744-0566     |                  | Dan Depudja<br>(714) 206-0752                                      | Jack O'Meara<br>(714) 317-4499                              | м        | NO<br>(No Work<br>Activities)            | No Work<br>Activities                           | 33.627321 | -117.691804 |
| 11/8/2007     | 47412                            | Saddleback Church<br>- Central Plant | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   |       | 92630 |                 | 1.61                     | 930C334509     | Commercial   | Commercial         | Grading              | 10/29/2007                 | 6/30/2008                | Saddleback<br>Development<br>Corporation         | 5 Rocky Road<br>Lake Forest, CA 92630                  | (949) 609-8260     | (949) 609-8282   | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013                      | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013               | М        | YES                                      | 1/4/2010<br>3/15/2010<br>4/7/2010               | 33.662103 | -117.651928 |
| 11/7/2007     | 47413                            | Saddleback Church<br>- Central Plant | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Foundations,<br>Slabs &<br>Retaining Walls                       | Commercial         | Footings             | 11/7/2007                  |                          | Saddleback<br>Development<br>Corporation         | 5 Rocky Road<br>Lake Forest, CA 92630                  | (949) 903-1013     |                  | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013                      | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013               | L        | YES                                      | 3/15/2010<br>4/7/2010                           | 33.662103 | -117.651928 |
| 11/20/2007    | 47472                            | Saddleback Church                    | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | New Building<br>(5,084 SF)                                       | Commercial         | Footings             | 11/20/2007                 |                          | Saddleback<br>Development<br>Corporation         | 5 Rocky Road<br>Lake Forest, CA 92630                  | (949) 903-1013     |                  | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013                      | Tim Loza<br>Saddleback Dev.<br>(949) 903-1013               | L        | YES                                      | 3/15/2010<br>4/7/2010                           | 33.662103 | -117.651928 |
| 3/27/2008     | 48222                            | El Toro<br>Retail Center             | 23572            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | 1.26                     | 6A30C350539    | Retail Building<br>& Parking Lot                                 | Commercial         | Grading              | 4/1/2008                   | 8/2008                   | Prothero Enterprises,<br>Inc.                    | 741 E. Briardale Avenue<br>Orange, CA 92865            | (714) 997-9734     | (949) 338-9661   | Jeff Dill<br>(949) 680-0799<br>Tim Free                            | Jeff Dill<br>(949) 680-0799<br>Tim Free                     | М        | YES                                      | FINALED<br>10/28/2008                           | 33.620175 | -117.700624 |
| 6/5/2008      | 48749                            | Oakley                               | 1                | Icon                |                  |       | Foothil<br>Ranch |       | 92610 |                 | < 1                      | NA             | Mezzanine<br>(4,223 SF)  | Commercial         | Footings             | 6/5/2008                   |                          | Granite Distribution<br>Solutions                | 27762 Antonio Parkway, U-500<br>Ladera Ranch, CA 92694 | (949) 861-1881     |                  | Granite Distribution<br>(949) 861-1881                             | Granite Distribution<br>(949) 861-1881                      | L        | YES                                      | 6/6/2008  | 33.669385 | -117.647351 |
| 7/9/2008      | 49001                            | Valley Building<br>Materials         | 23202            | Olive               | Avenue           |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Site Renovation,<br>Walls &Flat Work<br>Add Water                | Commercial         | Grading              | 7/29/2008                  |                          | Dave Leese<br>Saddleback                         | 1 San Anselmo<br>R. Santa Margarita, CA 92688          | (949) 677-2835     | (949) 858-9116   | Dave Leese<br>(949) 677-2835<br>Mark Marshall                      | Cliff<br>(949) 584-5197<br>Mark Marshall                    | L        | YES                                      | 6/29/2010                                       | 33.625473 | -117.690529 |
| 11/6/2008     | 49850                            | Saddleback Church                    | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Storage Tank to<br>Central Plant<br>Mechanical                   | Commercial         | Footings             | 11/6/2008                  |                          | Development<br>Corporation                       | 5 Rocky Road<br>Lake Forest, CA 92630                  | (949) 609-8000     |                  | Saddleback Dev.<br>(949) 903-1015                                  | Saddleback Dev.<br>(949) 903-1015                           | L        | YES                                      | 7/17/2009<br>1/16/2009                          | 33.662103 | -117.651928 |
| 12/3/2008     | 50004                            | Oakley                               | 1                | Icon                |                  |       | Foothil<br>Ranch |       | 92610 |                 | < 1                      | NA             | Enclosure<br>(1,698 SF)<br>Restaurant                            | Commercial         | Footings             | 12/3/2008                  |                          | Caliber Construction,<br>Inc.<br>BMW Management, | 240 N. Orange Avenue<br>Brea, CA 92821                 | (714) 255-2700     |                  | Caliber Construction<br>(714) 255-2700                             | Caliber Construction<br>(714) 255-2700                      | L        | YES                                      | FINALED<br>12/28/2009                           | 33.669385 | -117.647351 |
| 2/19/2009     | 50331                            | Sizzler Restaurant                   | 23501            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Expansion<br>(1,670 SF)  | Commercial         | Footings             | 2/19/2009                  |                          | Inc.<br>(Owner)                                  | 43172 Business Park Drive, #101<br>Temecula, CA 92590  | (951) 676-8616     |                  | BMW Management<br>(951) 676-8616<br>Gene Tripp                     | BMW Management<br>(951) 676-8616<br>Gene Tripp              | L        | (Work Activities<br>Not Initiated)       | 7/21/2010<br>8/17/2010                          | 33.621863 | -117.69924  |
| 2/23/2009     | 50342                            |                                      | 23891            | Bridger             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | EVR Phase II<br>Upgrade  | Commercial         | Footings             | 2/23/2009                  |                          | Slunaker<br>Construction                         | 3672 Chicago Avenue<br>Riverside, CA 92507             | (951) 788-7070     |                  | Slunaker Construct.<br>(951) 788-7070 x104<br>Corry Enyart         | Slunaker Construct.   | L        | YES                                      | 8/17/2010<br>FINALED<br>8/17/2010<br>3/26/2009  | 33.615511 | -117.707222 |
| 2/24/2009     | 50357                            | Arbor Christian<br>Fellowship        | 23302            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Monument Sign  | Commercial         | Footings             | 2/24/2009                  |                          | Saddleback Signs<br>Saddleback                   | 20996 Bake Parkway, #108<br>Lake Forest, CA 92630      | (949) 597-1966     |                  | Saddleback Signs<br>(949) 597-1966<br>Mark Marshall                | Saddleback Signs<br>(949) 597-1966<br>Mark Marshall         | L        | YES                                      | FINALED<br>1/4/2010                             | 33.623886 | -117.696116 |
| 4/21/2009     | 50693                            | Saddleback Church                    | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Front Wall<br>(H:28"/L:4'6")                                     | Commercial         | Footings             | 4/21/2009                  |                          | Development<br>Corporation                       | 5 Rocky Road<br>Lake Forest, CA 92630                  | (949) 609-8260     |                  | Saddleback Dev.<br>(949) 903-1015                                  | Saddleback Dev.<br>(949) 903-1015                           | L        | YES                                      | 3/15/2010<br>4/7/2010                           | 33.662103 | -117.651928 |
| 4/22/2009     | 50705                            | Oakley<br>Southwest Corner of        | 1                | Icon                |                  |       | Foothil<br>Ranch | CA    | 92610 |                 | < 1                      | NA             | CMU Screen Wall<br>Enclosure for<br>Equipment                    | Commercial         | Footings             | 4/22/2009                  |                          | Caliber Construction,<br>Inc.                    | 240 N. Orange Avenue<br>Brea, CA 92821                 | (714) 255-2700     |                  | Caliber Construction<br>(714) 255-2700                             | Caliber Construction<br>(714) 255-2700                      | L        | YES                                      | 4/30/2009<br>FINALED<br>12/28/2009<br>5/27/2009 | 33.669385 | -117.647351 |
| 4/23/2009     | 50721                            | El Toro Road and<br>Arbor Way        | 23635            | El Toro             | Road             | А     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Exterior Remodel<br>of Retail Bldg<br>Add Tower&Trellis          | Commercial         | Footings             | 4/23/2009                  |                          | Laubach<br>Construction, Inc.                    | 9841 Irvine Center Drive, #120<br>Irvine, CA 92618     | (949) 788-0299     |                  | Laubach Construction<br>(949) 788-0299<br>Craig Takata             | Laubach Construction<br>(949) 788-0299<br>Craig Takata      | L        | YES                                      | 5/27/2009<br>FINALED<br>8/10/2009<br>5/11/2009  | 33.618636 | -117.70323  |
| 5/4/2009      | 50800                            | Alacer Corporation                   | 80               | Icon                |                  |       | Foothil<br>Ranch |       | 92610 |                 | < 1                      | NA             | New Mezzanine<br>(585 SF)<br>Install                             | Commercial         | Footings             | 5/4/2009                   |                          | Clean Rooms West,<br>Inc.                        | 1392 Industrial Drive<br>Tustin, CA 92780              | (714) 258-7700     |                  | Clean Rooms West<br>(949) 274-1990<br>Lee Donovan                  | Clean Rooms West<br>(949) 274-1990<br>Lee Donovan           | L        | YES                                      | FINALED<br>8/13/2009                            | 33.670351 | -117.644137 |
| 5/7/2009      | 50826                            | Heroes Park                          | 25420            | Jeronimo            | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Scoreboards for<br>Baseball Fields<br>RTO Oxidizer Unit          | Commercial         | Footings             | 5/7/2009                   |                          | Tomark Sports<br>Baghouse &                      | 1180-A California Avenue<br>Corona, CA 92881           | (951) 371-1844     |                  | Tomark Sports<br>(951) 453-1840<br>Geno Meza                       | Tomark Sports<br>(951) 453-1840<br>Geno Meza                | L        | YES                                      | 5/14/2009                                       | 33.625465 | -117.687453 |
| 6/5/2009      | 50999                            | Oakley                               | 1                | Icon                |                  |       | Foothil<br>Ranch |       | 92610 |                 | < 1                      | NA             | - SeismicTieDown<br>& Foundation                                 | Commercial         | Footings             | 6/5/2009                   |                          | Industrial Sheet<br>Metal Services               | 1731 Pomona Road<br>Corona, CA 92880                   | (951) 272-6610     |                  | Baghouse&Industrial<br>(951) 272-6610                              | Baghouse&Industrial<br>(951) 272-6610                       | L        | YES                                      | FINALED<br>12/28/2009                           | 33.669385 | -117.647351 |
| 8/6/2009      | 51371                            | Hooters                              | 24356            | Swartz              | Drive            |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Underground<br>Private Fire Main<br>(200 FT)                     | Commercial         |                      | 8/6/2009                   |                          | Southern California<br>Fire Protection, Inc.     | 27665 Forbes Road, #8<br>Laguna Niguel, CA 92677       | (949) 348-9600     |                  | Southern California<br>Fire Protection, Inc.<br>(949) 348-9600     | (949) 348-9600  | L        | YES                                      | 10/27/2009<br>FINALED<br>10/27/2009             | 33.615723 | -117.70568  |
| 8/24/2009     | 51454                            |                                      | 22365            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Sewer Repair   | Commercial         |                      | 8/24/2009                  |                          | Sycamore Plaza<br>Tenants In Common<br>(Owner)   | P.O. Box 50847<br>Irvine, CA 92619                     | (949) 748-7030     |                  | Sycamore Plaza<br>Tenants In Common<br>(949) 748-7030              | Sycamore Plaza<br>Tenants In Common<br>(949) 748-7030       | L        | YES                                      | 8/24/2009<br>FINALED<br>8/24/2009               | 33.637842 | -117.679363 |
| 9/1/2009      | 51498                            |                                      | 22371            | El Toro             | Road             | А     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Underground<br>Plumbing Repair<br>Install New                    | Commercial         |                      | 9/1/2009                   |                          | Drainex Rooter &<br>Plumbing Company             | 840 S. Kenmore Street<br>Anaheim, CA 92804             | (714) 995-2996     |                  | Drainex Rooter<br>(714) 995-2996<br>Charles E. Thomas              | Drainex Rooter<br>(714) 995-2996<br>Charles E. Thomas       | L        | YES                                      | 9/3/2009<br>FINALED<br>9/28/2009<br>10/22/2009  | 33.637716 | -117.679539 |
| 9/21/2009     | 51622                            | 76 Station                           | 23391            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | VST Unit &<br>Screen Wall  | Commercial         | Footings             | 9/21/2009                  |                          | Charles E. Thomas<br>Company, Inc.               | 13701 S. Alma Avenue<br>Gardena, CA 90249              | (310) 323-6730     |                  | Company, Inc.<br>(310) 323-6730<br>Alpha Omega                     | Company, Inc.<br>(310) 323-6730<br>Alpha Omega              | L        | YES                                      | FINALED<br>10/23/2009<br>2/23/2010              | 33.623511 | -117.697194 |
| 10/7/2009     | 51727                            | Verizon Wireless                     | 21991 1/4        | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Cell Site - Equip.<br>Room (264 SF), New<br>Light Pole, Antennas | Commercial         | Footings             | 10/7/2009                  |                          | Alpha Omega<br>Construction                      | 25051 Earhart Road<br>Laguna Hills, CA 92653           | (949) 922-8925     |                  | Construction<br>(949) 922-8925                                     | Construction<br>(949) 922-8925                              | L        | YES                                      | FINALED<br>6/18/2010                            | 33.643375 | -117.667869 |
| 12/23/2009    | 52243                            | Saddleback Church                    | 1                | Saddleback          | Parkway          | ,     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Prefabricated<br>Walk-in & Freezer<br>at Student Zone            | Commercial         | Footings             | 12/23/2009                 |                          | Saddleback Church                                | 1 Saddleback Parkway<br>Lake Forest, CA 92630          | (949) 400-4534     |                  | Saddleback Church<br>(949) 400-4534                                | Saddleback Church<br>(949) 400-4534                         | L        | YES                                      | 8/27/2010                                       | 33.662103 | -117.651928 |
| 12/23/2009    | 52247                            | Jack-in-the-Box                      | 23812            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Install Larger<br>Grease Interceptor                             | Commercial         |                      | 12/23/2009                 |                          | Jerry Foster<br>Plumbing                         | P.O. Box 369<br>Alpine, CA 91903                       | (619) 405-9925     |                  | Jerry Foster Plumbing<br>(619) 405-9925                            | g Jerry Foster Plumbing<br>(619) 405-9925                   | L        | YES                                      | 1/12/2010<br>FINALED<br>1/12/2010               | 33.616569 | -117.705045 |
| 3/17/2010     | 1201                             | Verizon                              | 25017            | Whisler             | Drive            |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Cell Site -<br>Includes<br>Generator & Pad                       | Commercial         | Footings             | 3/17/2010                  |                          | Bay City<br>Electric Works                       | 12208 Industry Road<br>Lakeside, CA 92040              | (619) 938-8200     |                  | Bay City<br>Electric Works<br>(619) 938-8200                       | Bay City<br>Electric Works<br>(619) 938-8200                | L        | YES                                      | 3/25/2010<br>FINALED<br>4/6/2010                | 33.624657 | -117.694087 |
| 3/24/2010     | 1234                             | Clearwire                            | 23122            | El Toro<br>Frontage | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Cell Site  | Commercial         |                      | 3/24/2010                  |                          | Diversified<br>Communications<br>Services, Inc.  | 11944 Baker Place<br>Santa Fe Springs, CA 90670        | (562) 696-9660     |                  | Diversified<br>Communications<br>(562) 696-9660                    | Diversified<br>Communications<br>(562) 696-9660             | L        | YES                                      | 4/6/2010  | 33.625684 | -117.693753 |
| 3/25/2010     | 1240                             | Big Shots Billiards                  | 23512            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Sewer Repair<br>(4"=134' & 3'=16')                               | Commercial         |                      | 3/25/2010                  |                          | Julian Camacho<br>Plumbing                       | 11114 Walnut Street<br>El Monte, CA 91731              | (626) 443-0449     |                  | Julian Camacho<br>Plumbing<br>(626) 443-0449                       | Julian Camacho<br>Plumbing<br>(626) 443-0449                | L        | YES                                      | 3/26/2010<br>FINALED<br>3/26/2010               | 33.621354 | -117.699151 |
| 4/28/2010     | 1327                             | Sprint                               | 28610 1/2        | Icon                |                  |       | Foothil<br>Ranch | CA    | 92610 |                 | < 1                      | NA             | Cell Site  | Commercial         |                      | 4/28/2010                  |                          | Inland Valley<br>Construction                    | 18382 Slover Avenue<br>Bloomington, CA 92316           | (909) 875-2112     |                  | Inland Valley<br>Construction<br>(909) 875-2112                    | Inland Valley<br>Construction<br>(909) 875-2112             | L        | NO<br>(Work Activities<br>Not Initiated) | Work Activities<br>Not Initiated<br>(Extension) | 33.67124  | -117.643459 |
| 4/26/2010     | 1458<br>1459                     |                                      | 23861            | El Toro             | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | ATM Canopy &<br>Light Poles                                      | Commercial         | Footings             | 4/26/2010                  |                          | Superior<br>Construction                         | 14 Calle Altea<br>San Clemente, CA 92673               | (949) 584-9588     |                  | Mark Kalez<br>Superior Construction<br>(949) 584-9588<br>Bob Lloyd | Mark Kalez  Superior Construction (949) 584-9588  Bob Lloyd | L        | YES                                      | 5/24/2010<br>FINALED<br>5/27/2010<br>5/27/2010  | 33.615957 | -117.706441 |
| 5/4/2010      | 1506                             | Heroes Park                          | 25420            | Jeronimo            | Road             |       | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Stand (410 SF) &<br>Patio Cvr(138 SF)                            | Commercial         | Footings             | 5/4/2010                   |                          | Hondo Company                                    | 2121 S. Lyon Street<br>Santa Ana, CA 92750             | (714) 525-0363     |                  | Hondo Company<br>(714) 525-0363<br>Gregg Trickett                  | Hondo Company<br>(714) 525-0363<br>Gregg Trickett           | L        | YES                                      | 6/10/2010<br>7/7/2010                           | 33.625465 | -117.687453 |
| 6/10/2010     | 1768                             | The Habit Burger<br>Grill            | 23632            | El Toro             | Road             | А     | Lake<br>Forest   | CA    | 92630 |                 | < 1                      | NA             | Trellis (364 SF)   | Commercial         | Footings             | 6/10/2010                  |                          | Oranco Development                               | 3190-D Airport Loop Drive<br>Costa Mesa, CA 92626      | (714) 432-1199     |                  | Oranco Development<br>(714) 432-1199                               |   | L        | YES                                      | 6/24/2010<br>FINALED<br>6/24/2010               | 33.619265 | -117.701736 |

Page 1 of 1 11/10/2010

# NPDES Construction Facilities Inventory - Residential Projects ALISO CREEK WATERSHED (SDRWQCB) Year 2009-2010

|               | Grading/             |                 |                  |                             |                        |                   |       |       |                 | Total           |                |  |                    |                         |                            |                          |                                     |  |                    |                   |  |  |          | Inspected for<br>Erosion and |                                 |           |             |
|---------------|----------------------|-----------------|------------------|-----------------------------|------------------------|-------------------|-------|-------|-----------------|-----------------|----------------|--|--------------------|-------------------------|----------------------------|--------------------------|-------------------------------------|--|--------------------|-------------------|--|--|----------|------------------------------|---------------------------------|-----------|-------------|
| Issue<br>Date | Building<br>Permit # | Project<br>Name | Street<br>Number | Street<br>Name              | Street<br>Suffix Suite | City              | State |       | Tract<br>lumber | Site<br>Acreage | WDID<br>Number | Description<br>of Project                            | Type of<br>Project | Source<br>Activities    | Construction<br>Start Date | Construction<br>End Date | Developer<br>Name                   | Developer<br>Address                                   | Developer<br>Phone | Developer<br>Fax  | Developer<br>Onsite Contact                          | Responsible Party or<br>Emergency Contact              | Priority | Sediment<br>Control?         | Inspection<br>Date<br>8/11/2009 | Lat       | Lon         |
| 7/6/2007      | 46454                | Summit Crest    | Tract<br>#16886  | Tract #16886                |                        | Lake<br>Forest    | CA    | 92630 | 16886           | 6.1             | 930C345317     | Residential  | Residential        | Grading                 | 6/25/2007                  | 12/00/08                 | Atherton-Newport<br>Fund 121, LLC   | 4 Park Plaza, Suite 1050<br>Irvine, CA 92614           | (949) 833-1411     | (949)<br>833-1511 | Sean Finnegan<br>(949) 833-1411<br>Kenneth M. Keller | Jeff Lloyd<br>(714) 751-5557 x247<br>Kenneth M. Keller | М        | YES                          | 9/9/2009<br>1/4/2010            | 33.661061 | -117.691569 |
| 7/1/2009      | 51150                |                 | 22982            | Springwater                 |                        | Lake<br>Forest    | CA    | 92630 |                 | <1              | NA             | In-Ground Spa  | Residential        | Steel<br>Reinforcements | 7/1/2009                   |                          | Crystal Pools & Spas                | 1040 W. Katella Avenue, #D<br>Orange, CA 92867         | (714) 747-2041     |                   | Crystal Pools & Spas<br>(714) 747-2041               | Crystal Pools & Spas<br>(714) 747-2041                 | L        | YES                          | 7/14/2009                       | 33.628877 | -117.686409 |
| 7/27/2009     | 51302                |                 | 26426            | Pebble Creek                |                        | Lake<br>Forest    | CA    | 92630 |                 | < 1             | NA             | Room Additions (826 SF)<br>& Balcony (90 SF)         | Residential        | Footings                | 7/27/2009                  |                          | Chris McNinch<br>(Homeowner)        | 26426 Pebble Creek<br>Lake Forest, CA 92630            | (949) 295-0509     |                   | Chris McNinch<br>(949) 295-0509                      | Chris McNinch<br>(949) 295-0509                        | L        | YES                          | 8/14/2009                       | 33.638056 | -117.669693 |
| 7/29/2009     | 51324                |                 | 25846            | Greenhill                   |                        | Lake<br>Forest    | CA    | 02620 |                 | < 1             | NA             | 6' Retaining Wall (265 SF)                           | Residential        | Footings                | 7/29/2009                  |                          | Leonard Wittrock<br>(Homeowner)     | 25846 Greenhill<br>Lake Forest, CA 92630               | (949) 460-0325     |                   | Leonard Wittrock<br>(949) 460-0325                   | Leonard Wittrock<br>(949) 460-0325                     |          | YES                          | 9/2/2009                        | 33.631836 | -117.679342 |
|               |                      |                 |                  |                             |                        | Lake              |       | 32030 |                 |                 |                | ,              |                    |                         |                            |                          | Andrea Twork                        | 26035 Fallbrook  |                    |                   | Andrea Twork   | Andrea Twork   |          |                              |                                 |           |             |
| 8/12/2009     | 51391                |                 | 26035            | Fallbrook                   |                        | Forest            | CA    | 92630 |                 | < 1             | NA             | Room Additions (1,193 SF)                            | Residential        | Footings                | 8/12/2009                  |                          | (Homeowner)<br>Lake Forest          | Lake Forest, CA 92630                                  | (949) 981-7360     |                   | (949) 981-7360<br>Jim Montgomery                     | (949) 981-7360<br>Jim Montgomery                       | L        | YES                          | 9/14/2009                       | 33.634284 | -117.676139 |
| 8/20/2009     | 51442                | Summit Crest    | 2                | Summit Pointe               |                        | Lake<br>Forest    | CA    | 02620 | 16886           | - 1             | NA             | Retaining Walls (1,320 SF)                           | Residential        | Footings                | 8/20/2009                  |                          | Summit Crest, LLC<br>(Owner)        | 19100 Von Karman Ave., #400<br>Irvine, CA 92612        | (949) 477-9550     |                   | L.F. SummitCrest,LLC<br>(949) 477-9550               | L.F. SummitCrest,LLC<br>(949) 477-9550                 |          | YES                          | 12/14/2009<br>3/17/2010         | 33.661047 | -117.691659 |
|               | 51495                | Cultillik Cross | 19682            | -                           |                        | Trabuco           | CA    | 02000 | 10000           | 21              |                |  |                    | 1 ootiiigo              |                            |                          | T. Rex Thomas                       | 19682 Torres Way                                       | (949) 713-3997     |                   | T. Rex Thomas  | T. Rex Thomas  |          | YES                          | 9/2/2009                        | 33 62095  |             |
| 9/1/2009      | 51495                |                 | 19682            | Torres                      | Way                    | Canyon            | CA    | 92679 |                 | <1              | NA             | Demo In-Ground Pool                                  | Residential        |                         | 9/1/2009                   |                          | (Homeowner)<br>Mission Landscape 8  | Trabuco Canyon, CA 92679                               | (949) /13-399/     |                   | (949) 713-3997<br>Mission Landscape &                | (949) 713-3997<br>Mission Landscape &                  | L        | YES                          | 9/2/2009                        | 33.62095  | -117.57298  |
| 9/8/2009      | 51514                |                 | 22032            | Elsberry                    | Way                    | Lake<br>Forest    | CA    | 92630 |                 | < 1             | NA             | Pool Remodel   | Residential        | Steel<br>Reinforcements | 9/8/2009                   |                          | Design Pools &<br>Spas              | 20381 Lake Forest Drive, #B-7<br>Lake Forest, CA 92630 | (714) 745-7796     |                   | Design - Pools & Spas<br>(714) 745-7796              | Design - Pools & Spas<br>(714) 745-7796                | L        | YES                          | 9/15/2009                       | 33.642996 | -117.67548  |
| 9/11/2009     | 51534                |                 | 24255            | Larkwood                    | Lane                   | Lake<br>Forest    | CA    | 02620 |                 | -1              | NA             | Sewer Repair -<br>Repair of Disposal System          | Residential        |                         | 9/11/2009                  |                          | Carmen Barragan<br>(Homeowner)      | 24255 Larkwood Lane<br>Lake Forest, CA 92630           | (949) 677-8473     |                   | Carmen Barragan<br>(949) 677-8473                    | Carmen Barragan<br>(949) 677-8473                      |          | YES                          | 9/14/2009                       | 33.610507 |             |
| 9/11/2009     | 31334                |                 | 24233            | Laikwood                    | Latte                  |                   | CA    | 92630 |                 | < 1             | INA            | Repail of Disposal System                            | Residential        |                         | 9/11/2009                  |                          | Lake Forest                         |  | (949) 677-0473     |                   | Jim Montgomery                                       | Jim Montgomery   | L        | 150                          | 9/15/2009                       | 33.610307 | -117.090001 |
| 9/14/2009     | 51548                | Summit Crest    |                  | Summit Pointe               |                        | Lake<br>Forest    | CA    | 92630 | 16886           | < 1             | NA             | Street Improvements Only                             | Residential        | Grading                 | 9/14/2009                  |                          | Summit Crest, LLC<br>(Owner)        | 19100 Von Karman Ave., #400<br>Irvine, CA 92612        | (949) 477-9550     |                   | L.F. SummitCrest,LLC<br>(949) 477-9550<br>Tim Austin | L.F. SummitCrest,LLC<br>(949) 477-9550<br>Tim Austin   | L        | YES                          | 12/1/2009<br>3/17/2010          | 33.62905  | -117.691249 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                |  |                    |                         |                            |                          | Austin Construction,                | 1018 River Lane  |                    |                   | Austin Construction                                  | Austin Construction                                    |          |                              |                                 |           |             |
| 9/21/2009     | 51611                |                 | 21822            | Shenandoah                  | Drive                  | Forest            | CA    | 92630 |                 | < 1             | NA             | Room Addition (66 SF)<br>Lighting System             | Residential        | Footings                | 9/21/2009                  |                          | Inc.<br>Lake Forest                 | Santa Ana, CA 92706                                    | (714) 543-0238     |                   | (714) 543-0238<br>Jim Montgomery                     | (714) 543-0238<br>Jim Montgomery                       | L        | YES                          | 10/27/2009                      | 33.64628  | -117.662695 |
| 9/22/2009     | 51630                | Summit Crest    | 1                | Summit Pointe               |                        | Lake<br>Forest    | CA    | 92630 | 16886           | -1              | NA             | (20 Light Fixtures &<br>3 Electric Services)         | Residential        |                         | 9/22/2009                  |                          | Summit Crest, LLC<br>(Owner)        | 19100 Von Karman Ave., #400<br>Irvine, CA 92612        | (949) 477-9550     |                   | L.F. SummitCrest,LLC<br>(949) 477-9550               | L.F. SummitCrest,LLC<br>(949) 477-9550                 |          | YES                          | 3/18/2010<br>4/7/2010           | 33.661061 | -117.691569 |
| UZEZZOO       |                      |                 |                  | Odminit i Omito             |                        | Lake              | Or t  | 02000 | 10000           | - ` '           | 101            |  |                    |                         | ULLILOUS                   |                          | Donald Patton                       | 307 Pirate Road  | (0.10) 0000        |                   | Donald Patton<br>Construction, Inc.                  | Donald Patton<br>Construction, Inc.                    |          | 120                          | 4///2010                        | 00.001001 | 117.001000  |
| 10/5/2009     | 51714                |                 | 21362            | Vista Estate                | Drive                  | Forest            | CA    | 92630 |                 | < 1             | NA             | Room Additions (560 SF)                              | Residential        | Footings                | 10/5/2009                  |                          | Construction, Inc.                  | Newport Beach, CA 92663                                | (949) 642-8696     |                   | (949) 642-8696                                       | (949) 642-8696   | L        | YES                          | 10/20/2009                      | 33.653235 | -117.664623 |
|               |                      |                 |                  |                             |                        | Trabuco           |       |       |                 |                 |                |  |                    | Steel                   |                            |                          | King Pool Design                    | 16728 Daisy Avenue                                     |                    |                   | Craig King<br>King Pool Design                       | Craig King<br>King Pool Design                         |          |                              |                                 |           |             |
| 10/7/2009     | 51723                |                 | 19232            | Red Bluff                   | Drive                  | Canyon            | CA    | 92679 |                 | <1              | NA             | Pool / Spa   | Residential        | Reinforcements          | 10/7/2009                  |                          | & Consulting<br>Steven Webb         | Fountain Valley, CA 92708<br>19052 Singingwood Circle  | (714) 448-6106     |                   | (714) 448-6106<br>Steven Webb                        | (714) 448-6106<br>Steven Webb                          | L        | YES                          | 10/21/2009                      | 33.62095  | -117.57298  |
| 10/20/2009    | 51799                |                 | 19052            | Singingwood                 | Circle                 | Canyon            | CA    | 92679 |                 | < 1             | NA             | Garden Wall (200 SF)                                 | Residential        | Footings                | 10/20/2009                 |                          | (Homeowner)                         | Trabuco Canyon, CA 92679                               | (951) 852-9904     |                   | (951) 852-9904                                       | (951) 852-9904   | L        | YES                          | 11/18/2009                      | 33.62095  | -117.57298  |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                |  |                    |                         |                            |                          | Budget Design &                     | 19528 Ventura Boulevard, #537                          |                    |                   | Budget Design &<br>Remodeling, Inc.                  | Budget Design &<br>Remodeling, Inc.                    |          |                              |                                 |           |             |
| 11/2/2009     | 51881                |                 | 22101            | Elsberry                    | Way                    | Forest<br>Trabuco | CA    | 92630 |                 | < 1             | NA             | Room Addition (93 SF)                                | Residential        | Footings                | 11/2/2009                  |                          | Remodeling, Inc.<br>Phoenix Pacific | Tarzana, CA 91356<br>1918 Nipomo Avenue                | (310) 280-6197     |                   | (310) 280-6197<br>Phoenix Pacific G.C.               | (310) 280-6197   | L        | YES                          | 12/1/2009                       | 33.641977 | -117.675599 |
| 11/6/2009     | 51939                |                 | 19422            | Jasper Hill                 | Road                   | Canyon            | CA    | 92679 |                 | < 1             | NA             | Room Additions (480 SF)                              | Residential        | Footings                | 11/6/2009                  |                          | General Contractors                 | Long Beach, CA 90815                                   | (562) 598-6917     |                   | (562) 598-6917                                       | (562) 598-6917   | L        | YES                          | 12/15/2009                      | 33.62095  | -117.57298  |
|               |                      |                 |                  |                             |                        | Trabuco           |       |       |                 |                 |                |  |                    | Steel                   |                            |                          | King Pool Design                    | 16728 Daisy Avenue                                     |                    |                   | Craig King<br>King Pool Design                       | Craig King<br>King Pool Design                         |          |                              |                                 |           |             |
| 11/9/2009     | 51963                |                 | 28382            | Quiet Hill                  | Lane                   | Canyon            | CA    | 92679 |                 | <1              | NA             | Pool / Spa<br>Room Additions (1,222 SF) &            | Residential        | Reinforcements          | 11/9/2009                  |                          | & Consulting                        | Fountain Valley, CA 92708                              | (714) 448-6106     |                   | (714) 448-6106<br>Elizabeth Sill                     | (714) 448-6106<br>Elizabeth Sill                       | L        | YES                          | 11/10/2009                      | 33.62095  | -117.57298  |
|               | 50044                |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | Porch (78 SF) &<br>Trellis (85 SF)                   | Beetleerel         | F                       |                            |                          | Clark Contractors,                  | 29602 Vista Terrace                                    | (0.40) 504 0577    |                   | Clark Contractors, Inc.                              | Clark Contractors, Inc.                                |          |                              |                                 |           |             |
| 11/17/2009    | 52014                |                 | 26421            | Belshire                    | Way                    | Forest            | CA    | 92630 |                 | <1              | NA             | Trellis (85 SF)                                      | Residential        | Footings                | 11/17/2009                 |                          | Inc.                                | Lake Forest, CA 92630                                  | (949) 581-6577     |                   | (949) 581-6577<br>John Rice                          | (949) 581-6577<br>John Rice                            | L        | YES                          | 12/21/2009                      | 33.647246 | -117.66982  |
| 11/23/2009    | 52062                |                 | 21451            | Moresby                     | Wav                    | Lake<br>Forest    | CA    | 92630 |                 | < 1             | NA             | Room Additions (230 SF)                              | Residential        | Footings                | 11/23/2009                 |                          | A-Plus Maintenance,<br>Inc.         | , 256 Rose Lane<br>Costa Mesa, CA 92627                | (949) 632-6028     |                   | A-Plus Maintenance<br>(949) 632-6028                 | A-Plus Maintenance<br>(949) 632-6028                   | L        | YES                          | 11/25/2009                      | 33.651249 | -117.669998 |
|               |                      |                 |                  |                             | ,                      | Lake              |       |       |                 |                 |                | New Single Family Home<br>(2.845 SF) & Garage        |                    |                         |                            |                          | Van Daele<br>Development            | 2900 Adams Street. Suite C-25                          | (0.10) 000 0000    |                   | Terri Moss<br>Van Daele Dev.Corp.                    | Terri Moss<br>Van Daele Dev.Corp.                      | _        |                              |                                 |           |             |
| 12/1/2009     | 52107                | Summit Crest    | 112              | Summit Pointe               |                        | Forest            | CA    | 92630 | 16886           | < 1             | NA             | (421 SF) & Porch (36 SF)                             | Residential        | Footings                | 12/1/2009                  |                          | Corporation                         | Riverside, CA 92504                                    | (951) 354-2121     |                   | (951) 354-2121 x)140                                 | (951) 354-2121 x)140                                   | L        | YES                          | 12/21/2009                      | 33.662522 | -117.693017 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | New Single Family Home<br>(2,449 SF) & Garage (424   |                    |                         |                            |                          | Van Daele<br>Development            | 2900 Adams Street, Suite C-25                          |                    |                   | Terri Moss<br>Van Daele Dev.Corp.                    | Terri Moss<br>Van Daele Dev.Corp.                      |          |                              |                                 |           |             |
| 12/1/2009     | 52108                | Summit Crest    | 114              | Summit Pointe               |                        | Forest            | CA    | 92630 | 16886           | < 1             | NA             | SF) & Porch (57 SF) New Single Family Home           | Residential        | Footings                | 12/1/2009                  |                          | Corporation<br>Van Daele            | Riverside, CA 92504                                    | (951) 354-2121     |                   | (951) 354-2121 x)140<br>Terri Moss                   | (951) 354-2121 x)140<br>Terri Moss                     | L        | YES                          | 12/21/2009                      | 33.662516 | -117.693002 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | (3,026 SF) & Garage                                  |                    |                         |                            |                          | Development                         | 2900 Adams Street, Suite C-25                          |                    |                   | Van Daele Dev.Corp.                                  | Van Daele Dev.Corp.                                    |          |                              |                                 |           |             |
| 12/1/2009     | 52109                | Summit Crest    | 116              | Summit Pointe<br>Osterman & |                        | Forest            | CA    | 92630 | 16886           | < 1             | NA             | (393 SF) & Porch (39 SF)                             | Residential        | Footings                | 12/1/2009                  |                          | Corporation<br>Van Daele            | Riverside, CA 92504                                    | (951) 354-2121     |                   | (951) 354-2121 x)140<br>Terri Moss                   | (951) 354-2121 x)140<br>Terri Moss                     | L        | YES                          | 12/21/2009                      | 33.66251  | -117.692986 |
| 12/7/2009     | 52139                | Summit Crest    |                  | Summit Crest<br>Drive       |                        | Lake<br>Forest    | CA    | 92630 | 16886           | < 1             | NA             | Project Site Sign<br>(Tract 16886)                   | Residential        | Footings                | 12/7/2009                  |                          | Development<br>Corporation          | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                   | Van Daele Dev.Corp.<br>(951) 354-2121 x)140          | Van Daele Dev.Corp.<br>(951) 354-2121 x)140            |          | YES                          | 12/23/2009                      | 33.656537 | -117 667498 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 | Same as        | (  |                    |                         |                            |                          | Lake Forest<br>Summit Crest, LLC    | 19100 Von Karman Ave., #400                            | (==:/, ==:=:=:     |                   | Jim Montgomery                                       | Jim Montgomery<br>L.F. SummitCrest.LLC                 |          |                              |                                 |           |             |
| 12/7/2009     | 52140                | Summit Crest    | 1                | Summit Pointe               |                        | Forest            | CA    | 92630 | 16886           | 6.5             | Above          | Precise Grading, Lots 1-29                           | Residential        | Grading                 | 12/7/2009                  |                          | (Owner)                             | Irvine, CA 92612                                       | (949) 477-9550     |                   | (949) 477-9550                                       | (949) 477-9550   | М        | YES                          | 12/23/2009                      | 33.661061 | -117.691569 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                |  |                    |                         |                            |                          | Richard Cohen<br>Landscape &        | 20795 Canada Road                                      |                    |                   | Richard Cohen<br>Landscape & Const.                  | Richard Cohen<br>Landscape & Const.                    |          |                              |                                 |           |             |
| 12/7/2009     | 52145                |                 | 21391            | Aliso                       | Court                  | Forest            | CA    | 92630 |                 | < 1             | NA             | Room Additions (571 SF)                              | Residential        | Footings                | 12/7/2009                  |                          | Construction, Inc.                  | Lake Forest, CA 92630                                  | (949) 768-0599     |                   | (949) 768-0599<br>Joe Garcia                         | (949) 768-0599<br>Joe Garcia                           | L        | YES                          | 12/23/2009                      | 33.651614 | -117.66318  |
| 40/40/0000    | 52214                |                 | 26421            | Belshire                    |                        | Lake              | CA    | 92630 |                 | < 1             | NA             | Retaining Walls (6'                                  | Residential        | F                       | 40/40/0000                 |                          | Joe Garcia                          | 7911 Holt Street                                       | (744) 745 5000     |                   | Construction (714)<br>715-5200                       | Construction (714)<br>715-5200                         |          | YES                          | 12/17/2009                      | 33.647246 | -117.66982  |
| 12/16/2009    |                      |                 |                  |                             | Way                    | Lake              |       |       |                 |                 |                | High: 100 LF)  |                    | Footings                | 12/16/2009                 |                          | Construction                        | Buena Park, CA 90621<br>27 Parterre                    | (714) 715-5200     |                   | John T. Ertz, Inc.                                   | John T. Ertz, Inc.                                     | L        |                              |                                 |           |             |
| 12/28/2009    | 52252                |                 | 21381            | Monterra                    |                        | Forest<br>Lake    | CA    | 92630 |                 | < 1             | NA             | Room Additions (430 SF)                              | Residential        | Footings                | 12/28/2009                 |                          | John T. Ertz, Inc.                  | Foothill Ranch, CA 92610<br>26307 Girard Street        | (949) 254-9194     |                   | (949) 254-9194<br>Robert E. Bullard                  | (949) 254-9194<br>Robert E. Bullard                    | L        | YES                          | 1/7/2010                        | 33.652805 | -117.668599 |
| 12/29/2009    | 52264                |                 | 21171            | Larchmont                   | Drive                  | Forest            | CA    | 92630 |                 | <1              | NA             | Room Addition (250 SF)                               | Residential        | Footings                | 12/29/2009                 |                          | Robert E. Bullard<br>Richard Cohen  | Hemet, CA 92544  | (951) 210-6535     |                   | (951) 210-6535<br>Richard Cohen                      | (951) 210-6535<br>Richard Cohen                        | L        | YES                          | 1/6/2010                        | 33.655472 | -117.657957 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | Room Addition (Additional 70                         |                    |                         |                            |                          | Landscape &                         | 20795 Canada Road                                      |                    |                   | Landscape & Const.                                   | Landscape & Const.                                     |          |                              |                                 |           |             |
| 1/4/2010      | 52284                |                 | 21391            | Aliso                       | Court                  | Forest            | CA    | 92630 |                 | <1              | NA             | SF - to BP #52145)                                   | Residential        | Footings                | 1/4/2010                   |                          | Construction, Inc.                  | Lake Forest, CA 92630                                  | (949) 768-0599     |                   | (949) 768-0599<br>EM Landscape                       | (949) 768-0599<br>EM Landscape                         | L        | YES                          | 1/29/2010                       | 33.651614 | -117.66318  |
| 1/6/2010      | 52290                |                 | 26362            | Ives                        | Wav                    | Lake<br>Forest    | CA    | 92630 |                 | < 1             | NA             | Pool / Spa   | Residential        | Steel<br>Reinforcements | 1/6/2010                   |                          | EM Landscape Pools<br>& Spas        | 17537 Deer Valley Court<br>Riverside, CA 92504         | (949) 547-2657     |                   | Pools & Spas<br>(949) 547-2657                       | Pools & Spas<br>(949) 547-2657                         |          | YES                          | 1/26/2010                       | 33.649585 | -117 670306 |
| 2/16/2010     | 52537                |                 | 21521            | Rushford                    | Drive                  | Lake              | CA    | 00000 |                 | < 1             | NA             | Gravity Wall (250 SF) &<br>Backyard Terrace / Paving | Residential        | Footings                | 2/16/2010                  |                          | Stephen J. Wayland<br>(Homeowner)   | 21521 Rushford Drive<br>Lake Forest, CA 92630          | (949) 637-9985     |                   | Stephen J. Wayland<br>(949) 637-9985                 | Stephen J. Wayland<br>(949) 637-9985                   | Ī.       | YES                          | 2/18/2010                       | 33.650174 |             |
| 2/16/2010     | 5253/                |                 | 21521            | Rushford                    | Drive                  | Forest            | CA    | 92630 |                 | <1              | NA             | Backyard Terrace / Paving                            | Residential        |                         | 2/16/2010                  |                          |                                     |  | (949) 637-9985     |                   | Aquanetic Pools                                      | Aquanetic Pools  | L        | YES                          | 2/18/2010                       | 33.650174 | -117.663979 |
| 2/18/2010     | 52567                |                 | 26261            | Danby                       | Way                    | Lake<br>Forest    | CA    | 92630 |                 | < 1             | NA             | Pool / Spa   | Residential        | Steel<br>Reinforcements | 2/18/2010                  |                          | Aquanetic Pools<br>& Spas           | 26081 Merit Circle, #111<br>Laguna Hills, CA 92653     | (949) 348-1667     |                   | & Spas<br>(949) 348-1667                             | & Spas<br>(949) 348-1667                               | L        | YES                          | 3/9/2010                        | 33.645963 | -117.672576 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | New Single Family Home<br>(3.026 SF) & Garage        |                    |                         |                            |                          | Van Daele<br>Development            | 2900 Adams Street. Suite C-25                          |                    |                   | Terri Moss<br>Van Daele Dev.Corp.                    | Terri Moss<br>Van Daele Dev.Corp.                      |          | -                            |                                 |           |             |
| 2/24/2010     | 1013                 | Summit Crest    | 102              | Summit Pointe               |                        | Forest            | CA    | 92630 | 16886           | < 1             | NA             | (393 SF) & Porch (39 SF)                             | Residential        | Footings                | 2/24/2010                  |                          | Corporation                         | Riverside, CA 92504                                    | (951) 354-2121     |                   | (951) 354-2121 x)140                                 | (951) 354-2121 x)140                                   | L        | YES                          | 3/25/2010                       | 33.662551 | -117.693094 |
|               |                      |                 |                  |                             |                        | Lake              |       |       |                 |                 |                | New Single Family Home<br>(3,026 SF) & Garage        |                    |                         |                            |                          | Van Daele<br>Development            | 2900 Adams Street, Suite C-25                          |                    |                   | Terri Moss<br>Van Daele Dev.Corp.                    | Terri Moss<br>Van Daele Dev.Corp.                      |          |                              |                                 |           |             |
| 2/24/2010     | 1018                 | Summit Crest    | 118              | Summit Pointe               |                        | Forest            | CA    | 92630 | 16886           | < 1             | NA             | (393 SF) & Porch (39 SF)<br>New Single Family Home   | Residential        | Footings                | 2/24/2010                  |                          | Corporation<br>Van Daele            | Riverside, CA 92504                                    | (951) 354-2121     |                   | (951) 354-2121 x)140<br>Terri Moss                   | (951) 354-2121 x)140<br>Terri Moss                     | L        | YES                          | 3/25/2010                       | 33.662502 | -117.692975 |
| 2/24/2010     | 1019                 | Summit Crest    | 400              | 0                           |                        | Lake              |       | 00000 | 40000           |                 |                | (3,026 SF) & Garage                                  | Residential        | Footings                | 0/04/0045                  |                          | Development                         | 2900 Adams Street, Suite C-25                          | (951) 354-2121     |                   | Van Daele Dev.Corp.<br>(951) 354-2121 x)140          | Van Daele Dev.Corp.                                    |          | VES                          | 0/05/004                        | 33 662446 | -117 602057 |
| 2/24/2010     | 1019                 | oummit Crest    | 120              | Summit Pointe               | L                      | Forest            | CA    | 92630 | 16886           | < 1             | NA             | (393 SF) & Porch (39 SF)                             | residential        | Footings                | 2/24/2010                  |                          | Corporation                         | Riverside, CA 92504                                    | (901) 354-∠121     |                   | (901) 354-2121 X)140                                 | (951) 354-2121 x)140                                   | Į L      | YES                          | 3/25/2010                       | 33.662446 | -117.692957 |

Page 1 of 3 11/10/2010

# NPDES Construction Facilities Inventory - Residential Projects ALISO CREEK WATERSHED (SDRWQCB) Year 2009-2010

|               |                                  |                 |        |                                       |                        |                   |       |       |                 |                          |                |  |              |                         |   |   |  |                    |                  |   |   |          | Inspected for           |            |           |              |
|---------------|----------------------------------|-----------------|--------|---------------------------------------|------------------------|-------------------|-------|-------|-----------------|--------------------------|----------------|--|--------------|-------------------------|---|---|--|--------------------|------------------|---|---|----------|-------------------------|------------|-----------|--------------|
| Issue<br>Date | Grading/<br>Building<br>Permit # | Project<br>Name | Street | Street<br>Name                        | Street<br>Suffix Suite | 0.11              |       |       | Tract<br>Number | Total<br>Site<br>Acreage | WDID<br>Number | Description  | Type of      | Source<br>Activities    | Construction<br>Start Date Construction | Developer                               | Developer<br>Address                                   | Developer<br>Phone | Developer<br>Fax | Developer<br>Onsite Contact                 | Responsible Party or                        |          | Erosion and<br>Sediment | Inspection |           |              |
| Date          | Permit #                         | Name            | Number | Name                                  | Suffix Suite           | Ony               | State | Zip   | Number          | Acreage                  | Number         | of Project New Single Family Home                  | Project      | Activities              | Start Date End Date                     | Name<br>Van Daele                       |  | Phone              | Fax              | Terri Moss                                  | Emergency Contact<br>Terri Moss             | Priority | Control?                | Date       | Lat       | Lon          |
| 2/24/2010     | 1027                             | Summit Crest    | 104    | Summit Pointe                         |                        | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | (2,449 SF) & Garage (424<br>SF) & Porch (57 SF)    | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                     | 3/25/2010  | 33.662545 | -117.693079  |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | New Single Family Home<br>(2,449 SF) & Garage (424 |              |                         |   | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                         |            |           |              |
| 2/24/2010     | 1031                             | Summit Crest    | 106    | Summit Pointe                         |                        | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | SF) & Porch (57 SF)                                | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/25/2010  | 33.662539 | -117.693063  |
| 2/24/2010     | 1042                             | Summit Crest    | 302    | Summit Crest                          | Drive                  | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | ١.       | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2,2-4,2010    | 1042                             | Cultural Cross  | 002    | Odminic Orobi                         | Diive                  | Lake              | 0,,   | DEGGG | 10000           | ٠,                       |                | Foundation Only                                    | recordential | 1 dottings              | 22-42010                                | Van Daele<br>Development                | 2900 Adams Street Suite C-25                           | (001) 004 2121     |                  | Terri Moss<br>Van Daele Dev Corp            | Terri Moss<br>Van Daele Dev Corp            | _        | 120                     | 0/1/2010   | 00.041040 | 117.00001    |
| 2/24/2010     | 1043                             | Summit Crest    | 304    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1044                             | Summit Crest    | 306    | Summit Crest                          | Drivo                  | Lake              | CA    | ດລອວດ | 16886           | -1                       | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.                         | ١.       | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1044                             | Sullillik Crest | 300    | Summit Crest                          | Dilve                  | Lake              | - CA  | 32030 | 10000           | ` '                      | INO            | Foundation Only                                    | residential  | 1 ootings               | 2/24/2010                               | Van Daele<br>Development                | 2900 Adams Street. Suite C-25                          | (931) 334-2121     |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           | -        | 123                     | 3/1/2010   | 33.041040 | -117.00031   |
| 2/24/2010     | 1045                             | Summit Crest    | 308    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  |   | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1046                             | Summit Crest    | 310    | Summit Crest                          | Drive                  | Lake<br>Forest    |       | 92630 | 16886           |                          | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | ١.       | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1046                             | Summit Crest    | 310    | Summit Crest                          | Drive                  | Lake              | CA    | 92630 | 16886           | < 1                      | NA             |  | Residential  | Poolings                | 2/24/2010                               | Van Daele                               | 2900 Adams Street. Suite C-25                          | (951) 354-2121     |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          | 155                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1047                             | Summit Crest    | 312    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation<br>Van Daele | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          |   | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | Foundation Only                                    |              |                         |   | Development                             | 2900 Adams Street, Suite C-25                          |                    |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.                         |          |                         |            |           |              |
| 2/24/2010     | 1048                             | Summit Crest    | 314    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1049                             | Summit Crest    | 305    | Summit Crest                          | Drive                  | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  |   | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | Foundation Only                                    |              |                         |   | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                         |            |           |              |
| 2/24/2010     | 1050                             | Summit Crest    | 303    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | Terri Moss                                  | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1051                             | Summit Crest    | 301    | Summit Crest                          | Drive                  | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | Foundation Only                                    |              |                         |   | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                         |            |           |              |
| 2/24/2010     | 1052                             | Summit Crest    | 214    | Summit Vista                          |                        | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1053                             | Summit Crest    | 212    | Summit Vista                          |                        | Lake<br>Forest    | CA    | 92630 | 16886           | -1                       | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 v)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | ١.       | YES                     | 3/1/2010   | 33.641648 | -117.6889    |
| 2,24,2010     |                                  |                 | 2,12   | Currini Vidia                         |                        | Lake              |       | OLOGO | 10000           |                          |                | Foundation Only                                    |              |                         | 22-12010                                | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          | (001) 004 2121     |                  | Terri Moss<br>Van Daele Dev Corn            | Terri Moss<br>Van Daele Dev Corn            | _        | 120                     | 0/1/2010   | 00.041040 | 117.0000     |
| 2/24/2010     | 1054                             | Summit Crest    | 210    | Summit Vista                          |                        | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1055                             | Summit Crest    | 208    | Summit Vista                          |                        | Lake<br>Forest    | C4    | 92630 | 16886           | . 4                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.                         | ١.       | YES                     | 3/1/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1033                             | Summit Crest    | 200    | Summit vista                          |                        | Lake              | CA    | 92030 | 10000           | < 1                      | INA            | Foundation Only                                    | residential  | 1 ootings               | 2/24/2010                               | Van Daele<br>Development                | 2900 Adams Street Suite C-25                           | (931) 334-2121     |                  | Terri Moss<br>Van Daele Dev Corn            | Terri Moss<br>Van Daele Dev Corn            |          | 153                     | 3/1/2010   | 33.041040 | -117.00091   |
| 2/24/2010     | 1056                             | Summit Crest    | 206    | Summit Vista                          |                        | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation                             | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          |   | L        | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
|               | 1057                             | Summit Crest    | 204    |                                       |                        | Lake<br>Forest    |       |       |                 |                          | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Van Daele<br>Development<br>Corporation | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |          | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1057                             | Summit Crest    | 204    | Summit Vista                          |                        |                   | CA    | 92630 | 16886           | <1                       | NA             |  | Residential  | Footings                | 2/24/2010                               | Van Daele                               |  | (951) 354-2121     |                  | Terri Moss                                  | Terri Moss                                  | L        | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1058                             | Summit Crest    | 202    | Summit Vista                          |                        | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | Foundation Only                                    |              |                         |   | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                         |            |           | l            |
| 2/24/2010     | 1059                             | Summit Crest    | 205    | Summit Vista                          |                        | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (New Single Family Home)                           | Residential  | Footings                | 2/24/2010                               | Corporation<br>Van Daele                | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | Terri Moss                                  | L        | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
| 2/24/2010     | 1060                             | Summit Crest    | 207    | Summit Vista                          |                        | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | Foundation Only<br>(New Single Family Home)        | Residential  | Footings                | 2/24/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |   | L        | YES                     | 3/3/2010   | 33.641648 | -117.68891   |
| 3/11/2010     | 1101                             |                 | 28581  | Camelback                             | Road                   | Trabuco<br>Canyon | CA    | 92679 |                 | < 1                      | NA             | Room Additions (217 SF)                            | Residential  | Footings                | 3/11/2010                               | Blue Ribbon<br>Design Build             | 26150 Enterprise Way, #100<br>Lake Forest, CA 92630    | (949) 586-6673     | 3                | Blue Ribbon Design<br>(949) 586-6673        | Blue Ribbon Design<br>(949) 586-6673        | L        | YES                     | 4/19/2010  | 33.62095  | -117.57298   |
| 3/16/2010     | 1184                             |                 | 24721  | Penfield                              | Street                 | Lake<br>Forest    | CA    | 92630 |                 | < 1                      | NA             | Demo Illegal<br>Room Addition (100 SF)             | Residential  |                         | 3/16/2010                               | Sabas Isquierdo<br>(Homeowner)          | 24721 Penfield Street<br>Lake Forest, CA 92630         | (949) 494-1741     |                  | Sabas Isquierdo<br>(949) 494-1741           | Sabas Isquierdo<br>(949) 494-1741           | L        | YES                     | 7/7/2010   | 33.612909 | -117.698101  |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | Retaining Wall (75 SF) &                           |              |                         |   | The Water                               | 28715 Los Alisos Blvd., #7-408                         |                    |                  | Mike Moses<br>Water Mgmt.Group              | Mike Moses<br>Water Mgmt.Group              |          |                         |            |           |              |
| 3/16/2010     | 1189                             |                 | 26261  | Danby                                 | Way                    | Forest            | CA    | 92630 |                 | < 1                      | NA             | Patio Cover (270 SF)                               | Residential  | Footings                | 3/16/2010                               | Management Group                        |  | (949) 589-0460     | )                | (949) 589-0460<br>Maureen McCann            | (949) 589-0460<br>Maureen McCann            | L        | YES                     | 3/25/2010  | 33.645963 | -117.67257   |
| 3/18/2010     | 1214                             |                 | 26491  | Summer Creek                          |                        | Lake<br>Forest    | CA    | 92630 |                 | < 1                      | NA             | Patio Enclosure (264 SF)                           | Residential  | Footings                | 3/18/2010                               | Patio Warehouse,<br>Inc.                | 1046 N. Tustin Street, Unit N<br>Orange, CA 92867      | (714) 771-6400     | )                | Patio Warehouse, Inc.<br>(714) 771-6400     | Patio Warehouse, Inc.<br>(714) 771-6400     | L        | YES                     | 4/19/2010  | 33.639312 | -117.668136  |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                |  |              |                         |   | Miguel Perez                            | 24092 Gemwood Drive                                    |                    |                  | Miguel Perez                                | Miguel Perez                                |          | NO<br>(No Work          | No Work    |           |              |
| 3/29/2010     | 1227                             |                 | 24092  | Gemwood                               | Drive                  | Forest<br>Lake    | CA    | 92630 |                 | < 1                      | NA             | Room Additions (2,412 SF)                          | Residential  | Footings                | 3/29/2010                               | (Homeowner)                             | Lake Forest, CA 92630<br>24000 Alicia Parkway, #17-243 | (949) 455-9875     | i                | (949) 455-9875<br>David Garza               | (949) 455-9875<br>David Garza               | L        | Activities)             | Activities | 33.612972 | -117.702289  |
| 3/24/2010     | 1231                             |                 | 25401  | Esrose                                | Court                  | Forest            | CA    | 92630 |                 | < 1                      | NA             | Room Additions (171 SF)                            | Residential  | Footings                | 3/24/2010                               | David Garza                             | Mission Viejo, CA 92691                                | (949) 378-9109     | )                | (949) 378-9109<br>David Penton              | (949) 378-9109<br>David Penton              | L        | YES                     | 3/30/2010  | 33.626178 | -117.686921  |
| 3/31/2010     | 1263                             |                 | 19241  | Jasper Hill                           | Road                   | Trabuco<br>Canvon | CA    | 92679 |                 | < 1                      | NA             | Pool / Spa   | Residential  | Steel<br>Reinforcements | 3/31/2010                               | Fluid Dynamics Poo<br>& Spa             | I 426 Del Monte West<br>Fullerton, CA 92832            | (714) 526-5117     | ,                | Fluid Dynamics Pool<br>(714) 526-5117       | Fluid Dynamics Pool<br>(714) 526-5117       | ١.       | YES                     | 5/3/2010   | 33 62095  | -117 57298   |
|               |                                  |                 |        | , , , , , , , , , , , , , , , , , , , |                        | Lake              |       |       |                 |                          |                |  |              |                         |   | Coppola                                 | 21842 Bass Lake Circle                                 |                    |                  | Rob Coppola<br>Coppola Construction         | Rob Coppola<br>Coppola Construction         |          |                         |            | ,         |              |
| 4/15/2010     | 1165                             |                 | 21672  | Montbury                              | Drive                  | Forest            | CA    | 92630 |                 | < 1                      | NA             | Room Addition (99 SF)                              | Residential  | Footings                | 4/15/2010                               | Construction                            | Lake Forest, CA 92630                                  | (949) 282-9881     | 1                | (949) 282-9881<br>Roger Stalmer             | (949) 282-9881<br>Roger Stalmer             | L        | YES                     | 4/21/2010  | 33.648529 | -117.666348  |
| 4/8/2010      | 1302                             |                 | 21656  | Fernleaf                              | Drive                  | Lake<br>Forest    | CA    | 92630 |                 | < 1                      | NA             | Remodel & Replaster<br>Swimming Pool               | Residential  |                         | 4/8/2010                                | California Pools<br>& Spas              | 970 N. Tustin Avenue, #200<br>Anaheim, CA 92807        | (714) 575-9286     | ,                | California Pools&Spas<br>(714) 575-9286     |   |          | YES                     | 4/22/2010  | 33.648337 | -117,67581   |
|               | .502                             |                 |        |                                       |                        | Lake              | 571   |       |                 |                          |                | New Single Family Home<br>(2,845 SF) & Garage      |              |                         |   | Van Daele<br>Development                | 2900 Adams Street Suite C-25                           | , 570 0200         |                  | Terri Moss<br>Van Daele Dev Corn            | Terri Moss<br>Van Daele Dev Corn            |          | 0                       |            | 10001     |              |
| 4/22/2010     | 1381                             | Summit Crest    | 304    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (421 SF) & Porch (36 SF)                           | Residential  | Footings                | 4/22/2010                               | Corporation                             | Riverside, CA 92504                                    | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Shaun Robinson      |   | L        | YES                     | 5/19/2010  | 33.641648 | -117.68891   |
| 4/20/2010     | 1390                             |                 | 21671  | Montbury                              | Drive                  | Lake<br>Forest    | CA    | 02620 |                 | < 1                      | NA             | Swimming Pool Remodel                              | Residential  |                         | 4/20/2010                               | Alan Smith<br>Pool Plastering           | 227 W. Carleton  | (714) 628-9494     |                  | AlanSmith PoolPlaster<br>(714) 628-9494     | AlanSmith PoolPlaster<br>(714) 628-9494     | ١.       | YES                     | 6/21/2010  | 33.648727 | -117.666571  |
| 4/2U/2U1U     | 1390                             |                 | 210/1  | wontbury                              | Dilve                  | Forest            | CA    | 3203U |                 | < 1                      | ΝA             | New Single Family Home<br>(3.026 SF) & Garage      | Residential  |                         | *r/ZU/ZU IU                             | Van Daele                               | Orange, CA 92867<br>2900 Adams Street. Suite C-25      | (7 14) 028-9494    |                  | Terri Moss<br>Van Daele Dev Corn            | Terri Moss<br>Van Daele Dev Corn            | L        | 155                     | a/21/2010  | J3.048/2/ | -117.0000.71 |
| 4/22/2010     | 1403                             | Summit Crest    | 301    | Summit Crest                          | Drive                  | Lake<br>Forest    | CA    | 92630 | 16886           | < 1                      | NA             | (393 SF) & Porch (39 SF)                           | Residential  | Footings                | 4/22/2010                               | Development<br>Corporation              | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504   | (951) 354-2121     |                  | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                     | 5/19/2010  | 33.641648 | -117.68891   |
|               |                                  |                 |        |                                       |                        | Lake              |       |       |                 |                          |                | New Single Family Home<br>(3,026 SF) & Garage      |              |                         |   | Van Daele<br>Development                | 2900 Adams Street, Suite C-25                          |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           | ١.       |                         |            |           | l            |
| 4/22/2010     | 1404                             | Summit Crest    | 302    | Summit Crest                          | Drive                  | Forest            | CA    | 92630 | 16886           | < 1                      | NA             | (393 SF) & Porch (39 SF)                           | Residential  | Footings                | 4/22/2010                               | Corporation                             | Riverside, CA 92504                                    | (951) 354-2121     | 1                | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                     | 5/19/2010  | 33.641648 | -117.68891   |

Page 2 of 3 11/10/2010

# NPDES Construction Facilities Inventory - Residential Projects ALISO CREEK WATERSHED (SDRWQCB) Year 2009-2010

|               | Grading/             |                 |                  |                |                  |       |                |        |                | To    | otal                    |  |                    |                      |                            |                          |                                 |  |                    |                  |   |   |          | Inspected for<br>Erosion and |                    |           |             |
|---------------|----------------------|-----------------|------------------|----------------|------------------|-------|----------------|--------|----------------|-------|-------------------------|--|--------------------|----------------------|----------------------------|--------------------------|---------------------------------|--|--------------------|------------------|---|---|----------|------------------------------|--------------------|-----------|-------------|
| Issue<br>Date | Building<br>Permit # | Project<br>Name | Street<br>Number | Street<br>Name | Street<br>Suffix | Suite | City           | State  | Tr.<br>Cip Nur |       | ite WDID<br>eage Number | Description of Project                               | Type of<br>Project | Source<br>Activities | Construction<br>Start Date | Construction<br>End Date | Developer<br>Name               | Developer<br>Address                                 | Developer<br>Phone | Developer<br>Fax | Developer<br>Onsite Contact                 | Responsible Party or<br>Emergency Contact   | Priority | Sediment<br>Control?         | Inspection<br>Date | Lat       | Lon         |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(3.026 SF) & Garage        |                    |                      |                            |                          | Van Daele<br>Development        | 2900 Adams Street, Suite C-25                        |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 4/22/2010     | 1405                 | Summit Crest    | 306              | Summit Crest   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 < | 1 NA                    | (393 SF) & Porch (39 SF)                             | Residential        | Footings             | 4/22/2010                  |                          | Corporation                     | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(3,026 SF) & Garage        |                    |                      |                            |                          | Van Daele<br>Development        | 2900 Adams Street, Suite C-25                        |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 4/22/2010     | 1406                 | Summit Crest    | 314              | Summit Crest   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 4 | : 1 NA                  | (393 SF) & Porch (39 SF)<br>New Single Family Home   | Residential        | Footings             | 4/22/2010                  |                          | Corporation<br>Van Daele        | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | (2,449 SF) & Garage (4                               |                    |                      |                            |                          | Development                     | 2900 Adams Street, Suite C-25                        |                    |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.                         |          |                              |                    |           |             |
| 4/22/2010     | 1419                 | Summit Crest    | 303              | Summit Crest   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 < | : 1 NA                  | SF) & Porch (57 SF)  New Single Family Home          | Residential        | Footings             | 4/22/2010                  |                          | Corporation<br>Van Daele        | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
| 4/22/2010     | 1420                 | Summit Crest    | 312              | Summit Crest   | Drive            |       | Lake           | CA 9:  | 630 16         | 386 4 | 1 NA                    | (2,449 SF) & Garage (4:<br>SF) & Porch (57 SF)       | 24<br>Residential  | F                    | 4/22/2010                  |                          | Development<br>Corporation      | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |          | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
| 4/22/2010     | 1420                 | Summit Crest    | 312              | Summit Crest   | Dilve            |       |                | CA 9.  | 030 10         | 000 < | I INA                   | New Single Family Home                               | Residential        | Footings             | 4/22/2010                  |                          | Van Daele                       |  | (951) 354-2121     |                  | Terri Moss                                  | Terri Moss                                  | L        | 150                          | 3/19/2010          | 33.041040 | -117.00091  |
| 4/22/2010     | 1429                 | Summit Crest    | 305              | Summit Crest   | Drive            |       | Lake           | CA 9   | 630 16         | 386 < | . 1 NA                  | (2,845 SF) & Garage<br>(421 SF) & Porch (36 SF)      | Residential        | Footings             | 4/22/2010                  |                          | Development<br>Corporation      | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |          | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
| 4/LE/LOTO     | 1425                 | Commit Cross    | 000              | Odminik Orobi  | Diive            |       |                | 0/1 0/ | 000 10         | ,     | 101                     | New Single Family Home                               | recordenia         | 1 ooungo             | 4/LE/LOTO                  |                          | Van Daele                       |  | (001) 004 2121     |                  | Terri Moss                                  | Terri Moss                                  | _        | 120                          | 0/10/2010          | 00.041040 | 117.00001   |
| 4/22/2010     | 1430                 | Summit Crest    | 308              | Summit Crest   | Drive            |       | Lake<br>Forest | CA 9:  | 630 16         | 386 < | 1 NA                    | (2,845 SF) & Garage<br>(421 SF) & Porch (36 SF)      | Residential        | Footings             | 4/22/2010                  |                          | Development<br>Corporation      | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(2,845 SF) & Garage        |                    | _                    |                            |                          | Van Daele<br>Development        | 2900 Adams Street, Suite C-25                        |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 4/22/2010     | 1431                 | Summit Crest    | 310              | Summit Crest   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 . | 1 NA                    | (421 SF) & Porch (36 SF)                             | Residential        | Footings             | 4/22/2010                  |                          | Corporation                     | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                          | 5/19/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         |  |                    |                      |                            |                          | Antonio Cortez                  | 24361 Bridger Road                                   |                    |                  | Antonio Cortez                              | Antonio Cortez                              |          | NO<br>(No Work               | No Work            |           |             |
| 5/6/2010      | 1461                 |                 | 24361            | Bridger        | Road             |       | Forest         | CA 92  | 630            |       | 1 NA                    | Room Additions (688 SF)                              | Residential        | Footings             | 5/6/2010                   |                          | (Homeowner)                     | Lake Forest, CA 92630                                | (949) 472-9804     | ı                | (949) 472-9804                              | (949) 472-9804                              | L        | Activities)                  | Activities         | 33.611951 | -117.703597 |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | Demo Unpermitted                                     |                    |                      |                            |                          | John Kabbani                    | 21062 Larchmont Drive                                |                    |                  | John Kabbani                                | John Kabbani                                |          | NO<br>(No Work               | No Work            |           |             |
| 5/5/2010      | 1513                 |                 | 21062            | Larchmont      | Drive            |       | Forest         | CA 92  | 630            |       | : 1 NA                  | Living Area (225 SF) New Single Family Home          | Residential        |                      | 5/5/2010                   |                          | (Homeowner)<br>Van Daele        | Lake Forest, CA 92630                                | (949) 454-1449     | )                | (949) 454-1449<br>Terri Moss                | (949) 454-1449<br>Terri Moss                | L        | Activities)                  | Activities         | 33.656605 | -117.65702  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | (2,845 SF) & Garage                                  |                    |                      |                            |                          | Development                     | 2900 Adams Street, Suite C-25                        |                    |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.                         |          |                              |                    |           |             |
| 5/19/2010     | 1567                 | Summit Crest    | 214              | Summit Vista   | Drive            |       | Forest         | CA 92  | 630 16         | 386 < | :1 NA                   | (421 SF) & Porch (36 SF)<br>New Single Family Home   | Residential        | Footings             | 5/19/2010                  |                          | Corporation<br>Van Daele        | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                          | 6/1/2010           | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | (2,845 SF) & Garage                                  |                    |                      |                            |                          | Development                     | 2900 Adams Street, Suite C-25                        |                    |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.                         |          |                              |                    |           |             |
| 5/19/2010     | 1568                 | Summit Crest    | 202              | Summit Vista   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 < | 1 NA                    | (421 SF) & Porch (36 SF)<br>New Single Family Home   | Residential        | Footings             | 5/19/2010                  |                          | Corporation<br>Van Daele        | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                          | 6/1/2010           | 33.641648 | -117.68891  |
| 5/19/2010     | 1569                 | 0               | 005              | Summit Vista   | Drive            |       | Lake           | CA 9   | 630 16         | 386   | . 1 NA                  | (2,845 SF) & Garage<br>(421 SF) & Porch (36 SF)      | Residential        | F                    | 5/19/2010                  |                          | Development                     | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |          | YES                          | 6/1/2010           | 33 641648 | -117.68891  |
| 5/19/2010     | 1569                 | Summit Crest    | 205              | Summit vista   | Drive            |       | Forest         | CA 9.  | 150 150        | 586 < | 1 NA                    | New Single Family Home                               | Residential        | Footings             | 5/19/2010                  |                          | Corporation<br>Van Daele        |  | (951) 354-2121     |                  | Terri Moss                                  | Terri Moss                                  | L        | YES                          | 6/1/2010           | 33.641648 | -117.68891  |
| 5/19/2010     | 1604                 | Summit Crest    | 212              | Summit Vista   | Drive            |       | Lake<br>Forest | CA 9:  | 630 16         | 386 < | 1 NA                    | (3,026 SF) & Garage<br>(393 SF) & Porch (39 SF)      | Residential        | Footings             | 5/19/2010                  |                          | Development<br>Corporation      | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 |          | YES                          | 6/1/2010           | 33.641648 | -117.68891  |
| 0.70.2070     |                      |                 |                  |                |                  |       |                |        |                |       |                         | New Single Family Home                               |                    |                      |                            |                          | Van Daele                       |  | (001) 001212       |                  | Terri Moss                                  | Terri Moss                                  |          |                              |                    |           |             |
| 5/19/2010     | 1605                 | Summit Crest    | 208              | Summit Vista   | Drive            |       | Lake<br>Forest | CA 92  | 630 16         | 386   | 1 NA                    | (3,026 SF) & Garage<br>(393 SF) & Porch (39 SF)      | Residential        | Footings             | 5/19/2010                  |                          | Development<br>Corporation      | 2900 Adams Street, Suite C-25<br>Riverside, CA 92504 | (951) 354-2121     |                  | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | Van Daele Dev.Corp.<br>(951) 354-2121 x)140 | L        | YES                          | 7/2/2010           | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(3,026 SF) & Garage        |                    |                      |                            |                          | Van Daele<br>Development        | 2900 Adams Street, Suite C-25                        |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 5/19/2010     | 1606                 | Summit Crest    | 207              | Summit Vista   | Drive            |       | Forest         | CA 92  | 630 16         | 386 < | 1 NA                    | (393 SF) & Porch (39 SF)                             | Residential        | Footings             | 5/19/2010                  |                          | Corporation                     | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                          | 7/2/2010           | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(2,449 SF) & Garage (4)    | 24                 |                      |                            |                          | Van Daele<br>Development        | 2900 Adams Street Suite C-25                         |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 5/19/2010     | 1619                 | Summit Crest    | 210              | Summit Vista   | Drive            |       | Forest         | CA 92  | 630 16         | 386 < | :1 NA                   | SF) & Porch (57 SF)                                  | Residential        | Footings             | 5/19/2010                  |                          | Corporation                     | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140                        | (951) 354-2121 x)140                        | L        | YES                          | 7/2/2010           | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | New Single Family Home<br>(2,449 SF) & Garage (4.    | 24                 |                      |                            |                          | Van Daele<br>Development        | 2900 Adams Street, Suite C-25                        |                    |                  | Terri Moss<br>Van Daele Dev.Corp.           | Terri Moss<br>Van Daele Dev.Corp.           |          |                              |                    |           |             |
| 5/19/2010     | 1620                 | Summit Crest    | 206              | Summit Vista   | Drive            |       | Forest         | CA 92  | 630 16         | 386 < | : 1 NA                  | SF) & Porch (57 SF)<br>New Single Family Home        | Residential        | Footings             | 5/19/2010                  |                          | Corporation<br>Van Daele        | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Terri Moss          | (951) 354-2121 x)140<br>Terri Moss          | L        | YES                          | 7/13/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Lake           |        |                |       |                         | (2,449 SF) & Garage (4:                              | 24                 |                      |                            |                          | Development                     | 2900 Adams Street, Suite C-25                        |                    |                  | Van Daele Dev.Corp.                         | Van Daele Dev.Corp.                         |          |                              |                    |           |             |
| 5/19/2010     | 1621                 | Summit Crest    | 204              | Summit Vista   | Drive            |       | Forest         | CA 9:  | 630 16         | 386 < | : 1 NA                  | SF) & Porch (57 SF)                                  | Residential        | Footings             | 5/19/2010                  |                          | Corporation                     | Riverside, CA 92504                                  | (951) 354-2121     |                  | (951) 354-2121 x)140<br>Robert Loftus Rober |   | L        | YES                          | 7/13/2010          | 33.641648 | -117.68891  |
|               |                      |                 |                  |                |                  |       | Trabuco        |        |                |       |                         |  |                    |                      |                            |                          | Robert Loftus                   | 31103 Rancho Viejo Rd, #404                          |                    |                  | Loftus Const. (949)                         | Loftus Const. (949)                         |          |                              |                    |           |             |
| 5/24/2010     | 1667                 |                 | 28701            | Malabar        | Road             | -     | Canyon         | CA 9:  | 679            | *     | : 1 NA                  | Retaining Walls (504 SF)<br>Room Addition (270 SF) 8 |                    | Footings             | 5/24/2010                  |                          | Construction<br>Sabas Isquierdo | SanJuanCapistrano, CA 92675<br>24721 Penfield Street | (949) 310-0819     | 1                | 310-0819<br>Sabas Isquierdo                 | 310-0819<br>Sabas Isquierdo                 | L        | YES                          | 6/14/2010          | 33.62095  | -117.57298  |
| 6/28/2010     | 1683                 |                 | 24721            | Penfield       | Street           |       | Forest         | CA 9:  | 630            |       | : 1 NA                  | Patio Cover (313 SF)<br>Room Additions (449 SF)      | Residential        | Footings             | 6/28/2010                  |                          | (Homeowner)<br>Quang Nguyen     | Lake Forest, CA 92630<br>22665 Revere Road           | (949) 581-6033     | 3                | (949) 581-6033<br>Quang Nguyen              | (949) 581-6033<br>Quang Nguyen              | L        | YES                          | 7/7/2010           | 33.612909 | -117.698101 |
| 6/22/2010     | 1789                 |                 | 22665            | Revere         | Road             |       | Forest         | CA 9:  | 630            |       | 1 NA                    | SolidRoof Patio Cvr (169 S                           |                    | Footings             | 6/22/2010                  |                          | (Homeowner)                     | Lake Forest, CA 92630                                | (949) 458-0916     | 3                | (949) 458-0916                              | (949) 458-0916                              | L        | YES                          | 7/7/2010           | 33.633794 | -117.680781 |
|               |                      |                 |                  |                |                  |       | Trabuco        |        |                |       |                         |  |                    | Steel                |                            |                          | J.Q. Garcia                     | 25981 Cordillera Drive                               |                    |                  | Jaime Garcia<br>J.Q. Garcia Const.          | Jaime Garcia<br>J.Q. Garcia Const.          |          |                              |                    |           |             |
| 6/17/2010     | 1825                 |                 | 28362            | Harvest View   | Lane             |       | Canyon         | CA 92  | 679            |       | : 1 NA                  | Pool / Spa   | Residential        | Reinforcements       | 6/17/2010                  |                          | Construction                    | Mission Viejo, CA 92691                              | (949) 583-1991     |                  | (949) 583-1991                              | (949) 583-1991                              | L        | YES                          | 7/1/2010           | 33.62095  | -117.57298  |
|               |                      |                 |                  |                |                  |       | Trabuco        |        |                |       |                         |  |                    | Steel                |                            |                          | AquaScapes                      | 321 Calle Felicidad                                  |                    |                  | Paul Ellison<br>AquaScapes Pools            | Paul Ellison<br>AquaScapes Pools            |          |                              |                    |           |             |
| 6/29/2010     | 1894                 |                 | 19421            | Jasper Hill    | Road             |       | Canyon         | CA 9:  | 679            |       | : 1 NA                  | Pool / Spa   | Residential        | Reinforcements       | 6/29/2010                  |                          | Pools & Spas                    | San Clemente, CA 92672                               | (949) 492-7664     | 1                | (949) 492-7664<br>Steve Freese              | (949) 492-7664<br>Steve Freese              | L        | YES                          | 7/27/2010          | 33.62095  | -117.57298  |
|               | 4000                 |                 |                  | Managara       |                  |       | Lake           |        |                |       |                         | B. C. F. J   | B                  | Francis              |                            |                          | Capistrano                      | 26332 Paseo Toscana                                  |                    |                  | Capistrano Sunrooms                         | Capistrano Sunrooms                         | 1        |                              |                    |           |             |
| 6/30/2010     | 1906                 |                 | 21111            | Kensington     | Lane             |       | Forest         | CA 92  | 630            | 4     | :1 NA                   | Patio Enclosure (220 SF)                             | Residential        | Footings             | 6/30/2010                  |                          | Sunrooms                        | SanJuanCapistrano, CA 92675                          | (949) 307-9653     | 3                | (949) 307-9653                              | (949) 307-9653                              | L        | YES                          | 8/5/2010           | 33.656109 | -117.660674 |

Page 3 of 3 11/10/2010


# CITY OF LAKE FOREST PUBLIC WORKS CONTRACT INSPECTION PROJECT INVENTORY 2009-10

|   |              |   | 2009-10                               | ,       |          |                                |                              |
|---|--------------|---|---------------------------------------|---------|----------|--------------------------------|------------------------------|
|   | PROJECT ID # | PROJECT NAME                                      | PROJECT<br>LOCATION/ADDRESS           | ACREAGE | PRIORITY | WATERSHED                      | REGION                       |
| 1 | PW 2007.13   | Front Street and<br>Orange Street<br>Improvements | Front Street and Orange               | <1      | Medium   | Aliso Creek                    | San Diego                    |
| 2 | PW 2008.01   | ADA Access Ramp<br>Improvements                   | 28 locations throughout the City      | <1      | Low      | Aliso Creek and<br>Newport Bay | San Diego/<br>Newport<br>Bay |
| 3 | PW 2007.12   | Trabuco Rd Median<br>Nose at Lake Forest<br>Dr    | Trabuco Rd south of Lake<br>Forest Dr | <1      | Low      | Newport Bay                    | Santa Ana                    |
| 4 |              |   |                                       |         |          |                                |                              |
| 5 |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |
|   |              |   |                                       |         |          |                                |                              |

## Exhibit A-8.II

## Construction BMPs Fact Sheets





| Description | and | <b>Purpose</b> |
|-------------|-----|----------------|
|-------------|-----|----------------|

Scheduling is the development of a written plan that includes sequencing of construction activities and the implementation of BMPs such as erosion control and sediment control while taking local climate (rainfall, wind, etc.) into consideration. The purpose is to reduce the amount and duration of soil exposed to erosion by wind, rain, runoff, and vehicle tracking, and to perform the construction activities and control practices in accordance with the planned schedule.

#### Suitable Applications

Proper sequencing of construction activities to reduce erosion potential should be incorporated into the schedule of every construction project especially during rainy season. Use of other, more costly yet less effective, erosion and sediment control BMPs may often be reduced through proper construction sequencing.

#### Limitations

 Environmental constraints such as nesting season prohibitions reduce the full capabilities of this BMP.

#### **Implementation**

- Avoid rainy periods. Schedule major grading operations during dry months when practical. Allow enough time before rainfall begins to stabilize the soil with vegetation or physical means or to install sediment trapping devices.
- Plan the project and develop a schedule showing each phase

| Cat  | egories   |   |
|------|---|---|
| EC   | Erosion Control                                     | Ø |
| SE   | Sediment Control                                    | X |
| TC   | Tracking Control                                    | × |
| WE   | Wind Erosion Control                                | × |
| N\$  | Non-Stormwater<br>Management Control                |   |
| WM   | Waste Management and<br>Materials Pollution Control |   |
| Lege | ındı  |   |
| Ø 1  | Primary Objective                                   |   |
|      |   |   |

| Targeted Constituents |
|-----------------------|
|-----------------------|

☑ Secondary Objective

| Targeted Constituent | S |
|----------------------|---|
| Sediment             | ✓ |
| Nutrients            |   |
| Trash                |   |
| Metals               |   |
| Bacteria             |   |
| Oil and Grease       |   |
| Organics             |   |
|                      |   |

#### **Potential Alternatives**

None



of construction. Clearly show how the rainy season relates to soil disturbing and restabilization activities. Incorporate the construction schedule into the SWPPP.

- Include on the schedule, details on the rainy season implementation and deployment of:
  - Erosion control BMPs
  - Sediment control BMPs
  - Tracking control BMPs
  - Wind erosion control BMPs
  - Non-stormwater BMPs
  - Waste management and materials pollution control BMPs
- Include dates for activities that may require non-stormwater discharges such as dewatering, sawcutting, grinding, drilling, boring, crushing, blasting, painting, hydro-demolition, mortar mixing, pavement cleaning, etc.
- Work out the sequencing and timetable for the start and completion of each item such as site
  clearing and grubbing, grading, excavation, paving, foundation pouring utilities installation,
  etc., to minimize the active construction area during the rainy season.
  - Sequence trenching activities so that most open portions are closed before new trenching begins.
  - Incorporate staged seeding and re-vegetation of graded slopes as work progresses.
  - Schedule establishment of permanent vegetation during appropriate planting time for specified vegetation.
- Non-active areas should be stabilized as soon as practical after the cessation of soil disturbing activities or one day prior to the onset of precipitation.
- Monitor the weather forecast for rainfall.
- When rainfall is predicted, adjust the construction schedule to allow the implementation of soil stabilization and sediment treatment controls on all disturbed areas prior to the onset of rain.
- Be prepared year round to deploy erosion control and sediment control BMPs. Erosion may be caused during dry seasons by un-seasonal rainfall, wind, and vehicle tracking. Keep the site stabilized year round, and retain and maintain rainy season sediment trapping devices in operational condition.
- Apply permanent erosion control to areas deemed substantially complete during the project's defined seeding window.

#### Costs

Construction scheduling to reduce erosion may increase other construction costs due to reduced economies of scale in performing site grading. The cost effectiveness of scheduling techniques should be compared with the other less effective erosion and sedimentation controls to achieve a cost effective balance.


#### **Inspection and Maintenance**

- Verify that work is progressing in accordance with the schedule. If progress deviates, take corrective actions.
- Amend the schedule when changes are warranted.
- Amend the schedule prior to the rainy season to show updated information on the deployment and implementation of construction site BMPs.

#### References

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities Developing Pollution Prevention Plans and Best Management Practices (EPA 832-R-92-005), U.S. Environmental Protection Agency, Office of Water, September 1992.



#### **Description and Purpose**

Carefully planned preservation of existing vegetation minimizes the potential of removing or injuring existing trees, vines, shrubs, and grasses that protect soil from erosion.

#### **Suitable Applications**

Preservation of existing vegetation is suitable for use on most projects. Large project sites often provide the greatest opportunity for use of this BMP. Suitable applications include the following:

- Areas within the site where no construction activity occurs, or occurs at a later date. This BMP is especially suitable to multi year projects where grading can be phased.
- Areas where natural vegetation exists and is designated for preservation. Such areas often include steep slopes, watercourse, and building sites in wooded areas.
- Areas where local, state, and federal government require preservation, such as vernal pools, wetlands, marshes, certain oak trees, etc. These areas are usually designated on the plans, or in the specifications, permits, or environmental documents.
- Where vegetation designated for ultimate removal can be temporarily preserved and be utilized for erosion control and sediment control.

#### Limitations

Requires forward planning by the owner/developer,

#### Categories

C Erosion Control

 $\square$ 

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

**☒** Secondary Objective

#### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

None



contractor, and design staff.

- Limited opportunities for use when project plans do not incorporate existing vegetation into the site design.
- For sites with diverse topography, it is often difficult and expensive to save existing trees while grading the site satisfactory for the planned development.

#### **Implementation**

The best way to prevent erosion is to not disturb the land. In order to reduce the impacts of new development and redevelopment, projects may be designed to avoid disturbing land in sensitive areas of the site (e.g., natural watercourses, steep slopes), and to incorporate unique or desirable existing vegetation into the site's landscaping plan. Clearly marking and leaving a buffer area around these unique areas during construction will help to preserve these areas as well as take advantage of natural erosion prevention and sediment trapping.

Existing vegetation to be preserved on the site must be protected from mechanical and other injury while the land is being developed. The purpose of protecting existing vegetation is to ensure the survival of desirable vegetation for shade, beautification, and erosion control. Mature vegetation has extensive root systems that help to hold soil in place, thus reducing erosion. In addition, vegetation helps keep soil from drying rapidly and becoming susceptible to erosion. To effectively save existing vegetation, no disturbances of any kind should be allowed within a defined area around the vegetation. For trees, no construction activity should occur within the drip line of the tree.

#### Timing

Provide for preservation of existing vegetation prior to the commencement of clearing and grubbing operations or other soil disturbing activities in areas where no construction activity is planned or will occur at a later date.

#### Design and Layout

- Mark areas to be preserved with temporary fencing. Include sufficient setback to protect roots.
  - Orange colored plastic mesh fencing works well.
  - Use appropriate fence posts and adequate post spacing and depth to completely support the fence in an upright position.
- Locate temporary roadways, stockpiles, and layout areas to avoid stands of trees, shrubs, and grass.
- Consider the impact of grade changes to existing vegetation and the root zone.
- Maintain existing irrigation systems where feasible. Temporary irrigation may be required.
- Instruct employees and subcontractors to honor protective devices. Prohibit heavy equipment, vehicular traffic, or storage of construction materials within the protected area.

#### Costs

There is little cost associated with preserving existing vegetation if properly planned during the project design, and these costs may be offset by aesthetic benefits that enhance property values. During construction, the cost for preserving existing vegetation will likely be less than the cost of applying erosion and sediment controls to the disturbed area. Replacing vegetation inadvertently destroyed during construction can be extremely expensive, sometimes in excess of \$10,000 per tree.

#### **Inspection and Maintenance**

During construction, the limits of disturbance should remain clearly marked at all times. Irrigation or maintenance of existing vegetation should be described in the landscaping plan. If damage to protected trees still occurs, maintenance guidelines described below should be followed:

- Verify that protective measures remain in place. Restore damaged protection measures immediately.
- Serious tree injuries shall be attended to by an arborist.
- Damage to the crown, trunk, or root system of a retained tree shall be repaired immediately.
- Trench as far from tree trunks as possible, usually outside of the tree drip line or canopy. Curve trenches around trees to avoid large roots or root concentrations. If roots are encountered, consider tunneling under them. When trenching or tunneling near or under trees to be retained, place tunnels at least 18 in. below the ground surface, and not below the tree center to minimize impact on the roots.
- Do not leave tree roots exposed to air. Cover exposed roots with soil as soon as possible. If soil covering is not practical, protect exposed roots with wet burlap or peat moss until the tunnel or trench is ready for backfill.
- Cleanly remove the ends of damaged roots with a smooth cut.
- Fill trenches and tunnels as soon as possible. Careful filling and tamping will eliminate air spaces in the soil, which can damage roots.
- If bark damage occurs, cut back all loosened bark into the undamaged area, with the cut tapered at the top and bottom and drainage provided at the base of the wood. Limit cutting the undamaged area as much as possible.
- Aerate soil that has been compacted over a trees root zone by punching holes 12 in. deep with an iron bar, and moving the bar back and forth until the soil is loosened. Place holes 18 in. apart throughout the area of compacted soil under the tree crown.
- Fertilization
  - Fertilize stressed or damaged broadleaf trees to aid recovery.
  - Fertilize trees in the late fall or early spring.

- Apply fertilizer to the soil over the feeder roots and in accordance with label instructions, but never closer than 3 ft to the trunk. Increase the fertilized area by one-fourth of the crown area for conifers that have extended root systems.
- Retain protective measures until all other construction activity is complete to avoid damage during site cleanup and stabilization.

#### References


County of Sacramento Tree Preservation Ordinance, September 1981.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for The Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.

X



#### **Description and Purpose**

Hydraulic Mulch consists of various types of fibrous materials mixed with water and sprayed onto the soil surface in slurry form to provide a layer of temporary protection from wind and water erosion.

#### Suitable Applications

Hydraulic mulch as a temporary, stand alone, erosion control BMP is suitable for disturbed areas that require temporary protection from wind and water erosion until permanent soil stabilization activities commence. Examples include:

- Rough-graded areas that will remain inactive for longer than permit-required thresholds (e.g., 14 days) or otherwise require stabilization to minimize erosion or prevent sediment discharges.
- Soil stockpiles.
- Slopes with exposed soil between existing vegetation such as trees or shrubs.
- Slopes planted with live, container-grown vegetation or plugs.
- Slopes burned by wildfire.

Hydraulic mulch can also be applied to augment other erosion control BMPs such as:

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Eroslon Control

NS Non-Stormwater
Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

■ Secondary Category

#### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-4 Hydroseeding

EC-5 Soil Binders

EC-6 Straw Mulch

EC-7 Geotextiles and Mats

EC-8 Wood Mulching

EC-14 Compost Blanket

EC-16 Non-Vegetative Stabilization



- In conjunction with straw mulch (see EC-6 Straw Mulch) where the rate of hydraulic mulch is reduced to 100-500 lbs per acre and the slurry is applied over the straw as a tackifying agent to hold the straw in place.
- Supplemental application of soil amendments, such as fertilizer, lime, gypsum, soil biostimulants or compost.

#### Limitations

In general, hydraulic mulch is not limited by slope length, gradient or soil type. However, the following limitations typically apply:

- Most hydraulic mulch applications, particularly bonded fiber matrices (BFMs), require at least 24 hours to dry before rainfall occurs.
- Temporary applications (i.e., without a vegetative component) may require a second application in order to remain effective for an entire rainy season.
- Treatment areas must be accessible to hydraulic mulching equipment.
- Availability of water sources in remote areas for mixing and application.
- As a stand-alone temporary BMP, hydraulic mulches may need to be re-applied to maintain their erosion control effectiveness, typically after 6-12 months depending on the type of mulch used.
- Availability of hydraulic mulching equipment may be limited just prior to the rainy season and prior to storms due to high demand.
- Cellulose fiber mulches alone may not perform well on steep slopes or in course soils.

#### **Implementation**

- Where feasible, it is preferable to prepare soil surfaces prior to application by roughening embankments and fill areas with a crimping or punching type roller or by track walking.
- The majority of hydraulic mulch applications do not necessarily require surface/soil preparation (See EC-15 Soil Preparation) although in almost every case where re-vegetation is included as part of the practice, soil preparation can be beneficial. One of the advantages of hydraulic mulch over other erosion control methods is that it can be applied in areas where soil preparation is precluded by site conditions, such as steep slopes, rocky soils, or inaccessibility.
- Avoid mulch over spray onto roads, sidewalks, drainage channels, existing vegetation, etc.
- Hydraulic mulching is generally performed utilizing specialized machines that have a large water-holding/mixing tank and some form of mechanical agitation or other recirculation method to keep water, mulch and soil amendments in suspension. The mixed hydraulic slurry can be applied from a tower sprayer on top of the machine or by extending a hose to areas remote from the machine.

- Where possible apply hydraulic mulch from multiple directions to adequately cover the soil. Application from a single direction can result in shadowing, uneven coverage and failure of the BMP.
- Hydraulic mulch can also include a vegetative component, such as seed, rhizomes, or stolons (see EC-4 Hydraulic Seed).
- Typical hydraulic mulch application rates range from 2,000 pounds per acre for standard mulches (SMs) to 3,500 pounds per acre for BFMs. However, the required amount of hydraulic mulch to provide adequate coverage of exposed topsoil may appear to exceed the standard rates when the roughness of the soil surface is changed due to soil preparation methods (see EC-15 Soil Preparation) or by slope gradient.
- Other factors such as existing soil moisture and soil texture can have a profound effect on the amount of hydraulic mulch required (i.e. application rate) applied to achieve an erosionresistant covering.
- Avoid use of mulch without a tackifier component, especially on slopes.
- Mulches used in the hydraulic mulch slurry can include:
  - Cellulose fiber
  - Thermally-processed wood fibers
  - Cotton
  - Synthetics
  - Compost (see EC-14, Compost Blanket)
- Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### **Categories of Hydraulic Mulches**

#### Standard Hydraulic Mulch (SM)

Standard hydraulic mulches are generally applied at a rate of 2,000 pounds per acre and are manufactured containing around 5% tackifier (i.e. soil binder), usually a plant-derived guar or psyllium type. Most standard mulches are green in color derived from food-color based dyes.

#### Hydraulic Matrices (HM) and Stabilized Fiber Matrices (SFM)

Hydraulic matrices and stabilized fiber matrices are slurries which contain increased levels of tackifiers/soil binders; usually 10% or more by weight. HMs and SFMs have improved performance compared to a standard hydraulic mulch (SM) because of the additional percentage of tackifier and because of their higher application rates, typically 2,500 – 4,000 pounds per acre. Hydraulic matrices can include a mixture of fibers, for example, a 50/50 blend of paper and wood fiber. In the case of an SFM, the tackifier/soil binder is specified as a polyacrylamide (PAM).

#### Bonded Fiber Matrix (BFM)

Bonded fiber matrices (BFMs) are hydraulically-applied systems of fibers, adhesives (typically guar based) and chemical cross-links. Upon drying, the slurry forms an erosion-resistant blanket that prevents soil erosion and promotes vegetation establishment. The cross-linked adhesive in the BFM should be biodegradable and should not dissolve or disperse upon rewetting. BFMs are typically applied at rates from 3,000 to 4,000 lbs/acre based on the manufacturer's recommendation. BFMs should not be applied immediately before, during or immediately after rainfall or if the soil is saturated. Depending on the product, BFMs typically require 12 to 24 hours to dry and become effective.

# Mechanically-Bonded Fiber Matrices (MBFM)

Mechanically-bonded fiber matrices (MBFMs) are hydraulically applied systems similar to BFM that use crimped synthetic fibers and PAM and are typically applied to a slope at a higher application rate than a standard BFM.

# Hydraulic Compost Matrix (HCM)

Hydraulic compost matrix (HCM) is a field-derived practice whereby finely graded or sifted compost is introduced into the hydraulic mulch slurry. A guar-type tackifier can be added for steeper slope applications as well as any specified seed mixtures. A HCM can help to accelerate seed germination and growth. HCMs are particularly useful as an in-fill for three-dimensional re-vegetation geocomposites, such as turf reinforcement mats (TRM) (see EC-7 Geotextiles and Mats).

#### Costs

Average installed costs for hydraulic mulch categories are is provided in Table 1, below.

# Table 1 HYDRAULIC MULCH BMPs INSTALLED COSTS

| ВМР   | Installed Cost/Acre        |  |
|---|----------------------------|--|
| Standard Hydraulic Mulching (SM)                      | \$1,700 - \$3,600 per acre |  |
| Hydraulic Matrices (HM) and Stabilized Fiber Matrices |                            |  |
| Guar-based  | \$2,000 - \$4,000 per acre |  |
| PAM-based   | \$2,500 - \$5,610 per acre |  |
| Bonded Fiber Matrix (BFM)                             | \$3,900 - \$6,900 per acre |  |
| Mechanically Bonded Fiber Matrix (MBFM)               | \$4,500 - \$6,000 per acre |  |
| Hydraulic Compost Matrix (HCM)                        | \$3,000 - \$3,500 per acre |  |

Source: Caltrans Soil Stabilization BMP Research for Erosion and Sediment Controls, July 2007

#### **Inspection and Maintenance**

- Maintain an unbroken, temporary mulched ground cover throughout the period of construction when the soils are not being reworked.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected

weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.

- Areas where erosion is evident should be repaired and BMPs re-applied as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require re-application of BMPs.
- Compare the number of bags or weight of applied mulch to the area treated to determine actual application rates and compliance with specifications.

#### References

Soil Stabilization BMP Research for Erosion and Sediment Controls: Cost Survey Technical Memorandum, State of California Department of Transportation (Caltrans), July 2007.

Controlling Erosion of Construction Sites, Agricultural Information #347, U.S. Department of Agriculture (USDA), Natural Resources Conservation Service (NRCS) (formerly Soil Conservation Service – SCS).

Guides for Erosion and Sediment Control in California, USDA Soils Conservation Service, January 1991.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Sedimentation and Erosion Control, An Inventory of Current Practices Draft, US EPA, April 1990.

Soil Erosion by Water, Agriculture Information Bulletin #513, U.S. Department of Agriculture, Soil Conservation Service.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.


Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.

 $\sqrt{\phantom{a}}$ 

X



# **Description and Purpose**

Hydroseeding typically consists of applying a mixture of a hydraulic mulch, seed, fertilizer, and stabilizing emulsion with a hydraulic mulcher, to temporarily protect exposed soils from erosion by water and wind. Hydraulic seeding, or hydroseeding, is simply the method by which temporary or permanent seed is applied to the soil surface.

# **Suitable Applications**

Hydroseeding is suitable for disturbed areas requiring temporary protection until permanent stabilization is established, for disturbed areas that will be re-disturbed following an extended period of inactivity, or to apply permanent stabilization measures. Hydroseeding without mulch or other cover (e.g. EC-7, Erosion Control Blanket) is not a stand-alone erosion control BMP and should be combined with additional measures until vegetation establishment.

Typical applications for hydroseeding include:

- Disturbed soil/graded areas where permanent stabilization or continued earthwork is not anticipated prior to seed germination.
- Cleared and graded areas exposed to seasonal rains or temporary irrigation.
- Areas not subject to heavy wear by construction equipment or high traffic.

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

Non-Stormwater
Management Control

Waste Management and Materials Pollution Control

# Legend:

NS

☑ Primary Category

**☒** Secondary Category

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

**EC-5 Soil Binders** 

EC-6 Straw Mulch

EC-7 Geotextiles and Mats

EC-8 Wood Mulching

EC-14 Compost Blanket

EC-16 Non-Vegetative Stabilization



#### Limitations

- Availability of hydroseeding equipment may be limited just prior to the rainy season and prior to storms due to high demand.
- Hydraulic seed should be applied with hydraulic mulch or a stand-alone hydroseed application should be followed by one of the following:
  - Straw mulch (see Straw Mulch EC-6)
  - Rolled erosion control products (see Geotextiles and Mats EC-7)
  - Application of Compost Blanket (see Compost Blanket EC-14)

Hydraulic seed may be used alone only on small flat surfaces when there is sufficient time in the season to ensure adequate vegetation establishment and coverage to provide adequate erosion control.

- Hydraulic seed without mulch does not provide immediate erosion control.
- Temporary seeding may not be appropriate for steep slopes (i.e., slopes readily prone to rill
  erosion or without sufficient topsoil).
- Temporary seeding may not be appropriate in dry periods without supplemental irrigation.
- Temporary vegetation may have to be removed before permanent vegetation is applied.
- Temporary vegetation may not be appropriate for short term inactivity (i.e. less than 3-6 months).

#### **Implementation**

In order to select appropriate hydraulic seed mixtures, an evaluation of site conditions should be performed with respect to:

Soil conditions

- Maintenance requirements
- Site topography and exposure (sun/wind)
- Sensitive adjacent areas

- Season and climate

Water availability

Vegetation types

- Plans for permanent vegetation

The local office of the U.S.D.A. Natural Resources Conservation Service (NRCS) is an excellent source of information on appropriate seed mixes.

The following steps should be followed for implementation:

■ Where appropriate or feasible, soil should be prepared to receive the seed by disking or otherwise scarifying (See EC-15, Soil Preparation) the surface to eliminate crust, improve air and water infiltration and create a more favorable environment for germination and growth.

- Avoid use of hydraulic seed in areas where the BMP would be incompatible with future earthwork activities.
- Hydraulic seed can be applied using a multiple step or one step process.
  - In a multiple step process, hydraulic seed is applied first, followed by mulch or a Rolled Erosion Control Product (RECP).
  - In the one step process, hydraulic seed is applied with hydraulic mulch in a hydraulic matrix. When the one step process is used to apply the mixture of fiber, seed, etc., the seed rate should be increased to compensate for all seeds not having direct contact with the soil.
- All hydraulically seeded areas should have mulch, or alternate erosion control cover to keep seeds in place and to moderate soil moisture and temperature until the seeds germinate and grow.
- All seeds should be in conformance with the California State Seed Law of the Department of Agriculture. Each seed bag should be delivered to the site sealed and clearly marked as to species, purity, percent germination, dealer's guarantee, and dates of test. The container should be labeled to clearly reflect the amount of Pure Live Seed (PLS) contained. All legume seed should be pellet inoculated. Inoculant sources should be species specific and should be applied at a rate of 2 lb of inoculant per 100 lb seed.
- Commercial fertilizer should conform to the requirements of the California Food and Agricultural Code, which can be found at http://www.leginfo.ca.gov/.html/fac\_table\_of\_contents.html. Fertilizer should be pelleted or granular form.
- Follow up applications should be made as needed to cover areas of poor coverage or germination/vegetation establishment and to maintain adequate soil protection.
- Avoid over spray onto roads, sidewalks, drainage channels, existing vegetation, etc.
- Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### Costs

Average cost for installation and maintenance may vary from as low as \$1,900 per acre for flat slopes and stable soils, to \$4,000 per acre for moderate to steep slopes and/or erosive soils. Cost of seed mixtures vary based on types of required vegetation.

| ВМР            | Installed<br>Cost per Acre |
|----------------|----------------------------|
| Hydraulic Seed | \$1,900-\$4,000            |

Source: Caltrans Soil Stabilization BMP Research for Erosion and Sediment Controls, July 2007

# **Inspection and Maintenance**


- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Areas where erosion is evident should be repaired and BMPs re-applied as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require re-application of BMPs.
- Where seeds fail to germinate, or they germinate and die, the area must be re-seeded, fertilized, and mulched within the planting season, using not less than half the original application rates.
- Irrigation systems, if applicable, should be inspected daily while in use to identify system malfunctions and line breaks. When line breaks are detected, the system must be shut down immediately and breaks repaired before the system is put back into operation.
- Irrigation systems should be inspected for complete coverage and adjusted as needed to maintain complete coverage.

#### References

Soil Stabilization BMP Research for Erosion and Sediment Controls: Cost Survey Technical Memorandum, State of California Department of Transportation (Caltrans), July 2007.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999.



# **Description and Purpose**

Soil binding consists of application and maintenance of a soil stabilizer to exposed soil surfaces. Soil binders are materials applied to the soil surface to temporarily prevent water and wind induced erosion of exposed soils on construction sites.

# **Suitable Applications**

Soil binders are typically applied to disturbed areas requiring temporary protection. Because soil binders, when used as a stand-alone practice, can often be incorporated into the soil, they are a good alternative to mulches in areas where grading activities will soon resume. Soil binders are commonly used in the following areas:

- Rough graded soils that will be inactive for a short period of time
- Soil stockpiles
- Temporary haul roads prior to placement of crushed rock
- Compacted soil road base
- Construction staging, materials storage, and layout areas

#### Limitations

Soil binders are temporary in nature and may need reapplication.

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

E Wind Erosion Control

X

NS Non-Stormwater
Management Control

Waste Management and Materials Pollution Control

#### Legend:

Primary Category

**☒** Secondary Category

# **Targeted Constituents**

Sediment

 $\square$ 

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-4 Hydroseeding

EC-6 Straw Mulch

EC-7 Geotextiles and Mats

**EC-8 Wood Mulching** 



• Soil binders require a minimum curing time until fully effective, as prescribed by the manufacturer. Curing time may be 24 hours or longer. Soil binders may need reapplication after a storm event.

- Soil binders will generally experience spot failures during heavy rainfall events. If runoff penetrates the soil at the top of a slope treated with a soil binder, it is likely that the runoff will undercut the stabilized soil layer and discharge at a point further down slope.
- Plant-material-based soil binders do not generally hold up to pedestrian or vehicular traffic across treated areas as well as polymeric emulsion blends or cementitious-based binders.
- Soil binders may not sufficiently penetrate compacted soils.
- Some soil binders are soil texture specific in terms of their effectiveness. For example, polyacrylamides (PAMs) work very well on silt and clayey soils but their performance decreases dramatically in sandy soils.
- Some soil binders may not perform well with low relative humidity. Under rainy conditions, some agents may become slippery or leach out of the soil.
- Soil binders may not cure if low temperatures occur within 24 hours of application.
- The water quality impacts of some chemical soil binders are relatively unknown and some may have water quality impacts due to their chemical makeup.

# **Implementation**

#### **General Considerations**

- Soil binders should conform to local municipality specifications and requirements.
- Site soil types will dictate appropriate soil binders to be used.
- A soil binder must be environmentally benign (non-toxic to plant and animal life), easy to apply, easy to maintain, economical, and should not stain paved or painted surfaces. Soil binders should not pollute stormwater when cured. Obtain a Material Safety Data Sheet (MSDS) from the manufacturer to ensure non-toxicity.
- Stormwater runoff from PAM treated soils should pass through one of the following sediment control BMP prior to discharging to surface waters.
  - When the total drainage area is greater than or equal to 5 acres, PAM treated areas should drain to a sediment basin.
  - Areas less than 5 acres should drain to sediment control BMPs, such as a sediment trap, or a series of check dams. The total number of check dams used should be maximized to achieve the greatest amount of settlement of sediment prior to discharging from the site. Each check dam should be spaced evenly in the drainage channel through which stormwater flows are discharged off site.
- Performance of soil binders depends on temperature, humidity, and traffic across treated areas.

Avoid over spray onto roads, sidewalks, drainage channels, existing vegetation, etc.

 Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### Selecting a Soil Binder

Properties of common soil binders used for erosion control are provided on Table 1 at the end of this Fact Sheet. Use Table 1 to select an appropriate soil binder. Refer to WE-1, Wind Erosion Control, for dust control soil binders.

Factors to consider when selecting a soil binder include the following:

- Suitability to situation Consider where the soil binder will be applied, if it needs a high resistance to leaching or abrasion, and whether it needs to be compatible with any existing vegetation. Determine the length of time soil stabilization will be needed, and if the soil binder will be placed in an area where it will degrade rapidly. In general, slope steepness is not a discriminating factor for the listed soil binders.
- Soil types and surface materials Fines and moisture content are key properties of surface materials. Consider a soil binder's ability to penetrate, likelihood of leaching, and ability to form a surface crust on the surface materials.
- Frequency of application The frequency of application is related to the functional longevity
  of the binder, which can be affected by subgrade conditions, surface type, climate, and
  maintenance schedule.
- Frequent applications could lead to high costs. Application frequency may be minimized if the soil binder has good penetration, low evaporation, and good longevity. Consider also that frequent application will require frequent equipment clean up.

# Plant-Material-Based (Short Lived, <6 months) Binders

<u>Guar:</u> Guar is a non-toxic, biodegradable, natural galactomannan-based hydrocolloid treated with dispersant agents for easy field mixing. It should be mixed with water at the rate of 11 to 15 lb per 1,000 gallons. Recommended minimum application rates are as follows:

# **Application Rates for Guar Soil Stabilizer**

| Slope (H:V): | Flat | 4:1 | 3:1 | 2:1 | 1;1 |
|--------------|------|-----|-----|-----|-----|
| lb/acre:     | 40   | 45  | 50  | 60  | 70  |

<u>Psyllium:</u> Psyllium is composed of the finely ground muciloid coating of plantago seeds that is applied as a dry powder or in a wet slurry to the surface of the soil. It dries to form a firm but rewettable membrane that binds soil particles together, but permits germination and growth of seed. Psyllium requires 12 to 18 hours drying time. Application rates should be from 80 to 200 lb/acre, with enough water in solution to allow for a uniform slurry flow.

<u>Starch</u>: Starch is non-ionic, cold water soluble (pre-gelatinized) granular cornstarch. The material is mixed with water and applied at the rate of 150 lb/acre. Approximate drying time is 9 to 12 hours.

# Plant-Material-Based (Long Lived, 6-12 months) Binders

Pitch and Rosin Emulsion: Generally, a non-ionic pitch and rosin emulsion has a minimum solids content of 48%. The rosin should be a minimum of 26% of the total solids content. The soil stabilizer should be non-corrosive, water dilutable emulsion that upon application cures to a water insoluble binding and cementing agent. For soil erosion control applications, the emulsion is diluted and should be applied as follows:

■ For clayey soil: 5 parts water to 1 part emulsion

For sandy soil: 10 parts water to 1 part emulsion

Application can be by water truck or hydraulic seeder with the emulsion and product mixture applied at the rate specified by the manufacturer.

# **Polymeric Emulsion Blend Binders**

Acrylic Copolymers and Polymers: Polymeric soil stabilizers should consist of a liquid or solid polymer or copolymer with an acrylic base that contains a minimum of 55% solids. The polymeric compound should be handled and mixed in a manner that will not cause foaming or should contain an anti-foaming agent. The polymeric emulsion should not exceed its shelf life or expiration date; manufacturers should provide the expiration date. Polymeric soil stabilizer should be readily miscible in water, non-injurious to seed or animal life, non-flammable, should provide surface soil stabilization for various soil types without totally inhibiting water infiltration, and should not re-emulsify when cured. The applied compound typically requires 12 to 24 hours drying time. Liquid copolymer should be diluted at a rate of 10 parts water to 1 part polymer and the mixture applied to soil at a rate of 1,175 gallons/acre.

<u>Liquid Polymers of Methacrylates and Acrylates:</u> This material consists of a tackifier/sealer that is a liquid polymer of methacrylates and acrylates. It is an aqueous 100% acrylic emulsion blend of 40% solids by volume that is free from styrene, acetate, vinyl, ethoxylated surfactants or silicates. For soil stabilization applications, it is diluted with water in accordance with the manufacturer's recommendations, and applied with a hydraulic seeder at the rate of 20 gallons/acre. Drying time is 12 to 18 hours after application.

<u>Copolymers of Sodium Acrylates and Acrylamides:</u> These materials are non-toxic, dry powders that are copolymers of sodium acrylate and acrylamide. They are mixed with water and applied to the soil surface for erosion control at rates that are determined by slope gradient:

| Slope Gradient<br>(H:V) | lb/acre     |  |
|-------------------------|-------------|--|
| Flat to 5:1             | 3.0 - 5.0   |  |
| 5:1 to 3:1              | 5.0 – 10.0  |  |
| 2:1 to 1:1              | 10.0 - 20.0 |  |

<u>Poly-Acrylamide (PAM) and Copolymer of Acrylamide:</u> Linear copolymer polyacrylamide for use as a soil binder is packaged as a dry flowable solid, as a liquid. Refer to the manufacturer's recommendation for dilution and application rates as they vary based on liquid or dry form, site conditions and climate.

■ Limitations specific to PAM are as follows:

- Do not use PAM on a slope that flows into a water body without passing through a sediment trap or sediment basin.

- The specific PAM copolymer formulation must be anionic. Cationic PAM should not be used in any application because of known aquatic toxicity problems. Only the highest drinking water grade PAM, certified for compliance with ANSI/NSF Standard 60 for drinking water treatment, should be used for soil applications.
- PAM designated for erosion and sediment control should be "water soluble" or "linear" or "non-cross linked".
- PAM should not be used as a stand-alone BMP to protect against water-based erosion. When combined with mulch, its effectiveness increases dramatically.

<u>Hydro-Colloid Polymers</u>: Hydro-Colloid Polymers are various combinations of dry flowable poly-acrylamides, copolymers and hydro-colloid polymers that are mixed with water and applied to the soil surface at rates of 55 to 60 lb/acre. Drying times are 0 to 4 hours.

#### Cementitious-Based Binders

Gypsum: This is a formulated gypsum based product that readily mixes with water and mulch to form a thin protective crust on the soil surface. It is composed of high purity gypsum that is ground, calcined and processed into calcium sulfate hemihydrate with a minimum purity of 86%. It is mixed in a hydraulic seeder and applied at rates 4,000 to 12,000 lb/acre. Drying time is 4 to 8 hours.

# Applying Soil Binders

After selecting an appropriate soil binder, the untreated soil surface must be prepared before applying the soil binder. The untreated soil surface must contain sufficient moisture to assist the agent in achieving uniform distribution. In general, the following steps should be followed:

- Follow manufacturer's written recommendations for application rates, pre-wetting of application area, and cleaning of equipment after use.
- Prior to application, roughen embankment and fill areas.
- Consider the drying time for the selected soil binder and apply with sufficient time before anticipated rainfall. Soil binders should not be applied during or immediately before rainfall.
- Avoid over spray onto roads, sidewalks, drainage channels, sound walls, existing vegetation, etc.
- Soil binders should not be applied to frozen soil, areas with standing water, under freezing or rainy conditions, or when the temperature is below 40°F during the curing period.
- More than one treatment is often necessary, although the second treatment may be diluted or have a lower application rate.
- Generally, soil binders require a minimum curing time of 24 hours before they are fully
  effective. Refer to manufacturer's instructions for specific cure time.

- For liquid agents:
  - Crown or slope ground to avoid ponding.
  - Uniformly pre-wet ground at 0.03 to 0.3 gal/yd² or according to manufacturer's recommendations.
  - Apply solution under pressure. Overlap solution 6 to 12 in.
  - Allow treated area to cure for the time recommended by the manufacturer; typically at least 24 hours.
  - Apply second treatment before first treatment becomes ineffective, using 50% application rate.
  - In low humidities, reactivate chemicals by re-wetting with water at 0.1 to 0.2 gal/yd<sup>2</sup>.

#### Costs

Costs vary according to the soil stabilizer selected for implementation. The following are approximate installed costs:

| Soil Binder                                | Cost per Acre<br>(2000)¹ | Estimated Cost<br>per Acre<br>(2009) <sup>2</sup> |
|--|--------------------------|---|
| Plant-Material-Based (Short Lived) Binders | \$700-\$900              | \$770-\$990                                       |
| Plant-Material-Based (Long Lived) Binders  | \$1,200-\$1,500          | \$1,320-\$1,650                                   |
| Polymeric Emulsion Blend Binders           | \$700 -\$1,500           | \$770-\$1,650                                     |
| Cementitious-Based Binders                 | \$800-\$1,200            | \$880~\$1,350                                     |

<sup>1.</sup> Source: Erosion Control Pilot Study Report, Caltrans, June 2000.

# **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Areas where erosion is evident should be repaired and BMPs re-applied as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require re-application of BMPs.
- Reapply the selected soil binder as needed to maintain effectiveness.

<sup>2. 2009</sup> costs reflect a 10% escalation over year 2000 costs. Escalation based on informal survey of industry trends. Note: Expected cost increase is offset by competitive economic conditions.

| Table 1 Properties of Soil Binders for Erosion Control |  |   |  |  |
|--|--|---|--|--|
|  | Binder Type                              |   |  |  |
| Evaluation Criteria                                    | Plant Material<br>Based (Short<br>Lived) | Plant Material<br>Based (Long<br>Lived) | Polymeric<br>Emulsion Blends                 | Cementitious-<br>Based Binders               |
| Relative Cost  | Low                                      | Moderate to<br>High                     | Low to High                                  | Low to Moderate                              |
| Resistance to Leaching                                 | High                                     | High                                    | Low to Moderate                              | Moderate                                     |
| Resistance to Abrasion                                 | Moderate                                 | Low                                     | Moderate to High                             | Moderate to High                             |
| Longevity  | Short to Medium                          | Medium                                  | Medium to Long                               | Medium                                       |
| Minimum Curing Time<br>before Rain                     | 9 to 18 hours                            | 19 to 24 hours                          | 0 to 24 hours                                | 4 to 8 hours                                 |
| Compatibility with<br>Existing Vegetation              | Good                                     | Poor                                    | Poor   | Poor   |
| Mode of Degradation                                    | Biodegradable                            | Biodegradable                           | Photodegradable/<br>Chemically<br>Degradable | Photodegradable/<br>Chemically<br>Degradable |
| Labor Intensive  | No                                       | No                                      | No   | No   |
| Specialized Application<br>Equipment                   | Water Truck or<br>Hydraulic<br>Mulcher   | Water Truck or<br>Hydraulic<br>Mulcher  | Water Truck or<br>Hydraulic Mulcher          | Water Truck or<br>Hydraulic Mulcher          |
| Liquid/Powder  | Powder                                   | Liquid                                  | Liquid/Powder                                | Powder                                       |
| Surface Crusting                                       | Yes, but dissolves<br>on rewetting       | Yesl                                    | Yes, but dissolves on rewetting              | Yes  |
| Clean Up   | Water                                    | Water                                   | Water  | Water  |
| Erosion Control<br>Application Rate                    | Varies (1)                               | Varies (1)                              | Varies (1)                                   | 4,000 to 12,000<br>lbs/acre                  |

<sup>(1)</sup> See Implementation for specific rates.

#### References

Erosion Control Pilot Study Report, State of California Department of Transportation (Caltrans), June 2000.


Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Sedimentation and Erosion Control, An Inventory of Current Practices Draft, US EPA, April 1990.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



# **Description and Purpose**

Straw mulch consists of placing a uniform layer of straw and incorporating it into the soil with a studded roller or crimper, or anchoring it with a tackifier or stabilizing emulsion. Straw mulch protects the soil surface from the impact of rain drops, preventing soil particles from becoming dislodged.

# **Suitable Applications**

Straw mulch is suitable for disturbed areas requiring temporary protection until permanent stabilization is established. Straw mulch can be specified for the following applications:

- As a stand-alone BMP on disturbed areas until soils can be prepared for permanent vegetation. The longevity of straw mulch is typically less than six months.
- Applied in combination with temporary seeding strategies
- Applied in combination with permanent seeding strategies to enhance plant establishment and final soil stabilization
- Applied around containerized plantings to control erosion until the plants become established to provide permanent stabilization

#### Limitations

 Availability of straw and straw blowing equipment may be limited just prior to the rainy season and prior to storms due to high demand.

# Categories

EC Erosion Control

 $\mathbf{Q}$ 

X

abla

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control
Waste Management and

wm Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

Secondary Category

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

**EC-4** Hydroseeding

**EC-5 Soil Binders** 

EC-7 Geotextiles and Mats

EC-8 Wood Mulching

EC-14 Compost Blanket



Straw Mulch EC-6

There is a potential for introduction of weed seed and unwanted plant material if weed-free agricultural straw is not specified.

- Straw mulch applied by hand is more time intensive and potentially costly.
- Wind may limit application of straw and blow straw into undesired locations.
- May have to be removed prior to permanent seeding or prior to further earthwork.
- "Punching" of straw does not work in sandy soils, necessitating the use of tackifiers.
- Potential fugitive dust control issues associated with straw applications can occur.
   Application of a stabilizing emulsion or a water stream at the same time straw is being blown can reduce this problem.
- Use of plastic netting should be avoided in areas where wildlife may be entrapped and may be prohibited for projects in certain areas with sensitive wildlife species, especially reptiles and amphibians.

# **Implementation**

- Straw should be derived from weed-free wheat, rice, or barley. Where required by the plans, specifications, permits, or environmental documents, native grass straw should be used.
- Use tackifier to anchor straw mulch to the soil on slopes.
- Crimping, punch roller-type rollers, or track walking may also be used to incorporate straw mulch into the soil on slopes. Track walking can be used where other methods are impractical.
- Avoid placing straw onto roads, sidewalks, drainage channels, sound walls, existing vegetation, etc.
- Straw mulch with tackifier should not be applied during or immediately before rainfall.
- Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

# **Application Procedures**

- When using a tackifier to anchor the straw mulch, roughen embankment or fill areas by rolling with a crimping or punching-type roller or by track walking before placing the straw mulch. Track walking should only be used where rolling is impractical.
- Apply straw at a rate of between 3,000 and 4,000 lb/acre, either by machine or by hand distribution and provide 100% ground cover. A lighter application is used for flat surfaces and a heavier application is used for slopes.
- Evenly distribute straw mulch on the soil surface.
- Anchoring straw mulch to the soil surface by "punching" it into the soil mechanically (incorporating) can be used in lieu of a tackifier.

Straw Mulch EC-6

Methods for holding the straw mulch in place depend upon the slope steepness, accessibility, soil conditions, and longevity.

- A tackifier acts to glue the straw fibers together and to the soil surface. The tackifier should be selected based on longevity and ability to hold the fibers in place. A tackifier is typically applied at a rate of 125 lb/acre. In windy conditions, the rates are typically 180 lb/acre.
- On very small areas, a spade or shovel can be used to punch in straw mulch.
- On slopes with soils that are stable enough and of sufficient gradient to safely support construction equipment without contributing to compaction and instability problems, straw can be "punched" into the ground using a knife blade roller or a straight bladed coulter, known commercially as a "crimper."

#### Costs

Average annual cost for installation and maintenance is included in the table below. Application by hand is more time intensive and potentially more costly.

| ВМР                             | Unit Cost per Acre |  |
|---------------------------------|--------------------|--|
| Straw mulch, crimped or punched | \$2,458-\$5,375    |  |
| Straw mulch with tackifier      | \$1,823-\$4,802    |  |

Source: Caltrans Soil Stabilization BMP Research for Erosion and Sediment Controls, July 2007

# **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Areas where erosion is evident should be repaired and BMPs re-applied as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require re-application of BMPs.
- The key consideration in inspection and maintenance is that the straw needs to last long enough to achieve erosion control objectives. Straw mulch as a stand-alone BMP is temporary and is not suited for long-term erosion control.
- Maintain an unbroken, temporary mulched ground cover while disturbed soil areas are inactive. Repair any damaged ground cover and re-mulch exposed areas.
- Reapplication of straw mulch and tackifier may be required to maintain effective soil stabilization over disturbed areas and slopes.

Straw Mulch EC-6

#### References

Soil Stabilization BMP Research for Erosion and Sediment Controls: Cost Survey Technical Memorandum, State of California Department of Transportation (Caltrans), July 2007.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

Controlling Erosion of Construction Sites, Agricultural Information Bulletin #347, U.S. Department of Agriculture (USDA), Natural Resources Conservation Service (NRCS) (formerly Soil Conservation Service – SCS).

Guides for Erosion and Sediment Control in California, USDA Soils Conservation Service, January 1991.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Soil Erosion by Water, Agricultural Information Bulletin #513, U.S. Department of Agriculture, Soil Conservation Service.


Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.

 $\square$ 

×



# **Description and Purpose**

Mattings, or Rolled Erosion Control Products (RECPs), can be made of natural or synthetic materials or a combination of the two. RECPs are used to cover the soil surface to reduce erosion from rainfall impact, hold soil in place, and absorb and hold moisture near the soil surface. Additionally, RECPs may be used to stabilize soils until vegetation is established or to reinforce non-woody surface vegetation.

# **Suitable Applications**

RECPs are typically applied on slopes where erosion hazard is high and vegetation will be slow to establish. Mattings are also used on stream banks, swales and other drainage channels where moving water at velocities between 3 ft/s and 6 ft/s are likely to cause scour and wash out new vegetation, and in areas where the soil surface is disturbed and where existing vegetation has been removed. RECPs may also be used when seeding cannot occur (e.g., late season construction and/or the arrival of an early rain season). RECPs should be considered when the soils are fine grained and potentially erosive. RECPs should be considered in the following situations.

- Steep slopes, generally steeper than 3:1 (H:V)
- Slopes where the erosion potential is high
- Slopes and disturbed soils where mulch must be anchored
- Disturbed areas where plants are slow to develop

#### **Categories**

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

Secondary Category

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria
Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-4 Hydroseeding



15.45

- Channels with flows exceeding 3.3 ft/s
- Channels to be vegetated
- Stockpiles
- Slopes adjacent to water bodies

# Limitations

- RECP installed costs are generally higher than other erosion control BMPs, limiting their use to areas where other BMPs are ineffective (e.g. channels, steep slopes).
- RECPs may delay seed germination, due to reduction in soil temperature.
- RECPs are generally not suitable for excessively rocky sites or areas where the final vegetation will be mowed (since staples and netting can catch in mowers). If a staple or pin cannot be driven into the soil because the underlying soil is too hard or rocky, then an alternative BMP should be selected.
- If used for temporary erosion control, RECPs should be removed and disposed of prior to application of permanent soil stabilization measures.
- The use of plastic should be limited to covering stockpiles or very small graded areas for short periods of time (such as through one imminent storm event) until more environmentally friendly measures, such as seeding and mulching, may be installed.
  - Plastic sheeting is easily vandalized, easily torn, photodegradable, and must be disposed of at a landfill.
  - Plastic sheeting results in 100% runoff, which may cause serious erosion problems in the areas receiving the increased flow.
- RECPs may have limitations based on soil type, slope gradient, or channel flow rate; consult the manufacturer for proper selection.
- Not suitable for areas that have foot traffic (tripping hazard) e.g., pad areas around buildings under construction.
- RECPs that incorporate a plastic netting (e.g. straw blanket typically uses a plastic netting to hold the straw in place) may not be suitable near known wildlife habitat. Wildlife can become trapped in the plastic netting.
- RECPs may have limitations in extremely windy climates. However, when RECPs are properly trenched at the top and bottom and stapled in accordance with the manufacturer's recommendations, problems with wind can be minimized.

# *Implementation*

#### **Material Selection**

- Natural RECPs have been found to be effective where re-vegetation will be provided by reseeding. The choice of material should be based on the size of area, side slopes, surface conditions such as hardness, moisture, weed growth, and availability of materials.
- Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.
- The following natural and synthetic RECPs are commonly used:

#### Geotextiles

- Material can be a woven or a non-woven polypropylene fabric with minimum thickness of 0.06 in., minimum width of 12 ft and should have minimum tensile strength of 150 lbs (warp), 80 lbs (fill) in conformance with the requirements in ASTM Designation: D 4632. The permittivity of the fabric should be approximately 0.07 sec<sup>-1</sup> in conformance with the requirements in ASTM Designation: D4491. The fabric should have an ultraviolet (UV) stability of 70 percent in conformance with the requirements in ASTM designation: D4355. Geotextile blankets must be secured in place with wire staples or sandbags and by keying into tops of slopes to prevent infiltration of surface waters under geotextile. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Geotextiles may be reused if they are suitable for the use intended.

# Plastic Covers

- Generally plastic sheeting should only be used as stockpile covering or for very small graded areas for short periods of time (such as through one imminent storm event). If plastic sheeting must be used, choose a plastic that will withstand photo degradation.
- Plastic sheeting should have a minimum thickness of 6 mils, and must be keyed in at the top of slope (when used as a temporary slope protection) and firmly held in place with sandbags or other weights placed no more than 10 ft apart. Seams are typically taped or weighted down their entire length, and there should be at least a 12 in. to 24 in. overlap of all seams. Edges should be embedded a minimum of 6 in. in soil (when used as a temporary slope protection).
- All sheeting must be inspected periodically after installation and after significant rainstorms
  to check for erosion, undermining, and anchorage failure. Any failures must be repaired
  immediately. If washout or breakages occur, the material should be re-installed after
  repairing the damage to the slope.

# Erosion Control Blankets/Mats

■ Biodegradable RECPs are typically composed of jute fibers, curled wood fibers, straw, coconut fiber, or a combination of these materials. In order for an RECP to be considered 100% biodegradable, the netting, sewing or adhesive system that holds the biodegradable mulch fibers together must also be biodegradable. See typical installation details at the end of this fact sheet.

- **Jute** is a natural fiber that is made into a yarn that is loosely woven into a biodegradable mesh. The performance of jute as a stand-alone RECP is low. Most other RECPs outperform jute as a temporary erosion control product and therefore jute is not commonly used. It is designed to be used in conjunction with vegetation. The material is supplied in rolled strips, which should be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Excelsior (curled wood fiber) blanket material should consist of machine produced mats of curled wood excelsior with 80 percent of the fiber 6 in. or longer. The excelsior blanket should be of consistent thickness. The wood fiber must be evenly distributed over the entire area of the blanket. The top surface of the blanket should be covered with a photodegradable extruded plastic mesh. The blanket should be smolder resistant without the use of chemical additives and should be non-toxic and non-injurious to plant and animal life. Excelsior blankets should be furnished in rolled strips, a minimum of 48 in. wide, and should have an average weight of 0.8 lb/yd², ±10 percent, at the time of manufacture. Excelsior blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- **Straw blanket** should be machine produced mats of straw with a lightweight biodegradable netting top layer. The straw should be attached to the netting with biodegradable thread or glue strips. The straw blanket should be of consistent thickness. The straw should be evenly distributed over the entire area of the blanket. Straw blanket should be furnished in rolled strips a minimum of 6.5 ft wide, a minimum of 80 ft long and a minimum of 0.5 lb/yd². Straw blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- **Wood fiber blanket** is composed of biodegradable fiber mulch with extruded plastic netting held together with adhesives. The material is designed to enhance re-vegetation. The material is furnished in rolled strips, which must be secured to the ground with U-shaped staples or stakes in accordance with manufacturers' recommendations.
- Coconut fiber blanket should be a machine produced mat of 100 percent coconut fiber with biodegradable netting on the top and bottom. The coconut fiber should be attached to the netting with biodegradable thread or glue strips. The coconut fiber blanket should be of consistent thickness. The coconut fiber should be evenly distributed over the entire area of the blanket. Coconut fiber blanket should be furnished in rolled strips with a minimum of 6.5 ft wide, a minimum of 80 ft. long and a minimum of 0.5 lb/yd². Coconut fiber blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- **Coconut fiber mesh** is a thin permeable membrane made from coconut or corn fiber that is spun into a yarn and woven into a biodegradable mat. It is designed to be used in conjunction with vegetation and typically has longevity of several years. The material is supplied in rolled strips, which must be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.

- **Straw coconut fiber blanket** should be machine produced mats of 70 percent straw and 30 percent coconut fiber with a biodegradable netting top layer and a biodegradable bottom net. The straw and coconut fiber should be attached to the netting with biodegradable thread or glue strips. The straw coconut fiber blanket should be of consistent thickness. The straw and coconut fiber should be evenly distributed over the entire area of the blanket. Straw coconut fiber blanket should be furnished in rolled strips a minimum of 6.5 ft wide, a minimum of 80 ft long and a minimum of 0.5 lb/yd². Straw coconut fiber blankets must be secured in place with wire staples. Staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Non-biodegradable RECPs are typically composed of polypropylene, polyethylene, nylon or other synthetic fibers. In some cases, a combination of biodegradable and synthetic fibers is used to construct the RECP. Netting used to hold these fibers together is typically non-biodegradable as well.
  - **Plastic netting** is a lightweight biaxially oriented netting designed for securing loose mulches like straw or paper to soil surfaces to establish vegetation. The netting is photodegradable. The netting is supplied in rolled strips, which must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.
  - **Plastic mesh** is an open weave geotextile that is composed of an extruded synthetic fiber woven into a mesh with an opening size of less than ¼ in. It is used with revegetation or may be used to secure loose fiber such as straw to the ground. The material is supplied in rolled strips, which must be secured to the soil with U-shaped staples or stakes in accordance with manufacturers' recommendations.
  - **Synthetic fiber with netting** is a mat that is composed of durable synthetic fibers treated to resist chemicals and ultraviolet light. The mat is a dense, three dimensional mesh of synthetic (typically polyolefin) fibers stitched between two polypropylene nets. The mats are designed to be re-vegetated and provide a permanent composite system of soil, roots, and geomatrix. The material is furnished in rolled strips, which must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.
  - **Bonded synthetic fibers** consist of a three dimensional geomatrix nylon (or other synthetic) matting. Typically it has more than 90 percent open area, which facilitates root growth. It's tough root reinforcing system anchors vegetation and protects against hydraulic lift and shear forces created by high volume discharges. It can be installed over prepared soil, followed by seeding into the mat. Once vegetated, it becomes an invisible composite system of soil, roots, and geomatrix. The material is furnished in rolled strips that must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.
  - Combination synthetic and biodegradable RECPs consist of biodegradable fibers, such as wood fiber or coconut fiber, with a heavy polypropylene net stitched to the top and a high strength continuous filament geometrix or net stitched to the bottom. The material is designed to enhance re-vegetation. The material is furnished in rolled strips,

which must be secured with U-shaped staples or stakes in accordance with manufacturers' recommendations.

# Site Preparation

- Proper soil preparation is essential to ensure complete contact of the RECP with the soil. Soil Roughening is not recommended in areas where RECPs will be installed.
- Grade and shape the area of installation.
- Remove all rocks, clods, vegetation or other obstructions so that the installed blankets or mats will have complete, direct contact with the soil.
- Prepare seedbed by loosening 2 to 3 in. of topsoil.

# Seeding/Planting

Seed the area before blanket installation for erosion control and re-vegetation. Seeding after mat installation is often specified for turf reinforcement application. When seeding prior to blanket installation, all areas disturbed during blanket installation must be re-seeded. Where soil filling is specified for turf reinforcement mats (TRMs), seed the matting and the entire disturbed area after installation and prior to filling the mat with soil.

Fertilize and seed in accordance with seeding specifications or other types of landscaping plans. The protective matting can be laid over areas where grass has been planted and the seedlings have emerged. Where vines or other ground covers are to be planted, lay the protective matting first and then plant through matting according to design of planting.

# Check Slots

Check slots shall be installed as required by the manufacturer.

# Laying and Securing Matting

- Before laying the matting, all check slots should be installed and the seedbed should be friable, made free from clods, rocks, and roots. The surface should be compacted and finished according to the requirements of the manufacturer's recommendations.
- Mechanical or manual lay down equipment should be capable of handling full rolls of fabric and laying the fabric smoothly without wrinkles or folds. The equipment should meet the fabric manufacturer's recommendations or equivalent standards.

#### Anchoring

- U-shaped wire staples, metal geotextile stake pins, or triangular wooden stakes can be used to anchor mats and blankets to the ground surface.
- Wire staples should be made of minimum 11 gauge steel wire and should be U-shaped with 8 in. legs and 2 in. crown.
- Metal stake pins should be 0.188 in. diameter steel with a 1.5 in. steel washer at the head of the pin, and 8 in. in length.
- Wire staples and metal stakes should be driven flush to the soil surface.

# **Installation on Slopes**

Installation should be in accordance with the manufacturer's recommendations. In general, these will be as follows:

- Begin at the top of the slope and anchor the blanket in a 6 in. deep by 6 in. wide trench. Backfill trench and tamp earth firmly.
- Unroll blanket down slope in the direction of water flow.
- Overlap the edges of adjacent parallel rolls 2 to 3 in. and staple every 3 ft (or greater, per manufacturer's specifications).
- When blankets must be spliced, place blankets end over end (shingle style) with 6 in. overlap. Staple through overlapped area, approximately 12 in. apart.
- Lay blankets loosely and maintain direct contact with the soil. Do not stretch.
- Staple blankets sufficiently to anchor blanket and maintain contact with the soil. Staples should be placed down the center and staggered with the staples placed along the edges. Steep slopes, 1:1 (H:V) to 2:1 (H:V), require a minimum of 2 staples/yd². Moderate slopes, 2:1 (H:V) to 3:1 (H:V), require a minimum of 1 ½ staples/yd². Check manufacturer's specifications to determine if a higher density staple pattern is required.

# Installation in Channels

Installation should be in accordance with the manufacturer's recommendations. In general, these will be as follows:

- Dig initial anchor trench 12 in. deep and 6 in. wide across the channel at the lower end of the project area.
- Excavate intermittent check slots, 6 in. deep and 6 in. wide across the channel at 25 to 30 ft intervals along the channels.
- Cut longitudinal channel anchor trenches 4 in. deep and 4 in. wide along each side of the installation to bury edges of matting, whenever possible extend matting 2 to 3 in. above the crest of the channel side slopes.
- Beginning at the downstream end and in the center of the channel, place the initial end of the first roll in the anchor trench and secure with fastening devices at 12 in. intervals. Note: matting will initially be upside down in anchor trench.
- In the same manner, position adjacent rolls in anchor trench, overlapping the preceding roll a minimum of 3 in.
- Secure these initial ends of mats with anchors at 12 in. intervals, backfill and compact soil.
- Unroll center strip of matting upstream. Stop at next check slot or terminal anchor trench. Unroll adjacent mats upstream in similar fashion, maintaining a 3 in. overlap.

- Fold and secure all rolls of matting snugly into all transverse check slots. Lay mat in the bottom of the slot then fold back against itself. Anchor through both layers of mat at 12 in. intervals, then backfill and compact soil. Continue rolling all mat widths upstream to the next check slot or terminal anchor trench.
- Alternate method for non-critical installations: Place two rows of anchors on 6 in. centers at 25 to 30 ft. intervals in lieu of excavated check slots.
- Staple shingled lap spliced ends a minimum of 12 in, apart on 12 in, intervals.
- Place edges of outside mats in previously excavated longitudinal slots; anchor using prescribed staple pattern, backfill, and compact soil.
- Anchor, fill, and compact upstream end of mat in a 12 in. by 6 in. terminal trench.
- Secure mat to ground surface using U-shaped wire staples, geotextile pins, or wooden stakes.
- Seed and fill turf reinforcement matting with soil, if specified.

# Soil Filling (if specified for turf reinforcement mat (TRM))

Installation should be in accordance with the manufacturer's recommendations. Typical installation guidelines are as follows:

- After seeding, spread and lightly rake ½-3/4 inches of fine topsoil into the TRM apertures to completely fill TRM thickness. Use backside of rake or other flat implement.
- Alternatively, if allowed by product specifications, spread topsoil using lightweight loader, backhoe, or other power equipment. Avoid sharp turns with equipment.
- Always consult the manufacturer's recommendations for installation.
- Do not drive tracked or heavy equipment over mat.
- Avoid any traffic over matting if loose or wet soil conditions exist.
- Use shovels, rakes, or brooms for fine grading and touch up.
- Smooth out soil filling just exposing top netting of mat.

# Temporary Soil Stabilization Removal

■ Temporary soil stabilization removed from the site of the work must be disposed of if necessary.

#### Costs

Installed costs can be relatively high compared to other BMPs. Approximate costs for installed materials are shown below:

| Rolled Er         | osion Control Products         | Installed Cost per<br>Acre (2000)¹ | Estimated Cost<br>per Acre (2009) <sup>2</sup> |
|-------------------|--------------------------------|------------------------------------|--|
|                   | Jute Mesh                      | \$6,000-\$7,000                    | \$6,600-\$7,700                                |
|                   | Curled Wood Fiber              | \$8,000-\$10,500                   | \$8,800-\$11,050                               |
|                   | Straw                          | \$8,000-\$10,500                   | \$8,800-\$11,050                               |
| Biodegradable     | Wood Fiber                     | \$8,000-\$10,500                   | \$8,800-\$11,050                               |
|                   | Coconut Fiber                  | \$13,000-\$14,000                  | \$14,300-\$15,400                              |
|                   | Coconut Fiber Mesh             | \$30,000-\$33,000                  | \$33,000-\$36,300                              |
|                   | Straw Coconut Fiber            | \$10,000-\$12,000                  | \$11,000-\$13,200                              |
| Non-Biodegradable | Plastic Netting                | \$2,000-\$2,200                    | \$2,200-\$2,220                                |
|                   | Plastic Mesh                   | \$3,000-\$3,500                    | \$3,300-\$3,850                                |
|                   | Synthetic Fiber with Netting   | \$34,000-\$40,000                  | \$37,400-\$44,000                              |
|                   | Bonded Synthetic Fibers        | \$45,000-\$55,000                  | \$49,500-\$60,500                              |
|                   | Combination with Biodegradable | \$30,000-\$36,000                  | \$33,000-\$39,600                              |

<sup>1.</sup> Source: Erosion Control Pilot Study Report, Caltrans, June 2000.

# Inspection and Maintenance

- RECPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Areas where erosion is evident shall be repaired and BMPs reapplied as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs.
- If washout or breakage occurs, re-install the material after repairing the damage to the slope or channel.
- Make sure matting is uniformly in contact with the soil.
- Check that all the lap joints are secure.
- Check that staples are flush with the ground.

#### References

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005

Erosion Control Pilot Study Report, State of California Department of Transportation (Caltrans), June 2000.

Guides for Erosion and Sediment Controls in California, USDA Soils Conservation Service, January 1991.

<sup>2. 2009</sup> costs reflect a 10% escalation over year 2000 costs. Escalation based on informal survey of industry trends. Note: Expected cost increase is offset by competitive economic conditions.


National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Guidance Document: Soil Stabilization for Temporary Slopes, State of California Department of Transportation (Caltrans), November 1999.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.


Water Quality Management Plan for The Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.



#### NOTES:

- 1. Slope surface shall be free of rocks, clods, sticks and grass. Mats/blankets shall have good soil contact.
- 2. Lay blankets loosely and stake or staple to maintain direct contact with the soil. Do not stretch.
- 3. Install per manufacturer's recommendations


# TYPICAL INSTALLATION DETAIL



#### NOTES:

- 1. Check slots to be constructed per manufacturers specifications.
- 2. Staking or stapling layout per manufacturers specifications.
- 3. Install per manufacturer's recommendations

TYPICAL INSTALLATION DETAIL



# **Description and Purpose**

Wood mulching consists of applying a mixture of shredded wood mulch, bark or compost to disturbed soils. The primary function of wood mulching is to reduce erosion by protecting bare soil from rainfall impact, increasing infiltration, and reducing runoff.

# **Suitable Applications**

Wood mulching is suitable for disturbed soil areas requiring temporary protection until permanent stabilization is established.

#### Limitations

- Not suitable for use on slopes steeper than 3:1 (H:V). Best suited to flat areas or gentle slopes or 5:1 (H:V) or flatter.
- Wood mulch and compost may introduce unwanted species.
- Not suitable for areas exposed to concentrated flows.
- May need to be removed prior to further earthwork.

# **Implementation**

# **Mulch Selection**

There are many types of mulches. Selection of the appropriate type of mulch should be based on the type of application, site conditions, and compatibility with planned or future uses.

# **Application Procedures**

Prior to application, after existing vegetation has been

#### Categories

EC Erosion Control

 $\square$ 

×

SE Sediment Control

Tracking Control

Wind Erosion Control

NS Non-Stormwater

Management Control

Waste Management and

Materials Pollution Control

# Legend:

☑ Primary Objective

Secondary Objective

# **Targeted Constituents**

Sediment

V

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-4 Hydroseeding

**EC-5 Soil Binders** 

EC-6 Straw Mulch

EC-7 Geotextiles and Mats



removed, roughen embankment and fill areas by rolling with a device such as a punching type roller or by track walking. The construction application procedures for mulches vary significantly depending upon the type of mulching method specified. Two methods are highlighted here:

- Green Material: This type of mulch is produced by the recycling of vegetation trimmings such as grass, shredded shrubs, and trees. Methods of application are generally by hand although pneumatic methods are available.
  - Green material can be used as a temporary ground cover with or without seeding.
  - The green material should be evenly distributed on site to a depth of not more than 2 in.
- Shredded Wood: Suitable for ground cover in ornamental or revegetated plantings.
  - Shredded wood/bark is conditionally suitable. See note under limitations.
  - Distribute by hand or use pneumatic methods.
  - Evenly distribute the mulch across the soil surface to a depth of 2 to 3 in.
- Avoid mulch placement onto roads, sidewalks, drainage channels, existing vegetation, etc.

#### Costs

Average annual cost for installation and maintenance (3-4 months useful life) is around \$4,000 per acre, but cost can increase if the source is not close to the project site.

of Pents

#### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Areas where erosion is evident shall be repaired and BMPs reapplied as soon as possible.
   Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs.
- Regardless of the mulching technique selected, the key consideration in inspection and maintenance is that the mulch needs to last long enough to achieve erosion control objectives. If the mulch is applied as a stand alone erosion control method over disturbed areas (without seed), it should last the length of time the site will remain barren or until final re-grading and revegetation.
- Where vegetation is not the ultimate cover, such as ornamental and landscape applications
  of bark or wood chips, inspection and maintenance should focus on longevity and integrity
  of the mulch.
- Reapply mulch when bare earth becomes visible.

# References

Controlling Erosion of Construction Sites Agriculture Information Bulletin #347, U.S. Department of Agriculture (USDA), Natural Resources Conservation Service (NRCS) (formerly Soil Conservation Service – SCS).

Guides for Erosion and Sediment Control in California, USDA Soils Conservation Service, January 1991.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.


Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group Working Paper, USEPA, April 1992.

Sedimentation and Erosion Control, An Inventory of Current Practices Draft, U.S. EPA, April 1990.

Soil Erosion by Water Agricultural Information Bulletin #513, U.S. Department of Agriculture, Soil Conservation Service.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.



# **Description and Purpose**

An earth dike is a temporary berm or ridge of compacted soil used to divert runoff or channel water to a desired location. A drainage swale is a shaped and sloped depression in the soil surface used to convey runoff to a desired location. Earth dikes and drainage swales are used to divert off site runoff around the construction site, divert runoff from stabilized areas and disturbed areas, and direct runoff into sediment basins or traps.

# **Suitable Applications**

Earth dikes and drainage swales are suitable for use, individually or together, where runoff needs to be diverted from one area and conveyed to another.

- Earth dikes and drainage swales may be used:
  - To convey surface runoff down sloping land
  - To intercept and divert runoff to avoid sheet flow over sloped surfaces
  - To divert and direct runoff towards a stabilized watercourse, drainage pipe or channel
  - To intercept runoff from paved surfaces
  - Below steep grades where runoff begins to concentrate
  - Along roadways and facility improvements subject to flood drainage

# Categories

EC Erosion Control 

SE Sediment Control

□

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

**☒** Secondary Objective

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

None



# Earth Dikes and Drainage Swales EC-9

- At the top of slopes to divert runon from adjacent or undisturbed slopes
- At bottom and mid slope locations to intercept sheet flow and convey concentrated flows
- Divert sediment laden runoff into sediment basins or traps

#### Limitations

Dikes should not be used for drainage areas greater than 10 acres or along slopes greater than 10 percent. For larger areas more permanent drainage structures should be built. All drainage structures should be built in compliance with local municipal requirements.

- Earth dikes may create more disturbed area on site and become barriers to construction equipment.
- Earth dikes must be stabilized immediately, which adds cost and maintenance concerns.
- Diverted stormwater may cause downstream flood damage.
- Dikes should not be constructed of soils that may be easily eroded.
- Regrading the site to remove the dike may add additional cost.
- Temporary drains and swales or any other diversion of runoff should not adversely impact upstream or downstream properties.
- Temporary drains and swales must conform to local floodplain management requirements.
- Earth dikes/drainage swales are not suitable as sediment trapping devices.
- It may be necessary to use other soil stabilization and sediment controls such as check dams, plastics, and blankets, to prevent scour and erosion in newly graded dikes, swales, and ditches.
- Sediment accumulation, scour depressions, and/or persistent non-stormwater discharges can result in areas of standing water suitable for mosquito production in drainage swales.

#### Implementation

The temporary earth dike is a berm or ridge of compacted soil, located in such a manner as to divert stormwater to a sediment trapping device or a stabilized outlet, thereby reducing the potential for erosion and offsite sedimentation. Earth dikes can also be used to divert runoff from off site and from undisturbed areas away from disturbed areas and to divert sheet flows away from unprotected slopes.

An earth dike does not itself control erosion or remove sediment from runoff. A dike prevents erosion by directing runoff to an erosion control device such as a sediment trap or directing runoff away from an erodible area. Temporary diversion dikes should not adversely impact adjacent properties and must conform to local floodplain management regulations, and should not be used in areas with slopes steeper than 10%.

Slopes that are formed during cut and fill operations should be protected from erosion by runoff. A combination of a temporary drainage swale and an earth dike at the top of a slope can divert

# Earth Dikes and Drainage Swales EC-9

runoff to a location where it can be brought to the bottom of the slope (see EC-11, Slope Drains). A combination dike and swale is easily constructed by a single pass of a bulldozer or grader and compacted by a second pass of the tracks or wheels over the ridge. Diversion structures should be installed when the site is initially graded and remain in place until post construction BMPs are installed and the slopes are stabilized.

Diversion practices concentrate surface runoff, increasing its velocity and erosive force. Thus, the flow out of the drain or swale must be directed onto a stabilized area or into a grade stabilization structure. If significant erosion will occur, a swale should be stabilized using vegetation, chemical treatment, rock rip-rap, matting, or other physical means of stabilization. Any drain or swale that conveys sediment laden runoff must be diverted into a sediment basin or trap before it is discharged from the site.

#### General

- Care must be applied to correctly size and locate earth dikes, drainage swales. Excessively steep, unlined dikes, and swales are subject to erosion and gully formation.
- Conveyances should be stabilized.
- Use a lined ditch for high flow velocities.
- Select flow velocity based on careful evaluation of the risks due to erosion of the measure, soil types, overtopping, flow backups, washout, and drainage flow patterns for each project site.
- Compact any fills to prevent unequal settlement.
- Do not divert runoff onto other property without securing written authorization from the property owner.
- When possible, install and utilize permanent dikes, swales, and ditches early in the construction process.
- Provide stabilized outlets.

#### Earth Dikes

Temporary earth dikes are a practical, inexpensive BMP used to divert stormwater runoff. Temporary diversion dikes should be installed in the following manner:

- All dikes should be compacted by earth moving equipment.
- All dikes should have positive drainage to an outlet.
- All dikes should have 2:1 or flatter side slopes, 18 in. minimum height, and a minimum top width of 24 in. Wide top widths and flat slopes are usually needed at crossings for construction traffic.
- The outlet from the earth dike must function with a minimum of erosion. Runoff should be conveyed to a sediment trapping device such as a Sediment Trap (SE-3) or Sediment Basin

(SE-2) when either the dike channel or the drainage area above the dike are not adequately stabilized.

- Temporary stabilization may be achieved using seed and mulching for slopes less than 5% and either rip-rap or sod for slopes in excess of 5%. In either case, stabilization of the earth dike should be completed immediately after construction or prior to the first rain.
- If riprap is used to stabilize the channel formed along the toe of the dike, the following typical specifications apply:

| Channel Grade | Riprap Stabilization |
|---------------|----------------------|
| 0.5-1.0%      | 4 in. Rock           |
| 1.1-2.0%      | 6 in. Rock           |
| 2.1-4.0%      | 8 in. Rock           |
| 4.1-5.0%      | 8 in12 in. Riprap    |

- The stone riprap, recycled concrete, etc. used for stabilization should be pressed into the soil with construction equipment.
- Filter cloth may be used to cover dikes in use for long periods.
- Construction activity on the earth dike should be kept to a minimum.

### **Drainage Swales**

Drainage swales are only effective if they are properly installed. Swales are more effective than dikes because they tend to be more stable. The combination of a swale with a dike on the downhill side is the most cost effective diversion.

Standard engineering design criteria for small open channel and closed conveyance systems should be used (see the local drainage design manual). Unless local drainage design criteria state otherwise, drainage swales should be designed as follows:

- No more than 5 acres may drain to a temporary drainage swale.
- Place drainage swales above or below, not on, a cut or fill slope.
- Swale bottom width should be at least 2 ft
- Depth of the swale should be at least 18 in.
- Side slopes should be 2:1 or flatter.
- Drainage or swales should be laid at a grade of at least 1 percent, but not more than 15 percent.
- The swale must not be overtopped by the peak discharge from a 10-year storm, irrespective of the design criteria stated above.

## Earth Dikes and Drainage Swales EC-9

- Remove all trees, stumps, obstructions, and other objectionable material from the swale when it is built.
- Compact any fill material along the path of the swale.
- Stabilize all swales immediately. Seed and mulch swales at a slope of less than 5 percent, and use rip-rap or sod for swales with a slope between 5 and 15 percent. For temporary swales, geotextiles and mats (EC-7) may provide immediate stabilization.
- Irrigation may be required to establish sufficient vegetation to prevent erosion.
- Do not operate construction vehicles across a swale unless a stabilized crossing is provided.
- Permanent drainage facilities must be designed by a professional engineer (see the local drainage design criteria for proper design).
- At a minimum, the drainage swale should conform to predevelopment drainage patterns and capacities.
- Construct the drainage swale with a positive grade to a stabilized outlet.
- Provide erosion protection or energy dissipation measures if the flow out of the drainage swale can reach an erosive velocity.

#### Costs

- Cost ranges from \$15 to \$55 per ft for both earthwork and stabilization and depends on availability of material, site location, and access.
- Small dikes: \$2.50 \$6.50/linear ft; Large dikes: \$2.50/yd³.
- The cost of a drainage swale increases with drainage area and slope. Typical swales for controlling internal erosion are inexpensive, as they are quickly formed during routine earthwork.

### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges
- Inspect ditches and berms for washouts. Replace lost riprap, damaged linings or soil stabilizers as needed.
- Inspect channel linings, embankments, and beds of ditches and berms for erosion and accumulation of debris and sediment. Remove debris and sediment and repair linings and embankments as needed.
- Temporary conveyances should be completely removed as soon as the surrounding drainage area has been stabilized or at the completion of construction

# Earth Dikes and Drainage Swales EC-9

#### References

Erosion and Sediment Control Handbook, S.J. Goldman, K. Jackson, T.A. Bursetynsky, P.E., McGraw Hill Book Company, 1986.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Metzger, M.E. 2004. Managing mosquitoes in stormwater treatment devices. University of California Division of Agriculture and Natural Resources, Publication 8125. On-line: http://anrcatalog.ucdavis.edu/pdf/8125.pdf

National Association of Home Builders (NAHB). Stormwater Runoff & Nonpoint Source Pollution Control Guide for Builders and Developers. National Association of Home Builders, Washington, D.C., 1995


National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Southeastern Wisconsin Regional Planning Commission (SWRPC). Costs of Urban Nonpoint Source Water Pollution Control Measures. Technical Report No. 31. Southeastern Wisconsin Regional Planning Commission, Waukesha, WI. 1991

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.


Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.




### NOTES:

- 1. Stabilize inlet, outlets and slopes.
- 2. Properly compact the subgrade.



TYPICAL EARTH DIKE
NOT TO SCALE



### **Description and Purpose**

Outlet protection is a physical device composed of rock, grouted riprap, or concrete rubble, which is placed at the outlet of a pipe or channel to prevent scour of the soil caused by concentrated, high velocity flows.

### **Suitable Applications**

Whenever discharge velocities and energies at the outlets of culverts, conduits, or channels are sufficient to erode the next downstream reach. This includes temporary diversion structures to divert runon during construction.

- These devices may be used at the following locations:
  - Outlets of pipes, drains, culverts, slope drains, diversion ditches, swales, conduits, or channels.
  - Outlets located at the bottom of mild to steep slopes.
  - Discharge outlets that carry continuous flows of water.
  - Outlets subject to short, intense flows of water, such as flash floods.
  - Points where lined conveyances discharge to unlined conveyances

#### Limitations

Large storms or high flows can wash away the rock outlet protection and leave the area susceptible to erosion.

### **Categories**

EC Erosion Control

SE Sediment Control

TC . Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

**☒** Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

 $\overline{\mathbf{Q}}$ 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



- Sediment captured by the rock outlet protection may be difficult to remove without removing the rock.
- Outlet protection may negatively impact the channel habitat.
- Grouted riprap may break up in areas of freeze and thaw.
- If there is not adequate drainage, and water builds up behind grouted riprap, it may cause the grouted riprap to break up due to the resulting hydrostatic pressure.
- Sediment accumulation, scour depressions, and/or persistent non-stormwater discharges can result in areas of standing water suitable for mosquito production in velocity dissipation devices.

### **Implementation**

#### General

Outlet protection is needed where discharge velocities and energies at the outlets of culverts, conduits or channels are sufficient to erode the immediate downstream reach. This practice protects the outlet from developing small eroded pools (plange pools), and protects against gully erosion resulting from scouring at a culvert mouth.

### Design and Layout

As with most channel design projects, depth of flow, roughness, gradient, side slopes, discharge rate, and velocity should be considered in the outlet design. Compliance to local and state regulations should also be considered while working in environmentally sensitive streambeds. General recommendations for rock size and length of outlet protection mat are shown in the rock outlet protection figure in this BMP and should be considered minimums. The apron length and rock size gradation are determined using a combination of the discharge pipe diameter and estimate discharge rate: Select the longest apron length and largest rock size suggested by the pipe size and discharge rate. Where flows are conveyed in open channels such as ditches and swales, use the estimated discharge rate for selecting the apron length and rock size. Flows should be same as the culvert or channel design flow but never the less than the peak 5 year flow for temporary structures planned for one rainy season, or the 10 year peak flow for temporary structures planned for two or three rainy seasons.

- There are many types of energy dissipaters, with rock being the one that is represented in the attached figure.
- Best results are obtained when sound, durable, and angular rock is used.
- Install riprap, grouted riprap, or concrete apron at selected outlet. Riprap aprons are best suited for temporary use during construction. Grouted or wired tied rock riprap can minimize maintenance requirements.
- Rock outlet protection is usually less expensive and easier to install than concrete aprons or energy dissipaters. It also serves to trap sediment and reduce flow velocities.
- Carefully place riprap to avoid damaging the filter fabric.

- Stone 4 in. to 6 in. may be carefully dumped onto filter fabric from a height not to exceed 12 in.
- Stone 8 in. to 12 in. must be hand placed onto filter fabric, or the filter fabric may be covered with 4 in. of gravel and the 8 in. to 12 in. rock may be dumped from a height not to exceed 16 in.
- Stone greater than 12 in. shall only be dumped onto filter fabric protected with a layer of gravel with a thickness equal to one half the  $D_{50}$  rock size, and the dump height limited to twice the depth of the gravel protection layer thickness.
- For proper operation of apron: Align apron with receiving stream and keep straight throughout its length. If a curve is needed to fit site conditions, place it in upper section of apron.
- Outlets on slopes steeper than 10 percent should have additional protection.

#### Costs

Costs are low if material is readily available. If material is imported, costs will be higher. Average installed cost is \$150 per device.

### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Inspect BMPs subjected to non-stormwater discharges daily while non-stormwater discharges occur. Minimize areas of standing water by removing sediment blockages and filling scour depressions.
- Inspect apron for displacement of the riprap and damage to the underlying fabric. Repair fabric and replace riprap that has washed away. If riprap continues to wash away, consider using larger material.
- Inspect for scour beneath the riprap and around the outlet. Repair damage to slopes or underlying filter fabric immediately.
- Temporary devices should be completely removed as soon as the surrounding drainage area has been stabilized or at the completion of construction.

#### References

County of Sacramento Improvement Standards, Sacramento County, May 1989.

Erosion and Sediment Control Handbook, S.J. Goldman, K. Jackson, T.A. Bursztynsky, P.E., McGraw Hill Book Company, 1986.

Handbook of Steel Drainage & Highway Construction, American Iron and Steel Institute, 1983.


Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.


Metzger, M.E. 2004. Managing mosquitoes in stormwater treatment devices. University of California Division of Agriculture and Natural Resources, Publication 8125. On-line: http://anrcatalog.ucdavis.edu/pdf/8125.pdf

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, state of California Department of Transportation (Caltrans), November 2000.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.






SECTION A-A

| Pipe Diameter<br>inches | Discharge<br>ft³/s | Apron Length, La<br>ft | Rip Rap D <sub>50</sub> Diameter<br>Min<br>inches |
|-------------------------|--------------------|------------------------|---|
| 10                      | 5                  | 10                     | 4   |
| 12                      | 10                 | 13                     | 6   |
| -                       | 10                 | 10                     | 6   |
| -0                      | 20                 | 16                     | 8   |
| 18                      | 30                 | 23                     | 12  |
|                         | 40                 | 26                     | 16  |
| -                       | 30                 | 16                     | 8   |
| 24                      | 40                 | 26                     | 8   |
|                         | 50                 | 26                     | 12  |
|                         | 60                 | 30                     | 16  |

For larger or higher flows consult a Registered Civil Engineer

Source: USDA - SCS



### **Description and Purpose**

A slope drain is a pipe used to intercept and direct surface runoff or groundwater into a stabilized watercourse, trapping device, or stabilized area. Slope drains are used with earth dikes and drainage ditches to intercept and direct surface flow away from slope areas to protect cut or fill slopes.

### **Suitable Applications**

- Where concentrated flow of surface runoff must be conveyed down a slope in order to prevent erosion.
- Drainage for top of slope diversion dikes or swales.
- Drainage for top of cut and fill slopes where water can accumulate.
- Emergency spillway for a sediment basin.

#### Limitations

Installation is critical for effective use of the pipe slope drain to minimize potential gully erosion.

- Maximum drainage area per slope drain is 10 acres. (For large areas use a paved chute, rock lined channel, or additional pipes.)
- Severe erosion may result when slope drains fail by overtopping, piping, or pipe separation.
  - During large storms, pipe slope drains may become clogged or over charged, forcing water around the pipe

### Categories

EC Erosion Control  $\mathbf{V}$ 

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control Non-Stormwater NS

Management Control

Waste Management and WW Materials Pollution Control

#### Legend:

Primary Objective

**☒** Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

Trash Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-9 Earth Dike, Drainage Swales



and causing extreme slope erosion.

- If the sectional downdrain is not sized correctly, the runoff can spill over the drain sides causing gully erosion and potential failure of the structure.
- Dissipation of high flow velocities at the pipe outlet is required to avoid downstream erosion.
- Sediment accumulation, scour depressions, and/or persistent non-stormwater discharges can result in areas of standing water suitable for mosquito production in energy dissipaters associated with slope drain outlets.

### **Implementation**

#### General

The slope drain is applicable for any construction site where concentrated surface runoff can accumulate and must be conveyed down the slope in order to prevent erosion. The slope drain is effective because it prevents the stormwater from flowing directly down the slope by confining all the runoff into an enclosed pipe or channel. Due to the time lag between grading slopes and installation of permanent stormwater collection systems and slope stabilization measures, temporary provisions to intercept runoff are sometimes necessary. Particularly in steep terrain, slope drains can protect unstabilized areas from erosion.

#### Installation

The slope drain may be a rigid pipe, such as corrugated metal, a flexible conduit, or a lined terrace drain with the inlet placed on the top of a slope and the outlet at the bottom of the slope. This BMP typically is used in combination with a diversion control, such as an earth dike or drainage swale at the top of the slope.

The following criteria must be considered when siting slope drains.

- Permanent structures included in the project plans can often serve as construction BMPs if implemented early. However, the permanent structure must meet or exceed the criteria for the temporary structure.
- Inlet structures must be securely entrenched and compacted to avoid severe gully erosion.
- Slope drains must be securely anchored to the slope and must be adequately sized to carry the capacity of the design storm and associated forces.
- Outlets must be stabilized with riprap, concrete or other type of energy dissipator, or directed into a stable sediment trap or basin. See EC-10, Velocity Dissipation Devices.
- Debris racks are recommended at the inlet. Debris racks located several feet upstream of the inlet can usually be larger than racks at the inlet, and thus provide enhanced debris protection and less plugging.
- Safety racks are also recommended at the inlet and outlet of pipes where children or animals could become entrapped.
- Secure inlet and surround with dikes to prevent gully erosion and anchor pipe to slope.

■ When using slope drains, limit drainage area to 10 acres per pipe. For larger areas, use a rock lined channel or a series of pipes.

4

- Size to convey at least the peak flow of a 10-year storm. The design storm is conservative due to the potential impact of system failures.
- Maximum slope generally limited to 2:1 (H:V) as energy dissipation below steeper slopes is difficult.
- Direct surface runoff to slope drains with interceptor dikes. See BMP EC-9, Earth Dikes and Drainage Swales. Top of interceptor dikes should be 12 in. higher than the top of the slope drain.
- Slope drains can be placed on or buried underneath the slope surface.
- Recommended materials include both metal and plastic pipe, either corrugated or smooth wall. Concrete pipe can also be used.
- When installing slope drains:
  - Install slope drains perpendicular to slope contours.
  - Compact soil around and under entrance, outlet, and along length of pipe.
  - Securely anchor and stabilize pipe and appurtenances into soil.
  - Check to ensure that pipe connections are watertight.
  - Protect area around inlet with filter cloth. Protect outlet with riprap or other energy dissipation device. For high energy discharges, reinforce riprap with concrete or use reinforced concrete device.
  - Protect outlet of slope drains using a flared end section when outlet discharges to a flexible energy dissipation device.
  - A flared end section installed at the inlet will improve flow into the slope drain and prevent erosion at the pipe entrance. Use a flared end section with a 6 in. minimum toe plate to help prevent undercutting. The flared section should slope towards the pipe inlet.

#### Design and Layout

The capacity for temporary drains should be sufficient to convey at least the peak runoff from a 10-year rainfall event. The pipe size may be computed using the Rational Method or a method established by the local municipality. Higher flows must be safely stored or routed to prevent any offsite concentration of flow and any erosion of the slope. The design storm is purposely conservative due to the potential impacts associated with system failures.

As a guide, temporary pipe slope drains should not be sized smaller than shown in the following table:

| Minimum Pipe Diameter<br>(Inches) | Maximum Drainage Area<br>(Acres) |
|-----------------------------------|----------------------------------|
| 12                                | 1.0                              |
| 18                                | 3.0                              |
| 21                                | 5.0                              |
| 24                                | 7.0                              |
| 30                                | 10.0                             |

Larger drainage areas can be treated if the area can be subdivided into areas of 10 acres or less and each area is treated as a separate drainage. Drainage areas exceeding 10 acres must be designed by a Registered Civil Engineer and approved by the agency that issued the grading permit.

### **Materials:**

Soil type, rainfall patterns, construction schedule, local requirements, and available supply are some of the factors to be considered when selecting materials. The following types of slope drains are commonly used:

- **Rigid Pipe:** This type of slope drain is also known as a pipe drop. The pipe usually consists of corrugated metal pipe or rigid plastic pipe. The pipe is placed on undisturbed or compacted soil and secured onto the slope surface or buried in a trench. Concrete thrust blocks must be used when warranted by the calculated thrust forces. Collars should be properly installed and secured with metal strappings or watertight collars.
- Flexible Pipe: The flexible pipe slope drain consists of a flexible tube of heavy duty plastic, rubber, or composite material. The tube material is securely anchored onto the slope surface. The tube should be securely fastened to the metal inlet and outlet conduit sections with metal strappings or watertight collars.
- Section Downdrains: The section downdrain consists of pre-fabricated, section conduit of half round or third round material. The sectional downdrain performs similar to a flume or chute. The pipe must be placed on undisturbed or compacted soil and secured into the slope.
- Concrete-lined Terrace Drain: This is a concrete channel for draining water from a terrace on a slope to the next level. These drains are typically specified as permanent structures and if installed early, can serve as slope drains during construction, which should be designed according to local drainage design criteria.

#### Costs

Cost varies based on pipe selection and selected outlet protection.

|      | Corrugated Steel Pipes, Per Foot                    |
|------|---|
| Size | Supplied and Installed Cost (No Trenching Included) |
| 12"  | \$19.60 per LF                                      |
| 15"  | \$22.00   |
| 18"  | \$26.00   |
| 24"  | \$32.00   |
| 30"  | \$50.00   |
|      | PVC Pipes, Per Foot                                 |
| Size | Supplied and Installed Cost (No Trenching Included) |
| 12"  | \$24.50   |
| 14"  | \$49.00   |
| 16"  | \$51.00   |
| 18"  | \$54.00   |
| 20"  | \$66.00   |
| 24"  | \$93.00   |
| 30"  | \$130.00  |

### **Inspection and Maintenance**

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Inspect BMPs subjected to non-stormwater discharges daily while non-stormwater discharges occur. Minimize areas of standing water by removing sediment blockages and filling scour depressions.
- Inspect outlet for erosion and downstream scour. If eroded, repair damage and install additional energy dissipation measures. If downstream scour is occurring, it may be necessary to reduce flows being discharged into the channel unless other preventative measures are implemented.
- Insert inlet for clogging or undercutting. Remove debris from inlet to maintain flows. Repair undercutting at inlet and if needed, install flared section or rip rap around the inlet to prevent further undercutting.
- Inspect pipes for leakage. Repair leaks and restore damaged slopes.
- Inspect slope drainage for accumulations of debris and sediment.

- Remove built up sediment from entrances and outlets as required. Flush drains if necessary; capture and settle out sediment from discharge.
- Make sure water is not ponding onto inappropriate areas (e.g., active traffic lanes, material storage areas, etc.).
- Pipe anchors must be checked to ensure that the pipe remains anchored to the slope. Install additional anchors if pipe movement is detected.

#### References

Draft - Sedimentation and Erosion Control, An Inventory of Current Practices, U.S.E.P.A., April 1990.

Metzger, M.E. 2004. Managing mosquitoes in stormwater treatment devices. University of California Division of Agriculture and Natural Resources, Publication 8125. On-line: http://anrcatalog.ucdavis.edu/pdf/8125.pdf


National Association of Home Builders (NAHB). Stormwater Runoff & Nonpoint Source Pollution Control Guide for Builders and Developers. National Association of Home Builders, Washington, D.C., 1995

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.


Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.



TYPICAL SLOPE DRAIN
NOT TO SCALE



### **Description and Purpose**

Stream channels, streambanks, and associated riparian areas are dynamic and sensitive ecosystems that respond to changes in land use activity. Streambank and channel disturbance resulting from construction activities can increase the stream's sediment load, which can cause channel erosion or sedimentation and have adverse affects on the biotic system. BMPs can reduce the discharge of sediment and other pollutants to minimize the impact of construction activities on watercourses. Streams on the 303(d) list and listed for sediment may require numerous measures to prevent any increases in sediment load to the stream.

### **Suitable Applications**

These procedures typically apply to all construction projects that disturb or occur within stream channels and their associated riparian areas.

#### Limitations

Specific permit requirements or mitigation measures such as Regional Water Quality Control Board (RWQCB) 401 Certification, U.S. Army Corps of Engineers 404 permit and approval by California Department of Fish and Game supercede the guidance in this BMP.

 If numerical based water quality standards are mentioned in any of these and other related permits, testing and sampling may be required. Streams listed as 303(d) impaired for sediment, silt, or turbidity, are required to

#### Categories

| EC | Erosion Control                      | ✓ |
|----|--------------------------------------|---|
| SE | Sediment Control                     | × |
| TC | Tracking Control                     |   |
| WE | Wind Erosion Control                 |   |
| NS | Non-Stormwater<br>Management Control | × |

Waste Management and Materials Pollution Control

#### Legend:

| $\square$ | Primary Objective   |
|-----------|---------------------|
| ×         | Secondary Objective |

### **Targeted Constituents**

| Targeted Constituents |           |  |
|-----------------------|-----------|--|
| Sediment              | $\square$ |  |
| Nutrients             |           |  |
| Trash                 |           |  |
| Metals                |           |  |
| Bacteria              |           |  |
| Oll and Grease        |           |  |
| Organics              |           |  |
|                       |           |  |

### **Potential Alternatives**

Combination of erosion and sediment controls.



conduct sampling to verify that there is no net increase in sediment load due to construction activities.

### **Implementation**

#### **Planning**

Proper planning, design, and construction techniques can minimize impacts normally associated with in stream construction activities. Poor planning can adversely affect soil, fish, wildlife resources, land uses, or land users. Planning should take into account: scheduling; avoidance of in-stream construction; minimizing disturbance area and construction time period; using pre-disturbed areas; selecting crossing location; and selecting equipment.

#### Scheduling

- Construction activities should be scheduled according to the relative sensitivity of the
  environmental concerns and in accordance with EC-1, Scheduling. Scheduling
  considerations will be different when working near perennial streams vs. ephemeral streams
  and are as follows.
- When in-stream construction is conducted in a perennial stream, work should optimally be performed during the rainy season. This is because in the summer, any sediment-containing water that is discharged into the watercourse will cause a large change in both water clarity and water chemistry. During the rainy season, there is typically more and faster flowing water in the stream so discharges are diluted faster. However, should in-stream work be scheduled for summer, establishing an isolation area, or diverting the stream, will significantly decrease the amount of sediment stirred up by construction work. Construction work near perennial streams should optimally be performed during the dry season (see below).
- When working in or near ephemeral streams, work should be performed during the dry season. By their very nature, ephemeral streams are usually dry in the summer, and therefore, in-stream construction activities will not cause significant water quality problems. However, when tying up the site at the end of the project, wash any fines (see Washing Fines) that accumulated in the channel back into the bed material, to decrease pollution from the first rainstorm of the season.
- When working near ephemeral or perennial streams, erosion and sediment controls (see silt fences, straw bale barriers, etc.) should be implemented to keep sediment out of stream channel.

#### Minimize Disturbance

Minimize disturbance through: selection of the narrowest crossing location; limiting the number of equipment trips across a stream during construction; and, minimizing the number and size of work areas (equipment staging areas and spoil storage areas). Place work areas at least 50 ft from stream channel. Field reconnaissance should be conducted during the planning stage to identify work areas.

### Use of Pre-Disturbed Areas

■ Locate project sites and work areas in areas disturbed by prior construction or other activity when possible.

#### Selection of Project Site

- Avoid steep and unstable banks, highly erodible or saturated soils, or highly fractured rock.
- Select project site that minimizes disturbance to aquatic species or habitat.

### Equipment Selection

■ Select equipment that reduces the amount of pressure exerted on the ground surface, and therefore, reduces erosion potential and/or use overhead or aerial access for transporting equipment across drainage channels. Use equipment that exerts ground pressures of less than 5 or 6 lb/in², where possible. Low ground pressure equipment includes: wide or high flotation tires (34 to 72 in. wide); dual tires; bogie axle systems; tracked machines; lightweight equipment; and, central tire inflation systems.

#### Streambank Stabilization

### Preservation of Existing Vegetation

Preserve existing vegetation in accordance with EC-2, Preservation of Existing Vegetation. In a streambank environment, preservation of existing vegetation provides the following benefits.

### Water Quality Protection

■ Vegetated buffers on slopes trap sediment and promote groundwater recharge. The buffer width needed to maintain water quality ranges from 15 to 100 ft. On gradual slopes, most of the filtering occurs within the first 30 ft. Steeper slopes require a greater width of vegetative buffer to provide water quality benefits.

### Streambank Stabilization

■ The root system of riparian vegetation stabilizes streambanks by increasing tensile strength in the soil. The presence of vegetation modifies the moisture condition of slopes (infiltration, evapo transpiration, interception) and increases bank stability.

#### Riparian Habitat

- Buffers of diverse riparian vegetation provide food and shelter for riparian and aquatic organisms. Minimizing impacts to fisheries habitat is a major concern when working near streams and rivers. Riparian vegetation provides shade, shelter, organic matter (leaf detritus and large woody debris), and other nutrients that are necessary for fish and other aquatic organisms. Buffer widths for habitat concerns are typically wider than those recommended for water quality concerns (100 to 1500 ft).
- When working near watercourses, it is important to understand the work site's placement in the watershed. Riparian vegetation in headwater streams has a greater impact on overall water quality than vegetation in downstream reaches. Preserving existing vegetation upstream is necessary to maintain water quality, minimize bank failure, and maximize riparian habitat, downstream of the work site.

#### Limitations

 Local county and municipal ordinances regarding width, extent and type of vegetative buffer required may exceed the specifications provided here; these ordinances should be investigated prior to construction.

### Streambank Stabilization Specific Installation

As a general rule, the width of a buffer strip between a road and the stream is recommended to be 50 ft plus four times the percent slope of the land, measured between the road and the top of stream bank.

### Hydraulic Mulch

Apply hydraulic mulch on disturbed streambanks above mean high water level in accordance with EC-3, Hydraulic Mulch to provide temporary soil stabilization.

#### Limitations

■ Do not place hydraulic mulch or tackifiers below the mean high water level, as these materials could wash into the channel and impact water quality or possibly cause eutrophication (eutrophication is an algal bloom caused by excessively high nutrient levels in the water).

### Hydroseeding

Hydroseed disturbed streambanks in accordance with EC-4, Hydroseeding.

#### Limitations

■ Do not place tackifiers or fertilizers below the mean high water level, as these materials could wash into the channel and impact water quality or possibly cause eutrophication.

#### Soil Binders

■ Apply soil binders to disturbed streambanks in accordance with EC-5, Soil Binders.

#### Limitations

■ Do not place soil binders below the mean high water level. Soil binder must be environmentally benign and non-toxic to aquatic organisms.

#### Straw Mulch

Apply straw mulch to disturbed streambanks in accordance with EC-6, Straw Mulch.

#### Limitations

■ Do not place straw mulch below the mean high water level, as this material could wash into the channel and impact water quality or possibly cause eutrophication.

#### Geotextiles and Mats

■ Install geotextiles and mats as described in EC-7, Geotextiles and Mats, to stabilize disturbed channels and streambanks. Not all applications should be in the channel, for example, certain geotextile netting may snag fish gills and are not appropriate in fish bearing streams. Geotextile fabrics that are not biodegradable are not appropriate for in stream use. Additionally, geotextile fabric or blankets placed in channels must be adequate to sustain anticipated hydraulic forces.

### Earth Dikes, Drainage Swales, and Lined Ditches

 Convey, intercept, or divert runoff from disturbed streambanks using EC-9, Earth Dikes and Drainage Swales.

#### Limitations

- Do not place earth dikes in watercourses, as these structures are only suited for intercepting sheet flow, and should not be used to intercept concentrated flow.
- Appropriately sized velocity dissipation devices (EC-10) must be placed at outlets to minimize erosion and scour.

### Velocity Dissipation Devices

 Place velocity dissipation devices at outlets of pipes, drains, culverts, slope drains, diversion ditches, swales, conduits or channels in accordance with EC-10, Velocity Dissipation Devices.

### Slope Drains

 Use slope drains to intercept and direct surface runoff or groundwater into a stabilized watercourse, trapping device or stabilized area in accordance with EC-11, Slope Drains.

#### Limitations

 Appropriately sized outlet protection and velocity dissipation devices (EC-10) must be placed at outlets to minimize erosion and scour.

### Streambank Sediment Control

#### Silt Fences

■ Install silt fences in accordance with SE-1, Silt Fence, to control sediment. Silt fences should only be installed where sediment laden water can pond, thus allowing the sediment to settle out.

#### Fiber Rolls

■ Install fiber rolls in accordance with SE-5, Fiber Rolls, along contour of slopes above the high water level to intercept runoff, reduce flow velocity, release the runoff as sheet flow and provide removal of sediment from the runoff. In a stream environment, fiber rolls should be used in conjunction with other sediment control methods such as SE-1, Silt Fence or SE-9 Straw Bale Barrier. Install silt fence, straw bale barrier, or other erosion control method along toe of slope above the high water level.

#### Gravel Bag Berm

A gravel bag berm or barrier can be utilized to intercept and slow the flow of sediment laden sheet flow runoff in accordance with SE-6, Gravel Bag Berm. In a stream environment gravel bag barriers can allow sediment to settle from runoff before water leaves the construction site and can be used to isolate the work area from the live stream.

### Limitations

 Gravel bag barriers are not recommended as a perimeter sediment control practice around streams.

### Straw Bale Barrier

■ Install straw bale barriers in accordance with SE-9, Straw Bale Barrier, to control sediment. Straw bale barriers should only be installed where sediment laden water can pond, thus allowing the sediment to settle out. Install a silt fence in accordance with SE-1, Silt Fence,

on down slope side of straw bale barrier closest to stream channel to provide added sediment control.

#### **Rock Filter**

### Description and Purpose

Rock filters are temporary erosion control barriers composed of rock that is anchored in place. Rock filters detain the sediment laden runoff, retain the sediment, and release the water as sheet flow at a reduced velocity. Typical rock filter installations are illustrated at the end of this BMP.

#### **Applications**

• Near the toe of slopes that may be subject to flow and rill erosion.

#### Limitations

- Inappropriate for contributing drainage areas greater than 5 acres.
- Requires sufficient space for ponded water.
- Ineffective for diverting runoff because filters allow water to slowly seep through.
- Rock filter berms are difficult to remove when construction is complete.
- Unsuitable in developed areas or locations where aesthetics is a concern.

### Specifications

- Rock: open graded rock, 0.75 to 5 in. for concentrated flow applications.
- Woven wire sheathing: 1 in. diameter, hexagonal mesh, galvanized 20gauge (used with rock filters in areas of concentrated flow).
- In construction traffic areas, maximum rock berm heights should be 12 in. Berms should be constructed every 300 ft on slopes less than 5%, every 200 ft on slopes between 5% and 10%, and every 100 ft on slopes greater than 10%.

#### Maintenance

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Reshape berms as needed and replace lost or dislodged rock, and filter fabric.
- Sediment that accumulates in the BMP must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one third of the barrier height. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed at an appropriate location.

#### K-rail

### Description and Purpose

This is temporary sediment control that uses K-rails to form the sediment deposition area, or to isolate the near bank construction area. Install K-rails at toe of slope in accordance with procedures described in NS-5, Clear Water Diversion.

Barriers are placed end to end in a pre-designed configuration and gravel filled bags are used at the toe of the barrier and at their abutting ends to seal and prevent movement of sediment beneath or through the barrier walls.

### Appropriate Applications

■ This technique is useful at the toe of embankments, cuts or fills slopes.

#### Limitations

■ The K-rail method should not be used to dewater a project site, as the barrier is not watertight.

### *Implementation*

■ Refer to NS-5, Clear Water Diversion, for implementation requirements.

#### **Instream Construction Sediment Control**

There are three different options currently available for reducing turbidity while working in a stream or river. The stream can be isolated from the area in which work is occurring by means of a water barrier, the stream can be diverted around the work site through a pipe or temporary channel, or one can employ construction practices that minimize sediment suspension.

Whatever technique is implemented, an important thing to remember is that dilution can sometimes be the solution. A probable "worst time" to release high TSS into a stream system might be when the stream is very low; summer low flow, for example. During these times, the flow may be low while the biological activity in the stream is very high. Conversely, the addition of high TSS or sediment during a big storm discharge might have a relatively low impact, because the stream is already turbid, and the stream energy is capable of transporting both suspended solids, and large quantities of bedload through the system. The optimum time to "pull" in-stream structures may be during the rising limb of a storm hydrograph.

#### Techniques to minimize Total Suspended Solids (TSS)

- Padding Padding laid in the stream below the work site may trap some solids that are
  deposited in the stream during construction. After work is done, the padding is removed
  from the stream, and placed on the bank to assist in re-vegetation.
- Clean, washed gravel Using clean, washed gravel decreases solid suspension, as there
  are fewer small particles deposited in the stream.
- Excavation using a large bucket Each time a bucket of soil is placed in the stream, a portion is suspended. Approximately the same amount is suspended whether a small amount of soil is placed in the stream, or a large amount. Therefore, using a large excavator bucket instead of a small one, will reduce the total amount of soil that washes downstream.

- Use of dozer for backfilling Using a dozer for backfilling instead of a backhoe follows the same principles the fewer times soil is deposited in the stream, the less soil will be suspended.
- Partial dewatering with a pump Partially dewatering a stream with a pump reduces the amount of water, and thus the amount of water that can suspend sediment.

### **Washing Fines**

### Definition and Purpose

- Washing fines is an "in-channel" sediment control method, which uses water, either from a water truck or hydrant, to wash stream fines that were brought to the surface of the channel bed during restoration, back into the interstitial spaces of the gravel and cobbles.
- The purpose of this technique is to reduce or eliminate the discharge of sediment from the channel bottom during the first seasonal flow. Sediment should not be allowed into stream channels; however, occasionally in-channel restoration work will involve moving or otherwise disturbing fines (sand and silt sized particles) that are already in the stream, usually below bankfull discharge elevation. Subsequent re-watering of the channel can result in a plume of turbidity and sedimentation.
- This technique washes the fines back into the channel bed. Bedload materials, including gravel cobbles, boulders and those fines, are naturally mobilized during higher storm flows. This technique is intended to delay the discharge until the fines would naturally be mobilized.

#### Appropriate Applications

This technique should be used when construction work is required in channels. It is especially useful in intermittent or ephemeral streams in which work is performed "in the dry", and which subsequently become re-watered.

#### Limitations

- The stream must have sufficient gravel and cobble substrate composition.
- The use of this technique requires consideration of time of year and timing of expected stream flows.
- The optimum time for the use of this technique is in the fall, prior to winter flows.
- Consultation with, and approval from the Department of Fish and Game and the Regional Water Quality Control Board may be required.

#### **Implementation**

- Apply sufficient water to wash fines, but not cause further erosion or runoff.
- Apply water slowly and evenly to prevent runoff and erosion.
- Consult with Department of Fish and Game and the Regional Water Quality Control Board for specific water quality requirements of applied water (e.g. chlorine).

Inspection and Maintenance

None necessary

#### Costs

Cost may vary according to the combination of practices implemented.

### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Inspect and repair equipment (for damaged hoses, fittings, and gaskets).

#### References

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.


Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group Working Paper, USEPA, April 1992.


Sedimentation and Erosion Control Practices, An Inventory of Current Practices (Draft), UESPA, 1990.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.





PLAN

TYPICAL ROCK FILTER NOT TO SCALE

Reserved EC-13

BMP Factsheet removed in 2009. Formerly PAM. See SE-11, Active Treatment Systems.

### **Categories**

EC Erosion Control
SE Sediment Control
TC Tracking Control
WE Wind Erosion Control
NS Non-Stormwater
Management Control
Waste Management and
Materials Pollution Control

#### Legend:


☑ Primary Category☑ Secondary Category

### **Targeted Constituents**

Sediment Nutrients Trash Metals Bacteria Oil and Grease Organics

### **Potential Alternatives**





### **Description and Purpose**

A compost blanket is applied to slopes and earth disturbed areas to prevent erosion, and in some cases, increase infiltration and/or establish vegetation. The compost blanket can be applied by hand, conveyor system, compost spreader, or pneumatic delivery (blower) system. The blanket thickness is determined from the slope steepness and anticipated precipitation. A compost blanket protects the soil surface from raindrop erosion, particularly rills and gullies that may form under other methods of erosion control.

A compost blanket, if properly installed, can be very successful at vegetation establishment, weed suppression and erosion control. The compost blanket comes into direct contact with the underlying soil, reducing rill formation. Furthermore, compost provides organic matter and nutrients important for vegetation growth. The compost blanket provides soil structure that allows water to infiltrate the soil surface and retain moisture, which also promotes seed germination and vegetation growth, in addition to reducing runoff.

Compost is typically derived from combinations of feedstocks, biosolids, leaf and yard trimmings, manure, wood, or mixed solid waste. Many types of compost are products of municipal recycle or "Greenwaste" programs. Compost is organic and biodegradable and can be left onsite. There are many types of compost with a variety of properties with specific functions, and accordingly, compost selection is an important design consideration in the application of this type of erosion control.

### **Categories**

EC **Erosion Control** 

 $\square$ 

SE **Sediment Control** TC **Tracking Control** 

WE Wind Erosion Control

Non-Stormwater

NS Management Control

Waste Management and Materials Pollution Control

#### Legend:

Primary Category

Secondary Category

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-4 Hydroseeding

**EC-5 Soil Binders** 

EC-7 Geotextiles and Mats

EC-8 Wood Mulching



### **Suitable Applications**

A compost blanket is appropriate for slopes and earth disturbed areas requiring protection until permanent stabilization is established. A compost blanket can also used in combination with temporary and/or permanent seeding strategies to enhance plant establishment. Examples include:

- Rough-graded areas that will remain inactive for longer than 14 days
- Soil stockpiles
- Slopes with exposed soil between existing vegetation such as trees or shrubs
- Slopes planted with live, container-grown vegetation
- Disturbed areas where plants are slow to develop

A compost blanket is typically used on slopes of 2:1 (H:V) or gentler. However, a compost blanket can be effective when applied to slopes as steep as 1:1 (H:V) with appropriate design considerations including slope length, blanket thickness, adding components such as a tackifier, or using compost blankets in conjunction with other techniques, such as compost socks and berms or fiber rolls.

Compost can be pre-seeded prior to application to the soil (recommended by the EPA for construction site stormwater runoff control) or seeded after the blanket has been installed. The compost medium can also remove pollutants in stormwater including heavy metals; oil and grease; and hydrocarbons (USEPA, 1998).

#### Limitations

- Compost can potentially leach nutrients (dissolved phosphorus and nitrogen) into runoff and potentially impact water quality. Compost should not be used directly upstream from nutrient impaired waterbodies (Adams et. al, 2008).
- Compost may also contain other undesirable constituents that are detrimental to water quality. Carefully consider the qualifications and experience of any compost producer/supplier.
- A compost blanket applied by hand is more time intensive and potentially costly. Using a pneumatic blower truck is the recommended cost effective method of application.
- When blowers are used, the treatment areas should be within 300 ft of a road or surface capable of supporting trucks.
- Wind may limit application of compost and result in application to undesired locations.
- Compost blankets should not be applied in areas of concentrated flows.
- Steeper slopes may require additional blanket thickness and other stability measures such as using tackifiers or slope interruption devices (compost socks and berms, or fiber rolls). The same applies for sites with high precipitation totals or during the rainy season.

### **Implementation**

Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### **Compost Materials**

- California Compost Regulations (Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3) define and require a quality of compost for application. Compost should comply with all physical and chemical requirements. Specific requirements are provided in Table 1 below, taken from Caltrans Standard Special Provision 10-1 (SSP 10-1), Erosion Control (Compost Blanket).
- The compost producer should be fully permitted as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility should certify that it follows guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
- The compost producer should be a participant in United States Composting Council's Seal of Testing Assurance program.
- Compost moisture should be considered for composition quality and application purposes. A range of 30-50% is typical. Compost that is too dry is hard to apply and compost that is too wet is more difficult (and more expensive) to transport. For arid or semi-arid areas, or for application during the dry season, use compost with greater moisture content than areas with wetter climates. For wetter or more humid climates or for application during the wet season, drier composts can be used as the compost will absorb moisture from the ambient air.
- Organic content of the compost is also important and should range from 30 to 65% depending on site conditions.
- Compost should be high-quality mature compost. Immature compost can potentially leach nutrients.
- Compost should not be derived from mixed municipal solid waste and should be free of visible contaminants.
- Compost should not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Metal concentrations in compost should not exceed the maximum metal concentrations listed under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.
- Compost should not possess objectionable odors.
- Compost should be weed free.

Table 1. Physical/Chemical Requirements of Compost
Reference - Caltrans SSP-10 Erosion Control Blanket (Compost)

| Property              | Test Method  | Requirement   |
|-----------------------|--|---|
| Troperty              | *TMECC 04:11-A                                       | - Requirement   |
| рН                    | Elastometric pH 1:5 Slurry Method                    | 6.0-8.0   |
|                       | pH Units   |   |
| 0.1.1.1.0.1.          | TMECC 04.10-A  | ,                 |
| Soluble Salts         | Electrical Conductivity 1:5 Slurry Method            | 0-10.0  |
|                       | dS/m (mmhos/cm)                                      |   |
| 17.                   | TMECC 03.09-A  |   |
| Moisture Content      | Total Solids & Moisture at 70+/- 5 deg C             | 30-60   |
|                       | % Wet Weight Basis                                   |   |
| Organic Matter        | TMECÇ 05.07-A  | ,   |
| Content               | Loss-On-Ignition Organic Matter Method (LOI)         | 30-65   |
| Content               | % Dry Weight Basis                                   |   |
|                       | TMEČC 05.05-A  |   |
| Maturity              | Germination and Vigor                                | 80 or Above   |
|                       | Seed Emergence                                       | 80 or Above   |
|                       | Seedling Vigor                                       |   |
|                       | % Relative to Positive Control                       |   |
| G. 1 114              | TMECC 05.08-B  | 011   |
| Stability             | Carbon Dioxide Evolution Rate                        | 8 or below  |
|                       | mg CO <sub>2</sub> -C/g OM per day                   | 100% Passing, 3 inch                                    |
|                       | TMECC 02.02-B  | 90-100% Passing, 3 inch                                 |
| Particle Size         | Sample Sieving for Aggregate Size Classification     | 65-100% Passing, 3/4 inch                               |
| I al ticle bize       | % Dry Weight Basis                                   | 03-100% 1 assing, 3/4 inch<br>0 - 75% Passing, 1/4 inch |
|                       | No Dif Weight Duois                                  | Maximum length 6 inches                                 |
|                       | TMECC 07.01-B  |   |
| Pathogen              | Fecal Coliform Bacteria                              | Pass  |
|                       | < 1000 MPN/gram dry wt.                              |   |
| N-+1                  | TMECC,07,01-B  |   |
| Pathogen              | Salmonella   | Pass  |
|                       | < 3 MPN/4 grams dry wt.                              |   |
| Physical Contaminants | TMECC 02.02-C  | 1   |
|                       | Man Made Inert Removal and Classification:           | Combined Total:   |
|                       | Plastic, Glass and Metal                             | < 1.0   |
|                       | % > 4mm fraction                                     |   |
| Physical Contaminants | TMECC 02.02-C  | 1   |
|                       | Man Made Inert Removal and Classification:           |   |
|                       | Sharps (Sewing needles, straight pins and hypodermic | None Detected   |
|                       | needles)   | •   |
|                       | % > 4mm fraction                                     |   |

<sup>\*</sup>TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

### Installation

- Prior to compost application, prepare the slope by removing loose rocks, roots, stumps, and other debris greater than 2" in diameter. Prepare the slope area surface by scarifying or track walking/roughening if necessary.
- Select method to apply the compost blanket. A pneumatic blower is most cost effective and most adaptive in applying compost to steep, rough terrain, and hard to reach locations.
- A compost blanket thickness of 1" to 4" should be applied to slopes of 2:1 (H:V) or gentler, based on site-specific conditions. Increase blanket thickness with increased slope steepness and/or during installation during the rainy season (for example, 2" to 3" should be used for a

3:1 slope, while 1" to 2" can be used for a 4:1 slope). Erosion control using a compost blanket is not recommended for slopes greater than 1:1 (H:V).

- For steeper slopes, tackifiers should be utilized and/or other stabilization techniques employed. For example, compost socks or berms can be installed at intervals over the compost blanket (in a similar manner as Fiber Rolls, SE-5).
- Compost socks or berms (or equivalent linear sediment control BMP) should be placed at the top and/or bottom of the slope for additional erosion control performance.
- For optimum vegetation establishment, a blanket thickness of 1" to 2" is recommended. If vegetation establishment is not the primary function of the compost blanket, a thicker blanket may be recommended based on slope or rainfall conditions.
- Evenly distribute compost on the soil surface to the desired blanket thickness (1/2" to 4" as calculated prior based on site conditions and objectives). Even distribution is an important factor in preventing future rill and gully erosion.
- The compost blanket should extend 3 to 6 feet over the top of the shoulder of the slope. A compost sock or compost berm can be used at the top of the slope as an auxiliary technique to prevent runoff from flowing underneath the compost blanket.
- Use additional anchoring and erosion control BMPs in conjunction of the compost blanket as needed.

#### Costs

The cost associated with a compost blanket is similar to that of a straw mat and generally less expensive than a geotextile blanket (USEPA, 2009). Caltrans has provided a recent estimate for \$5,000 to \$8,000 per acre for application of an unseeded 1 inch compost blanket (Caltrans Compost Specifications, 2009). Recently obtained vendor costs indicate that proprietary blends of compost that are seeded and contain a nutrient rich "tackifier" can cost approximately \$0.35 per square foot, or approximately \$15,000 per acre for a 2 inch blanket. Application by hand is more time intensive and likely more costly.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Areas where erosion is evident, another layer of compost should be reapplied as soon as possible. It may be necessary to install an additional type of stormwater BMP at the top of slope or as a slope interrupter to control flow, such as a fiber roll (SE-5) or compost sock (SE-11).
- Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs.
- Limit or prohibit foot traffic to minimize damage to BMP or impede vegetation establishment.

#### References

An Analysis of Composting as an Environmental Remediation Technology, U.S. Environmental Protection Agency (USEPA), Solid Waste and Emergency Response (5305W), EPA530-R-8-008, 1998.

Characteristics of Compost: Moisture Holding and Water Quality Improvement, Center for Research in Water Resources, Kirchoff, C., Malina, J., and Barrett, M., 2003.

Compost Utilization for Erosion Control, The University of Georgia College of Agricultural and Environmental Sciences, pubs.caes.uga.edu/caespubs/pubcd/B1200.htm, Faucette, B. and Risse, M., 2009.

Demonstration Project Using Yard Debris Compost for Erosion Control, Final Report, presented to Metropolitan Service District, W&H Pacific, 1993.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, 2005.

Standard Special Provision 10-1, Erosion Control (Compost Blanket), California Department of Transportation (Caltrans). 2007 Update.

Evaluation of Environmental Benefits and Impacts of Compost and Industry Standard Erosion and Sediment Controls Measures Used in Construction Activities, Dissertation, Institute of Ecology, University of Georgia, Faucette, B., 2004.

Filter Sock Presentation provided at Erosion, Sediment Control and Stormwater Management with Compost BMPs Workshop, U.S. Composting Council 13<sup>th</sup> Annual Conference and Trade Show, McCov, S., 2005.

National Pollutant Discharge Elimination System (NPDES), Compost Blankets, U.S. Environmental Protection Agency (USEPA).

http://cfpub.epa.gov/npdes/stormwater/menuofbmps/index.cfm?action=factsheet\_results&vie w=specific&bmp=118, 2009.

Standard Specifications for Transportation Materials and Methods of Sampling and Testing Designation M10-03, Compost for Erosion/Sediment Control (Compost Blankets), Provisional, American Association of State Highway Transportation Officials (AASHTO), 2003.

Stormwater Best Management Practices (BMPs) Field Trials of Erosion Control Compost in Reclamation of Rock Quarry Operations, Nonpoint Source Protection Program CWA §319(h), Texas Commission on Environmental Quality, Adams, T., McFarland, A., Hauck, L., Barrett, M., and Eck, B., 2008.



### **Description and Purpose**

Soil Preparation/Roughening involves assessment and preparation of surface soils for BMP installation. This can include soil testing (for seed base, soil characteristics, or nutrients), as well as roughening surface soils by mechanical methods (including sheepsfoot rolling, track walking, scarifying, stair stepping, and imprinting) to prepare soil for additional BMPs, or to break up sheet flow. Soil Preparation can also involve tilling topsoil to prepare a seed bed and/or incorporation of soil amendments, to enhance vegetative establishment.

### **Suitable Applications**

**Soil preparation:** Soil preparation is essential to proper vegetative establishment. In particular, soil preparation (i.e. tilling, raking, and amendment) is suitable for use in combination with any soil stabilization method, including RECPs or sod. Soil preparation should not be confused with roughening.

Roughening: Soil roughening is generally referred to as track walking (sometimes called imprinting) a slope, where treads from heavy equipment run parallel to the contours of the slope and act as mini terraces. Soil preparation is most effective when used in combination with erosion controls. Soil Roughening is suitable for use as a complementary process for controlling erosion on a site. Roughening is not intended to be used as a stand-alone BMP, and should be used with perimeter controls, additional erosion control measures, grade breaks, and vegetative establishment for maximum effectiveness. Roughening is intended to only affect surface soils and should not compromise slope stability or overall compaction. Suitable applications for soil roughening include:

| Categories |  |
|------------|--|
|            |  |

EC Erosion Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

Secondary Category

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

EC-3 Hydraulic Mulch

EC-5 Soil Binders

EC-7 Geotextiles and Mats



- Along any disturbed slopes, including temporary stockpiles, sediment basins, or compacted soil diversion berms and swales.
- Roughening should be used in combination with hydraulically applied stabilization methods, compost blanket, or straw mulch; but should not be used in combination with RECPs or sod because roughening is intended to leave terraces on the slope.

#### Limitations

- Preparation and roughening must take place prior to installing other erosion controls (such as hydraulically applied stabilizers) or sediment controls (such as fiber rolls) on the faces of slopes.
- In such cases where slope preparation is minimal, erosion control/revegetation BMPs that
  do not require extensive soil preparation such as hydraulic mulching and seeding
  applications should be employed.
- Consideration should be given to the type of erosion control BMP that follows surface preparation, as some BMPs are not designed to be installed over various types of tillage/roughening, i.e., RECPs (erosion control blankets) should not be used with soil roughening due to a "bridging" effect, which suspends the blanket above the seed bed.
- Surface roughness has an effect on the amount of mulch material that needs to be applied, which shows up as a general increase in mulch material due to an increase in surface area (Topographic Index -see EC-3 Hydraulic Mulching).

### **Implementation**

■ Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### General

A roughened surface can significantly reduce erosion. Based on tests done at the San Diego State Erosion Research Laboratory, various roughening techniques on slopes can result in a 12 - 76% reduction in the erosion rate versus smooth slopes.

#### Materials

Minimal materials are required unless amendments and/or seed are added to the soil. The majority of soil roughening/preparation can be done with equipment that is on hand at a normal construction site, such as bull dozers and compaction equipment.

## **Installation Guidelines**

### **Soil Preparation**

- Where appropriate or feasible, soil should be prepared to receive the seed by disking or otherwise scarifying the surface to eliminate crust, improve air and water infiltration and create a more favorable environment for germination and growth.
- Based upon soil testing conducted, apply additional soil amendments (e.g. fertilizers, additional seed) to the soil to help with germination. Follow EC-4, Hydroseeding, when selecting and applying seed and fertilizers.

### **Cut Slope Roughening:**

- Stair-step grade or groove the cut slopes that are steeper than 3:1.
- Use stair-step grading on any erodible material soft enough to be ripped with a bulldozer.
   Slopes consisting of soft rock with some subsoil are particularly suited to stair-step grading.
- Make the vertical cut distance less than the horizontal distance, and slightly slope the horizontal position of the "step" in toward the vertical wall.
- Do not make individual vertical cuts more than 2 feet (0.6 m) high in soft materials or more than 3 feet (0.9 m) high in rocky materials.
- Groove the slope using machinery to create a series of ridges and depressions that run across the slope, on the contour.

### Fill Slope Roughening:

- Place on fill slopes with a gradient steeper than 3:1 in lifts not to exceed 8 inches (0.2 m), and make sure each lift is properly compacted.
- Ensure that the face of the slope consists of loose, uncompacted fill 4-6 inches (0.1-0.2 m) deep.
- Use grooving or tracking to roughen the face of the slopes, if necessary.
- Do not blade or scrape the final slope face.

#### Roughening for Slopes to be Mowed:

- Slopes which require mowing activities should not be steeper than 3:1.
- Roughen these areas to shallow grooves by track walking, scarifying, sheepsfoot rolling, or imprinting.
- Make grooves close together (less than 10 inches), and not less than 1 inch deep, and perpendicular to the direction of runoff (i.e., parallel to the slope contours).
- Excessive roughness is undesirable where moving is planned.

#### **Roughening With Tracked Machinery:**

- Limit roughening with tracked machinery to soils with a sandy textural component to avoid undue compaction of the soil surface.
- Operate tracked machinery up and down the slope to leave horizontal depressions in the soil. Do not back-blade during the final grading operation.
- Seed and mulch roughened areas as soon as possible to obtain optimum seed germination and growth.

#### Costs

Costs are based on the additional labor of tracking or preparation of the slope plus the cost of any required soil amendment materials.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Check the seeded slopes for signs of erosion such as rills and gullies. Fill these areas slightly above the original grade, then reseed and mulch as soon as possible.
- Inspect BMPs weekly during normal operations, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.

#### References

Soil Stabilization BMP Research for Erosion and Sediment Controls: Cost Survey Technical Memorandum, State of California Department of Transportation (Caltrans), July 2007.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.



#### **Description and Purpose**

Non-vegetative stabilization methods are used for temporary or permanent stabilization of areas prone to erosion and should be used only where vegetative options are not feasible; examples include:

- Areas of vehicular or pedestrian traffic such as roads or paths;
- Arid environments where vegetation would not provide timely ground coverage, or would require excessive irrigation;
- Rocky substrate, infertile or droughty soils where vegetation would be difficult to establish; and
- Areas where vegetation will not grow adequately within the construction time frame.

There are several non-vegetative stabilization methods and selection should be based on site-specific conditions.

**Decomposed Granite (DG)** is a permanent erosion protection method that consists of a layer of stabilized decomposed granite placed over an erodible surface.

**Degradable Mulches** of various types (see EC-3, EC-6, EC-8) can be used for temporary non-vegetative stabilization; examples include straw mulch, compost, wood chips or hydraulic mulch.

Geotextiles and Mats can be used for temporary non-vegetative stabilization (see EC-7). These BMPs are typically manufactured

# Categories EC Erosion Control SE Sediment Control TR Tracking Control WE Wind Erosion Control Non-Stormwater Management Control WM Waste Management and Materials Pollution Control

#### Legend:

- ☑ Primary Category
- Secondary Category

#### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



from degradable or synthetic materials and are designed and specified based on their functional longevity, i.e., how long they will persist and provide erosion protection. All geotextiles and mats should be replaced when they exceed their functional longevity or when permanent stabilization methods are instituted.

**Gravel Mulch** is a non-degradable erosion control product that is composed of washed and screened coarse to very coarse gravel, 16 mm to 64 mm (0.6" - 2.5"), similar to an AASHTO No. 3 coarse aggregate.

**Rock Slope Protection** consists of utilizing large rock or rip-rap (4"- 24") to stabilize slopes with a high erosion potential and those subject to scour along waterways.

**Soil Binders** can be used for temporary non-vegetative stabilization (see EC-5). The key to their use is functional longevity. In most cases, the soil binder will need to be routinely monitored and re-applied to maintain an erosion-resistant coverage.

#### **Suitable Applications**

Non-vegetated stabilization methods are suitable for use on disturbed soil areas and on material stockpiles that need to be temporarily or permanently protected from erosion by water and wind. Non-vegetated stabilization should only be utilized when vegetation cannot be established in the required timeframe, due to soil or climactic conditions, or where vegetation may be a potential fire hazard.

**Decomposed Granite (DG) and Gravel Mulch** are suitable for use in areas where vegetation establishment is difficult, on flat surfaces, trails and pathways, and when used in conjunction with a stabilizer or tackifier, on shallow slopes (i.e., 10:1 [H:V]). DG and gravel can also be used on shallow rocky slopes where vegetation cannot be established for permanent erosion control.

**Degradable Mulches** can be used to cover and protect soil surfaces from erosion both in temporary and permanent applications. In many cases, the use of mulches by themselves requires routine inspection and re-application. See EC-3 Hydraulic Mulch, EC-6 Straw Mulch, EC-8 Wood Mulch, or EC-14 Compost Blankets for more information.

Geotextiles and Mats can be used as a temporary stand-alone soil stabilization method. Depending on material selection, geotextiles and mats can be a short-term (3 mos - 1 year) or long-term (1-2 years) temporary stabilization method. For more information on geotextiles and mats see EC-7 Geotextiles and Mats.

**Rock Slope Protection** can be used when the slopes are subject to scour or have a high erosion potential, such as slopes adjacent to flowing waterways or slopes subject to overflow from detention facilities (spillways).

**Soil Binders** can be used for temporary stabilization of stockpiles and disturbed areas not subject to heavy traffic. See EC-5 Soil Binders for more information.

#### Limitations

#### General

Refer to EC-3, EC-6, EC-8, and EC-14 for limitations on use of mulches. Refer to EC-7 for limitations on use of geotextiles and mats. Refer to EC-5 for limitations on use of Soil Binders.

#### **Decomposed Granite**

- Not available in some geographic regions.
- If not tackified, material may be susceptible to erosion even on slight slopes (e.g., 30:1 [H:V]).
- Installed costs may be more expensive than vegetative stabilization methods.

#### Gravel Mulch

- Availability is limited in some geographic regions.
- If not properly screened and washed, can contain fine material that can erode and/or create dust problems.
- If inadequately sized, material may be susceptible to erosion on sloped areas.
- Pore spaces fill with dirt and debris over time; may provide a growing medium for weeds.

#### Rock Slope Protection

- Installation is labor intensive.
- Installed costs can be significantly higher than vegetative stabilization methods.
- Rounded stones may not be used on slopes greater than 2:1 [H:V].

#### Implementation

#### General

Non-vegetated stabilization should be used in accordance with the following general guidance:

- Should be used in conjunction with other BMPs, including drainage, erosion controls and sediment controls:
- Refer to EC-3, EC-6, EC-8, and EC-14 for implementation details for mulches. Refer to EC-7 for implementation details for geotextiles and mats. Refer to EC-5 for implementation details for soil binders.
- Non-vegetated stabilization measures should be implemented as soon as the disturbance in the areas they are intended to protect has ceased.
- Additional guidance on the comparison and selection of temporary slope stabilization methods is provided in Appendix F of the Handbook.

#### Decomposed Granite Stabilization

If used for a road or path should be installed on a prepared base.

11 to 12

- Should be mixed with a stabilizer if used for roads or pathways, or on slope applications.
- Though porous it is recommended to prevent standing water on or next to a decomposed granite road or pathway.

#### Gravel Mulch

- Should be sized based on slope, rainfall, and upgradient run-on conditions. Stone size should be increased as potential for erosion increases (steeper slopes, high intensity rainfall).
- If permanent, a weed control fabric should be placed prior to installation.
- Should be installed at a minimum 2" depth.
- Should completely cover all exposed surfaces.

#### Rock Slope Protection

- Rock slope protection installation should follow Caltrans Standard Specification 72-2: Rock Slope Protection. Refer to the specification for rock conformity requirements and installation methods.
- When using rock slope protection, rock size and installation method should be specified by an Engineer.
- A geotextile fabric should be placed prior to installation.

#### Costs

■ Costs are highly variable depending not only on technique chosen, but also on materials chosen within specific techniques. In addition, availability of certain materials will vary by region/location, which will also affect the cost. Costs of mulches, geotextiles and mats, and soil binders are presented in their respective fact sheets. Costs for decomposed granite, gravel mulch stabilization and rock slope protection may be higher depending on location and availability of materials. Caltrans has provided an estimate for gravel mulch of \$10 - \$15/yd² in flat areas and \$11 - \$23/yd² on side slopes.

#### **Inspection and Maintenance**

#### General

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- For permanent installation, require inspection periodically and after major storm events to look for signs of erosion or damage to the stabilization.
- All damage should be repaired immediately.
- Refer to EC-3, EC-6, EC-8, and EC-14 for inspection and maintenance requirements for mulches. Refer to EC-7 for inspection and maintenance requirements for geotextiles and mats. Refer to EC-5 for inspection and maintenance requirements for soil binders.

#### Decomposed Granite and Gravel Mulch Stabilization

- Rake out and add decomposed granite or gravel as needed to areas subject to rill erosion. Inspect upgradient drainage controls and repair/modify as necessary.
- Should remain stable under loose surface material. Any significant problem areas should be repaired to restore uniformity to the installation.

#### References

Arid Zone Forestry: A Guide for Field Technicians. Food and Agriculture Organization of the United Nations, 1989.

Design of Roadside Channels with Flexible Linings, Hydraulic Engineering Circular Number 15, Third Edition, Federal Highway Administration, 2007.

Design Standards for Urban Infrastructure - Soft Landscape Design, Department of Territory and Municipal Services - Australian Capital Territory <a href="http://www.tams.act.gov.au/work/standards">http://www.tams.act.gov.au/work/standards</a> and procedures/design standards for urban infrastructure

Erosion and Sediment Control Handbook: A Guide for Protection of State Waters through the use of Best Management Practices during Land Disturbing Activities, Tennessee Department of Environment and Conservation, 2002.


Gravel Mulch, Landscape Architecture Non-Standard Specification 10-2, California Department of Transportation (Caltrans), <a href="http://www.dot.ca.gov/hg/LandArch/roadside/detail-gm.htm">http://www.dot.ca.gov/hg/LandArch/roadside/detail-gm.htm</a>

Maine Erosion and Sediment Control BMPs, DEPLW0588, Maine Department of Environmental Protection: Bureau of Land and Water Quality, 2003.

National Menu of Best Management Practices, US Environmental Protection Agency, 2006.

Standard Specification 72-2: Rock Slope Protection. California Department of Transportation, 2006.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.



#### **Description and Purpose**

A silt fence is made of a woven geotextile that has been entrenched, attached to supporting poles, and sometimes backed by a plastic or wire mesh for support. The silt fence detains sediment-laden water, promoting sedimentation behind the fence.

#### **Suitable Applications**

Silt fences are suitable for perimeter control, placed below areas where sheet flows discharge from the site. They could also be used as interior controls below disturbed areas where runoff may occur in the form of sheet and rill erosion and around inlets within disturbed areas (SE-10). Silt fences are generally ineffective in locations where the flow is concentrated and are only applicable for sheet or overland flows. Silt fences are most effective when used in combination with erosion controls. Suitable applications include:

- Along the perimeter of a project.
- Below the toe or down slope of exposed and erodible slopes.
- Along streams and channels.
- Around temporary spoil areas and stockpiles.
- Around inlets.
- Below other small cleared areas.

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

 $\square$ 

M

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

**☒** Secondary Category

#### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-5 Flber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-10 Storm Drain Inlet Protection

SE-14 Biofilter Bags



#### Limitations

- Do not use in streams, channels, drain inlets, or anywhere flow is concentrated.
- Do not use in locations where ponded water may cause a flooding hazard. Runoff typically ponds temporarily on the upstream side of silt fence.
- Do not use silt fence to divert water flows or place across any contour line. Fences not constructed on a level contour, or fences used to divert flow will concentrate flows resulting in additional erosion and possibly overtopping or failure of the silt fence.
- Improperly installed fences are subject to failure from undercutting, overtopping, or collapsing.
- Not effective unless trenched and keyed in.
- Not intended for use as mid-slope protection on slopes greater than 4:1 (H:V).
- Do not use on slopes subject to creeping, slumping, or landslides.

#### **Implementation**

#### General

A silt fence is a temporary sediment barrier consisting of woven geotextile stretched across and attached to supporting posts, trenched-in, and, depending upon the strength of fabric used, supported with plastic or wire mesh fence. Silt fences trap sediment by intercepting and detaining small amounts of sediment-laden runoff from disturbed areas in order to promote sedimentation behind the fence.

The following layout and installation guidance can improve performance and should be followed:

- Use principally in areas where sheet flow occurs.
- Install along a level contour, so water does not pond more than 1.5 ft at any point along the silt fence.
- The maximum length of slope draining to any point along the silt fence should be 200 ft or less.
- The maximum slope perpendicular to the fence line should be 1:1.
- Provide sufficient room for runoff to pond behind the fence and to allow sediment removal equipment to pass between the silt fence and toes of slopes or other obstructions. About 1200 ft² of ponding area should be provided for every acre draining to the fence.
- Turn the ends of the filter fence uphill to prevent stormwater from flowing around the fence.
- Leave an undisturbed or stabilized area immediately down slope from the fence where feasible.

 Silt fences should remain in place until the disturbed area is permanently stabilized, after which, the silt fence should be removed and properly disposed.

- Silt fence should be used in combination with erosion source controls up slope in order to provide the most effective sediment control.
- Be aware of local regulations regarding the type and installation requirements of silt fence, which may differ from those presented in this fact sheet.

#### Design and Layout

The fence should be supported by a plastic or wire mesh if the fabric selected does not have sufficient strength and bursting strength characteristics for the planned application (as recommended by the fabric manufacturer). Woven geotextile material should contain ultraviolet inhibitors and stabilizers to provide a minimum of six months of expected usable construction life at a temperature range of 0 °F to 120 °F.

- Layout in accordance with attached figures.
- For slopes steeper than 2:1 (H:V) and that contain a high number of rocks or large dirt clods that tend to dislodge, it may be necessary to install additional protection immediately adjacent to the bottom of the slope, prior to installing silt fence. Additional protection may be a chain link fence or a cable fence.
- For slopes adjacent to sensitive receiving waters or Environmentally Sensitive Areas (ESAs), silt fence should be used in conjunction with erosion control BMPs.

#### Standard vs. Heavy Duty Silt Fence

Standard Silt Fence

- Generally applicable in cases where the slope of area draining to the silt fence is 4:1 (H:V) or less.
- Used for shorter durations, typically 5 months or less
- Area draining to fence produces moderate sediment loads.

#### Heavy Duty Silt Fence

- Use is generally limited to 8 months or less.
- Area draining to fence produces moderate sediment loads.
- Heavy duty silt fence usually has 1 or more of the following characteristics, not possessed by standard silt fence.
  - o Fence fabric has higher tensile strength.
  - o Fabric is reinforced with wire backing or additional support.
  - o Posts are spaced closer than pre-manufactured, standard silt fence products.
  - o Posts are metal (steel or aluminum)

#### Materials

#### Standard Silt Fence

■ Silt fence material should be woven geotextile with a minimum width of 36 in. and a minimum tensile strength of 100 lb force. The fabric should conform to the requirements in ASTM designation D4632 and should have an integral reinforcement layer. The

reinforcement layer should be a polypropylene, or equivalent, net provided by the manufacturer. The permittivity of the fabric should be between 0.1 sec<sup>-1</sup> and 0.15 sec<sup>-1</sup> in conformance with the requirements in ASTM designation D4491.

- Wood stakes should be commercial quality lumber of the size and shape shown on the plans. Each stake should be free from decay, splits or cracks longer than the thickness of the stake or other defects that would weaken the stakes and cause the stakes to be structurally unsuitable.
- Staples used to fasten the fence fabric to the stakes should be not less than 1.75 in. long and should be fabricated from 15 gauge or heavier wire. The wire used to fasten the tops of the stakes together when joining two sections of fence should be 9 gauge or heavier wire. Galvanizing of the fastening wire will not be required.

#### **Heavy-Duty Silt Fence**

Some silt fence has a wire backing to provide additional support, and there are products that may use prefabricated plastic holders for the silt fence and use metal posts or bar reinforcement instead of wood stakes. If bar reinforcement is used in lieu of wood stakes, use number four or greater bar. Provide end protection for any exposed bar reinforcement for health and safety purposes.

#### Installation Guidelines - Traditional Method

Silt fences are to be constructed on a level contour. Sufficient area should exist behind the fence for ponding to occur without flooding or overtopping the fence.

- A trench should be excavated approximately 6 in. wide and 6 in. deep along the line of the proposed silt fence (trenches should not be excavated wider or deeper than necessary for proper silt fence installation).
- Bottom of the silt fence should be keyed-in a minimum of 12 in.
- Posts should be spaced a maximum of 6 ft apart and driven securely into the ground a minimum of 18 in. or 12 in. below the bottom of the trench.
- When standard strength geotextile is used, a plastic or wire mesh support fence should be fastened securely to the upslope side of posts using heavy—duty wire staples at least 1 in. long. The mesh should extend into the trench.
- When extra-strength geotextile and closer post spacing are used, the mesh support fence may be eliminated.
- Woven geotextile should be purchased in a long roll, then cut to the length of the barrier. When joints are necessary, geotextile should be spliced together only at a support post, with a minimum 6 in. overlap and both ends securely fastened to the post.
- The trench should be backfilled with native material and compacted.
- Construct silt fences with a setback of at least 3 ft from the toe of a slope. Where, due to specific site conditions, a 3 ft setback is not available, the silt fence may be constructed at the

toe of the slope, but should be constructed as far from the toe of the slope as practicable. Silt fences close to the toe of the slope will be less effective and more difficult to maintain.

- Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the barrier; in no case should the reach exceed 500 ft.
- Cross barriers should be a minimum of  $\frac{1}{3}$  and a maximum of  $\frac{1}{2}$  the height of the linear barrier.
- See typical installation details at the end of this fact sheet.

#### Installation Guidelines - Static Slicing Method

- Static Slicing is defined as insertion of a narrow blade pulled behind a tractor, similar to a plow blade, at least 10 inches into the soil while at the same time pulling silt geotextile fabric into the ground through the opening created by the blade to the depth of the blade. Once the gerotextile is installed, the soil is compacted using tractor tires.
- This method will not work with pre-fabricated, wire backed silt fence.
- Benefits:
  - Ease of installation (most often done with a 2 person crew). In addition, installation using static slicing has been found to be more efficient on slopes, in rocky soils, and in saturated soils.
  - Minimal soil disturbance.
  - o Greater level of compaction along fence, leading to higher performance (i.e. greater sediment retention).
  - o Uniform installation.
  - o Less susceptible to undercutting/undermining.

#### Costs

- It should be noted that costs vary greatly across regions due to available supplies and labor costs.
- Average annual cost for installation using the traditional silt fence installation method
  (assumes 6 month useful life) is \$7 per linear foot based on vendor research. Range of cost
  is \$3.50 \$9.10 per linear foot.
- In tests, the slicing method required 0.33 man hours per 100 linear feet, while the trenched based systems required as much as 1.01 man hours per linear foot.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Repair undercut silt fences.

Repair or replace split, torn, slumping, or weathered fabric. The lifespan of silt fence fabric is generally 5 to 8 months.

- Silt fences that are damaged and become unsuitable for the intended purpose should be removed from the site of work, disposed, and replaced with new silt fence barriers.
- Sediment that accumulates in the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Silt fences should be left in place until the upstream area is permanently stabilized. Until then, the silt fence should be inspected and maintained regularly.
- Remove silt fence when upgradient areas are stabilized. Fill and compact post holes and anchor trench, remove sediment accumulation, grade fence alignment to blend with adjacent ground, and stabilize disturbed area.

#### References

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group-Working Paper, USEPA, April 1992.

Sedimentation and Erosion Control Practices, and Inventory of Current Practices (Draft), UESPA, 1990.

Southeastern Wisconsin Regional Planning Commission (SWRPC). Costs of Urban Nonpoint Source Water Pollution Control Measures. Technical Report No. 31. Southeastern Wisconsin Regional Planning Commission, Waukesha, WI. 1991


Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management Manual for The Puget Sound Basin, Washington State Department of Ecology, Public Review Draft, 1991.

U.S. Environmental Protection Agency (USEPA). Stormwater Management for Industrial Activities: Developing Pollution Prevention Plans and Best Management Practices. U.S. Environmental Protection Agency, Office of Water, Washington, DC, 1992.


Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988. Soil Stabilization BMP Research for Erosion and Sediment Controls: Cost Survey Technical Memorandum, State of California Department of Transportation (Caltrans), July 2007.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.



NOTES

To a of stope




SECTION C-C


7.

ರ

- Johning sections shall not be placed at sump locations. 실
- Scricture rows and layers shall be offset to eliminate gaps. ቪ
- Add 3-4 bags to cross barrier on commandent side of sist fence as needed to prevent bycass or undermining and as allowable bassed on side limits of disturbance. 7

Coss barrier (See note 10)





#### **Description and Purpose**

A sediment basin is a temporary basin formed by excavation or by constructing an embankment so that sediment-laden runoff is temporarily detained under quiescent conditions, allowing sediment to settle out before the runoff is discharged.

Sediment basin design guidance presented in this fact sheet is intended to provide options, methods, and techniques to optimize temporary sediment basin performance and basin sediment removal. Basin design guidance provided in this fact sheet is not intended to guarantee basin effluent compliance with numeric discharge limits (numeric action levels or numeric effluent limits for turbidity). Compliance with discharge limits requires a thoughtful approach to comprehensive BMP planning, implementation, and maintenance. Therefore, optimally designed and maintained sediment basins should be used in conjunction with a comprehensive system of BMPs that includes:

- Diverting runoff from undisturbed areas away from the basin
- Erosion control practices to minimize disturbed areas onsite and to provide temporary stabilization and interim sediment controls (e.g., stockpile perimeter control, check dams, perimeter controls around individual lots) to reduce the basin's influent sediment concentration.

At some sites, sediment basin design enhancements may be required to adequately remove sediment. Traditional

#### Categories EC **Erosion Control** $\square$ SE Sediment Control TC Tracking Control Wind Erosion Control WE Non-Stormwater Management Control Waste Management and WM Materials Pollution Control

#### Legend:

| $\checkmark$ | Primary Category   |
|--------------|--------------------|
| ×            | Secondary Category |

#### **Targeted Constituents**

| Sediment       | Ø |
|----------------|---|
| Nutrients      |   |
| Trash          | V |
| Metals         |   |
| Bacteria       |   |
| Oil and Grease |   |
| Organics       |   |

#### **Potential Alternatives**

SE-3 Sediment Trap (for smaller areas)



(aka "physical") enhancements such as alternative outlet configurations or flow deflection baffles increase detention time and other techniques such as outlet skimmers preferentially drain flows with lower sediment concentrations. These "physical" enhancement techniques are described in this fact sheet. To further enhance sediment removal particularly at sites with fine soils or turbidity sensitive receiving waters, some projects may need to consider implementing Active Treatment Systems (ATS) whereby coagulants and flocculants are used to enhance settling and removal of suspended sediments. Guidance on implementing ATS is provided in SE-11.

#### **Suitable Applications**

Sediment basins may be suitable for use on larger projects with sufficient space for constructing the basin. Sediment basins should be considered for use:

- Where sediment-laden water may enter the drainage system or watercourses
- On construction projects with disturbed areas during the rainy season
- At the outlet of disturbed watersheds between 5 acres and 75 acres and evaluated on a site by site basis
- Where post construction detention basins are required
- In association with dikes, temporary channels, and pipes used to convey runoff from disturbed areas

#### Limitations

Sediment basins must be installed only within the property limits and where failure of the structure will not result in loss of life, damage to homes or buildings, or interruption of use or service of public roads or utilities. In addition, sediment basins are attractive to children and can be very dangerous. Local ordinances regarding health and safety must be adhered to. If fencing of the basin is required, the type of fence and its location should be shown in the SWPPP and in the construction specifications.

- As a general guideline, sediment basins are suitable for drainage areas of 5 acres or more, but not appropriate for drainage areas greater than 75 acres. However, the tributary area should be evaluated on a site by site basis.
- Sediment basins may become an "attractive nuisance" and care must be taken to adhere to all safety practices. If safety is a concern, basin may require protective fencing.
- Sediment basins designed according to this fact sheet are only effective in removing sediment down to about the silt size fraction. Sediment-laden runoff with smaller size fractions (fine silt and clay) may not be adequately treated unless chemical (or other appropriate method) treatment is used in addition to the sediment basin.
- Basins with a height of 25 ft or more or an impounding capacity of 50 ac-ft or more must obtain approval from California Department of Water Resources Division of Safety of Dams (<a href="http://www.water.ca.gov/damsafety/">http://www.water.ca.gov/damsafety/</a>).

- Water that stands in sediment basins longer than 96 hours may become a source of mosquitoes (and midges), particularly along perimeter edges, in shallow zones, in scour or below-grade pools, around inlet pipes, along low-flow channels, and among protected habitats created by emergent or floating vegetation (e.g. cattails, water hyacinth), algal mats, riprap, etc.
- Basins require large surface areas to permit settling of sediment. Size may be limited by the available area.

#### **Implementation**

#### General

A sediment basin is a controlled stormwater release structure formed by excavation or by construction of an embankment of compacted soil across a drainage way, or other suitable location. It is intended to trap sediment before it leaves the construction site. The basin is a temporary measure expected to be used during active construction in most cases and is to be maintained until the site area is permanently protected against erosion or a permanent detention basin is constructed.

Sediment basins are suitable for nearly all types of construction projects. Whenever possible, construct the sediment basins before clearing and grading work begins. Basins should be located at the stormwater outlet from the site but not in any natural or undisturbed stream. A typical application would include temporary dikes, pipes, and/or channels to convey runoff to the basin inlet.

Many development projects in California are required by local ordinances to provide a stormwater detention basin for post-construction flood control, desilting, or stormwater pollution control. A temporary sediment basin may be constructed by rough grading the post-construction control basins early in the project.

Sediment basins if properly designed and maintained can trap a significant amount of the sediment that flows into them. However, traditional basins do not remove all inflowing sediment. Therefore, they should be used in conjunction with erosion control practices such as temporary seeding, mulching, diversion dikes, etc., to reduce the amount of sediment flowing into the basin.

#### **Planning**

To improve the effectiveness of the basin, it should be located to intercept runoff from the largest possible amount of disturbed area. Locations best suited for a sediment basin are generally in lower elevation areas of the site (or basin tributary area) where site drainage would not require significant diversion or other means to direct water to the basin but outside jurisdictional waterways. However, as necessary, drainage into the basin can be improved by the use of earth dikes and drainage swales (see BMP EC-9). The basin should not be located where its failure would result in the loss of life or interruption of the use or service of public utilities or roads.

Construct before clearing and grading work begins when feasible.

• Do not locate the basin in a jurisdictional stream.

- Basin sites should be located where failure of the structure will not cause loss of life, damage to homes or buildings, or interruption of use or service of public roads or utilities.
- Basins with a height of 25 ft or more or an impounding capacity of 50 ac-ft must obtain approval from the Division of Dam Safety. Local dam safety requirements may be more stringent.
- Limit the contributing area to the sediment basin to only the runoff from the disturbed soil areas. Use temporary concentrated flow conveyance controls to divert runoff from undisturbed areas away from the sediment basin.
- The basin should be located: (1) by excavating a suitable area or where a low embankment can be constructed across a swale, (2) where post-construction (permanent) detention basins will be constructed, and (3) where the basins can be maintained on a year-round basis to provide access for maintenance, including sediment removal and sediment stockpiling in a protected area, and to maintain the basin to provide the required capacity.

#### Design

When designing a sediment basin, designers should evaluate the site constraints that could affect the efficiency of the BMP. Some of these constraints include: the relationship between basin capacity, anticipated sediment load, and freeboard, available footprint for the basin, maintenance frequency and access, and hydraulic capacity and efficiency of the temporary outlet infrastructure. Sediment basins should be designed to maximize sediment removal and to consider sediment load retained by the basin as it affects basin performance.

Three Basin Design Options (Part A) are presented below along with a Typical Sediment/Detention Basin Design Methodology (Part B). Regardless of the design option that is selected, designers also need to evaluate the sediment basin capacity with respect to sediment accumulation (See "Step 3. Evaluate the Capacity of the Sediment Basin"), and should incorporate approaches identified in "Step 4. Other Design Considerations" to enhance basin performance.

#### A) Basin Design Options:

#### Option 1:

Design sediment basin(s) using the standard equation:

$$A_{r} = \frac{1.2Q}{V_{r}}$$
 (Eq. 1)

Where:

A<sub>s</sub> = Minimum surface area for trapping soil particles of a certain size

 $V_s$  = Settling velocity of the design particle size chosen ( $V_s$  = 0.00028 ft/s for a design particle size of 0.01 mm at 68°F)

1.2 = Factor of safety recommended by USEPA to account for the reduction in basin efficiency caused due to turbulence and other non ideal conditions.

Q = CIA

(Eq.2)

Where

Q = Discharge rate measured in cubic feet per second

C = Runoff coefficient (unitless)

I = Peak rainfall intensity for the 10-year, 6-hour rain event (in/hr)

A = Area draining into the sediment basin in acres

The design particle size should be the smallest soil grain size determined by wet sieve analysis, or the fine silt sized (0.01 mm [or 0.0004 in.]) particle, and the Vs used should be 100 percent of the calculated settling velocity.

This sizing basin method is dependent on the outlet structure design or the total basin length with an appropriate outlet. If the designer chooses to utilize the outlet structure to control the flow duration in the basin, the basin length (distance between the inlet and the outlet) should be a minimum of twice the basin width; the depth should not be less than 3 ft nor greater than 5 ft for safety reasons and for maximum efficiency (2 ft of sediment storage, 2 ft of capacity). If the designer chooses to utilize the basin length (with appropriate basin outlet) to control the flow duration in the basin, the basin length (distance between the inlet and the outlet) should be a specifically designed to capture 100% of the design particle size; the depth should not be less than 3 ft nor greater than 5 ft for safety reasons and for maximum efficiency (2 ft of sediment storage, 2 ft of capacity).

The basin should be located on the site where it can be maintained on a year-round basis and should be maintained on a schedule to retain the 2 ft of capacity.

#### Option 2:

Design pursuant to local ordinance for sediment basin design and maintenance, provided that the design efficiency is as protective or more protective of water quality than Option 1.

#### Option 3:

The use of an equivalent surface area design or equation provided that the design efficiency is as protective or more protective of water quality than Option 1.

#### B) Typical Sediment/Detention Basin Design Methodology:

Design of a sediment basin requires the designer to have an understanding of the site constraints, knowledge of the local soil (e.g., particle size distribution of potentially contributing soils), drainage area of the basin, and local hydrology. Designers should not assume that a sediment basin for location A is applicable to location B. Therefore, designers can use this factsheet as guidance but will need to apply professional judgment and knowledge of the site to design an effective and efficient sediment basin. The following provides a general overview of typical design methodologies:

14.13

#### Step 1. Hydrologic Design

- Evaluate the site constraints and assess the drainage area for the sediment basin. Designers should consider on- and off-site flows as well as changes in the drainage area associated with site construction/disturbance. To minimize additional construction during the course of the project, the designer should consider identifying the maximum drainage area when calculating the basin dimensions.
- If a local hydrology manual is not available it is recommended to follow standard rational method procedures to estimate discharge. The references section of this factsheet provides a reference to standard hydrology textbooks that can provide standard methodologies. If local rainfall depths are not available, values can be obtained from standard precipitation frequency maps from NOAA (downloaded from <a href="http://www.wrcc.dri.edu/pcpnfreq.html">http://www.wrcc.dri.edu/pcpnfreq.html</a>).

#### Step 2. Hydraulic Design

Calculate the surface area required for the sediment basin using Equation 1. In which
discharge is estimated for a 10-yr 6-hr event using rational method procedure listed in local
hydrology manual and Vs is estimated using Stokes Law presented in Equation 3.

$$V_s = 2.81d^2$$
 (Eq.3)

Where

 $V_s$  = Settling velocity in feet per second at 68°F

d = diameter of sediment particle in millimeters (smallest soil grain size determined by wet sieve analysis or fine silt (0.01 mm [or 0.0004 in.])

- In general the basin outlet design requires an iterative trial and error approach that considered the maximum water surface elevation, the elevation versus volume (stage-storage) relationship, the elevation verses discharge (stage-discharge) relationship, and the estimated inflow hydrograph. To adequately design the basins to settle sediment, the outlet configuration and associated outflow rates can be estimated by numerous methodologies. The following provides some guidance for design the basin outlet:
  - An outlet should have more than one orifice.
  - An outlet design typically utilizes multiple horizontal rows of orifices (approximately 3 or more) with at least 2 orifices per row (see Figures 1 and 2 at the end of this fact sheet).
  - Orifices can vary in shape.
  - Select the appropriate orifice diameter and number of perforations per row with the objective of minimizing the number of rows while maximizing the detention time.

- The diameter of each orifice is typically a maximum of 3-4 inches and a minimum of 0.25-0.5 inches.
- If a rectangular orifice is used, it is recommended to have minimum height of 0.5 inches and a maximum height of 6 inches.
- Rows are typically spaced at three times the diameter center to center vertically with a minimum distance of approximately 4 inches on center and a maximum distance of 1 foot on center.
- To estimate the outflow rate, each row is calculated separately based on the flow through a single orifice then multiplied by the number of orifices in the row. This step is repeated for each of the rows. Once all of the orifices are estimated, the total outflow rate versus elevation (stage-discharge curve) is developed to evaluate the detention time within the basin.
- Flow through a single orifice can be estimated using an Equation 4:

$$Q = BC' A(2gH)^{0.5}$$
 (Eq.4)

Where

 $Q = Discharge in ft^3/s$ 

C' = Orifice coefficient (unitless)

 $A = Area of the orifice (ft^2)$ 

 $g = acceleration due to gravity (ft^3/s)$ 

H = Head above the orifice (ft)

B = Anticipated Blockage or clogging factor (unitless), It is dependent on anticipated sediment and debris load, trash rack configuration etc, so the value is dependent on design engineers professional judgment and/or local requirements (B is never greater than 1 and a value of 0.5 is generally used)

- Care must be taken in the selection of orifice coefficient ("C'"); 0.60 is most often recommended and used. However, based on actual tests, Young and Graziano (1989), "Outlet Hydraulics of Extended Detention Facilities for Northern Virginia Planning District Commission", recommends the following:
  - C' = 0.66 for thin materials; where the thickness is equal to or less than the orifice diameter, or
  - C' = 0.80 when the material is thicker than the orifice diameter
- If different sizes of orifices are used along the riser then they have to be sized such that not more than 50 percent of the design storm event drains in one-third of the drawdown time (to provide adequate settling time for events smaller than the design storm event) and the entire volume drains within 96 hours or as regulated by the local vector control agency. If a basin fails to drain within 96 hours, the basin must be pumped dry.

- Because basins are not maintained for infiltration, water loss by infiltration should be disregarded when designing the hydraulic capacity of the outlet structure.
- Floating Outlet Skimmer: The floating skimmer (see Figure 3 at the end of this fact sheet is an alternative outlet configuration (patented) that drains water from upper portion of the water column. This configuration has been used for temporary and permanent basins and can improve basin performance by eliminating bottom orifices which have the potential of discharging solids. Some design considerations for this alternative outlet device includes the addition of a sand filter or perforated under drain at the low point in the basin and near the floating skimmer. These secondary drains allow the basin to fully drain. More detailed guidelines for sizing the skimmer can be downloaded from <a href="http://www.fairclothskimmer.com/">http://www.fairclothskimmer.com/</a>.
- Hold and Release Valve: An ideal sediment/detention basin would hold all flows to the design storm level for sufficient time to settle solids, and then slowly release the storm water. Implementing a reliable valve system for releasing detention basins is critical to eliminate the potential for flooding in such a system. Some variations of hold and release valves include manual valves, bladder devices or electrically operated valves. When a precipitation event is forecast, the valve would be close for the duration of the storm and appropriate settling time. When the settling duration is met (approximately 24 or 48 hours), the valve would be opened and allow the stormwater to be discharged at a rate that does not resuspend settled solids and in a non-erosive manner. If this type of system is used the valve should be designed to empty the entire basin within 96 hours or as stipulated by local vector control regulations.

Step 3. Evaluate the Capacity of the Sediment Basin

- Typically, sediment basins do not perform as designed when they are not properly maintained or the sediment yield to the basin is larger than expected. As part of a good sediment basin design, designers should consider maintenance cycles, estimated soil loss and/or sediment yield, and basin sediment storage volume. The two equations below can be used to quantify the amount of soil entering the basin.
- The Revised Universal Soil Loss Equation (RUSLE, Eq.5) can be used to estimate annual soil loss and the Modified Universal Soil Equation (MUSLE, Eq.6) can be used to estimate sediment yield from a single storm event.

$$A = R \times K \times LS \times C \times P$$
 (Eq.5)  

$$Y = 95(Q \times q_p)^{0.56} \times K \times LS \times C \times P$$
 (Eq.6)

Where:

A = annual soil loss, tons/acre-year

R = rainfall erosion index, in 100 ft.tons/acre.in/hr

K = soil erodibility factor, tons/acre per unit of R

LS = slope length and steepness factor (unitless)

- C = vegetative cover factor (unitless)
- P = erosion control practice factor (unitless)
- Y = single storm sediment yield in tons
- Q = runoff volume in acre-feet
- $q_p$  = peak flow in cfs
- Detailed descriptions and methodologies for estimating the soil loss can be obtained from standard hydrology text books (See References section).
- Determination of the appropriate equation should consider construction duration and local environmental factors (soils, hydrology, etc.). For example, if a basin is planned for a project duration of 1 year and the designer specifies one maintenance cycle, RUSLE could be used to estimate the soil loss and thereby the designer could indicate that the sediment storage volume would be half of the soil loss value estimated. As an example for use of MUSLE, a project may have a short construction duration thereby requiring fewer maintenance cycles and a reduced sediment storage volume. MUSLE would be used to estimate the anticipated soil loss based on a specific storm event to evaluate the sediment storage volume and appropriate maintenance frequency.
- The soil loss estimates are an essential step in the design and it is essential that the designer provide construction contractors with enough information to understand maintenance frequency and/or depths within the basin that would trigger maintenance. Providing maintenance methods, frequency and specification should be included in design bid documents such as the SWPPP Site Map.
- Once the designer has quantified the amount of soil entering the basin, the depth required for sediment storage can be determined by dividing the estimated sediment loss by the surface area of the basin.

#### Step 4. Other Design Considerations

- Consider designing the volume of the settling zone for the total storm volume associated with the 2-year event or other appropriate design storms specified by the local agency. This volume can be used as a guide for sizing the basin without iterative routing calculations. The depth of the settling zone can be estimated by dividing the estimated 2-yr storm volume by the surface area of the basin.
- The basin volume consists of two zones:
  - A sediment storage zone at least 1 ft deep.
  - A settling zone at least 2 ft deep.
  - The basin depth must be no less than 3 ft (not including freeboard).
- Proper hydraulic design of the outlet is critical to achieving the desired performance of the basin. The outlet should be designed to drain the basin within 24 to 96 hours (also referred

to as "drawdown time"). The 24-hour limit is specified to provide adequate settling time; the 96-hour limit is specified to mitigate vector control concerns.

- Confirmation of the basin performance can be evaluated by routing the design storm (10-yr 6-hr, or as directed by local regulations) through the basin based on the basin volume (stage-storage curve) and the outlet design (stage-discharge curve based on the orifice configuration or equivalent outlet design).
- Sediment basins, regardless of size and storage volume, should include features to accommodate overflow or bypass flows that exceed the design storm event.
  - Include an emergency spillway to accommodate flows not carried by the principal spillway. The spillway should consist of an open channel (earthen or vegetated) over undisturbed material (not fill) or constructed of a non-erodible riprap (or equivalent protection) on fill slopes.
  - The spillway control section, which is a level portion of the spillway channel at the highest elevation in the channel, should be a minimum of 20 ft in length.
- Rock, vegetation or appropriate erosion control should be used to protect the basin inlet, outlet, and slopes against erosion.
- The total depth of the sediment basin should include the depth required for sediment storage, depth required for settling zone and freeboard of at least 1 foot or as regulated by local flood control agency for a flood event specified by the local agency.
- The basin alignment should be designed such that the length of the basin is more than twice the width of the basin; the length should be determined by measuring the distance between the inlet and the outlet. If the site topography does not allow for this configuration baffles should be installed so that the ratio is satisfied. If a basin has more than one inflow point, any inflow point that conveys more than 30 percent of the total peak inflow rate has to meet the required length to width ratio.
- An alternative basin sizing method proposed by Fifield (2004) can be consulted to estimate an alternative length to width ratio and basin configuration. These methods can be considered as part of Option 3 which allows for alternative designs that are protective or more protective of water quality.
- Baffles (see Figure 4 at the end of this fact sheet) can be considered at project sites where the existing topography or site constraints limit the length to width ratio. Baffles should be constructed of earthen berms or other structural material within the basin to divert flow in the basin, thus increasing the effective flow length from the basin inlet to the outlet riser. Baffles also reduce the change of short circuiting and allows for settling throughout the basin.
- Baffles are typically constructed from the invert of the basin to the crest of the emergency spillway (i.e., design event flows are meant to flow around the baffles and flows greater than the design event would flow over the baffles to the emergency spillway).

- Use of other materials for construction of basin baffles (such as silt fence) may not be appropriate based on the material specifications and will require frequent maintenance (maintain after every storm event). Maintenance may not be feasible when required due to flooded conditions resulting from frequent (i.e., back to back) storm events. Use of alternative baffle materials should not deviate from the intended purpose of the material, as described by the manufacturer.
- Sediment basins are best used in conjunction with erosion controls.
- Basins with an impounding levee greater than 4.5 ft tall, measured from the lowest point to the impounding area to the highest point of the levee, and basins capable of impounding more than 35,000 ft³, should be designed by a Registered Civil Engineer. The design should include maintenance requirements, including sediment and vegetation removal, to ensure continuous function of the basin outlet and bypass structures.
- A forebay, constructed upstream of the basin may be provided to remove debris and larger particles.
- The outflow from the sediment basin should be provided with velocity dissipation devices (see BMP EC-10) to prevent erosion and scouring of the embankment and channel.
- The principal outlet should consist of a corrugated metal, high density polyethylene (HDPE), or reinforced concrete riser pipe with dewatering holes and an anti-vortex device and trash rack attached to the top of the riser, to prevent floating debris from flowing out of the basin or obstructing the system. This principal structure should be designed to accommodate the inflow design storm.
- A rock pile or rock-filled gabions can serve as alternatives to the debris screen, although the designer should be aware of the potential for extra maintenance involved should the pore spaces in the rock pile clog.
- The outlet structure should be placed on a firm, smooth foundation with the base securely anchored with concrete or other means to prevent floatation.
- Attach riser pipe (watertight connection) to a horizontal pipe (barrel). Provide anti-seep collars on the barrel.
- Cleanout level should be clearly marked on the riser pipe.

#### Installation

- Securely anchor and install an anti-seep collar on the outlet pipe/riser and provide an emergency spillway for passing major floods (see local flood control agency).
- Areas under embankments must be cleared and stripped of vegetation.
- Chain link fencing should be provided around each sediment basin to prevent unauthorized entry to the basin or if safety is a concern.

#### Costs

The cost of a sediment basin is highly variable and is dependent of the site configuration. To decrease basin construction costs, designers should consider using existing site features such as berms or depressed area to site the sediment basin. Designers should also consider potential savings associated with designing the basin to minimize the number of maintenance cycles and siting the basin in a location where a permanent BMP (e.g., extended detention basin) is required for the project site.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level and as required by local requirements. It is recommended that at a minimum, basins be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Examine basin banks for seepage and structural soundness.
- Check inlet and outlet structures and spillway for any damage or obstructions. Repair damage and remove obstructions as needed.
- Check inlet and outlet area for erosion and stabilize if required.
- Check fencing for damage and repair as needed.
- Sediment that accumulates in the basin must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when sediment accumulation reaches one-half the designated sediment storage volume. Sediment removed during maintenance should be managed properly. The sediment should be appropriately evaluated and used or disposed of accordingly. Options include: incorporating sediment into earthwork on the site (only if there is no risk that sediment is contaminated); or off-site export/disposal at an appropriate location (e.g., sediment characterization and disposal to an appropriate landfill).
- Remove standing water from basin within 96 hours after accumulation.
- If the basin does not drain adequately (e.g., due to storms that are more frequent or larger than the design storm or other unforeseen site conditions), dewatering should be conducted in accordance with appropriate dewatering BMPs (see NS-2) and in accordance with local permits as applicable.
- To minimize vector production:
  - Remove accumulation of live and dead floating vegetation in basins during every inspection.
  - Remove excessive emergent and perimeter vegetation as needed or as advised by local or state vector control agencies.

#### References

A Current Assessment of Urban Best Management Practices: Techniques for Reducing Nonpoint Source Pollution in the Coastal Zones, Metropolitan Washington Council of Governments, March 1992.

Draft-Sedimentation and Erosion Control, an Inventory of Current Practices, USEPA. April 1990.

U.S. Environmental Protection Agency (USEPA). Erosion and Sediment Control, Surface Mining in the Eastern U.S., U.S. Environmental Protection Agency, Office of Water, Washington, DC, Washington, D.C., 1976.

Fifield, J.S. Designing for Effective Sediment and Erosion Control on Construction Sites. Forester Press, Santa Barbara, CA. 2004.

Goldman S.J., Jackson K. and Bursztynsky T.A. Erosion and Sediment Control Handbook. McGraw-Hill Book Company, 1986.

U.S. Environmental Protection Agency (USEPA). Guidance Specifying Management Measures for Nonpoint Pollution in Coastal Waters. EPA 840-B-9-002. U.S. Environmental Protection Agency, Office of Water, Washington, DC, 1993.

Guidelines for the Design and Construction of Small Embankment Dams, Division of Safety of Dams, California Department of Water Resources, March 1986.

Haan C.T., Barfield B.J. and Hayes J.C. Design Hydrology and Sedimentology for Small Catchments. Academic Press. 1994.

Inlet/Outlet Alternatives for Extended Detention Basins. State of California Department of Transportation (Caltrans), 2001.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

McLean, J., 2000. Mosquitoes in Constructed Wetlands: A Management Bugaboo? In T.R. Schueler and H.K. Holland [eds.], The Practice of Watershed Protection. pp. 29-33. Center for Watershed Protection, Ellicott City, MD, 2000.

Metzger, M.E., D. F. Messer, C. L. Beitia, C. M. Myers, and V. L. Kramer. The Dark Side of Stormwater Runoff Management: Disease Vectors Associated with Structural BMPs, 2002.

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, United States Environmental Protection Agency, 2002.

Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Water, Work Group-Working Paper, USEPA, April 1992.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Water Quality Management Plan for the Lake Tahoe Region, Volume II Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.

Young, G.K. and Graziano, F., Outlet Hydraulics of Extended Detention Facilities for Northern Virginia Planning District Commission, 1989.




FIGURE 1: TYPICAL TEMPORARY SEDIMENT BASIN
MULTIPLE ORIFICE DESIGN
NOT TO SCALE




FIGURE 2: MULTIPLE ORIFICE OUTLET RISER
NOT TO SCALE






FIGURE 3: TYPICAL SKIMMER
NOT TO SCALE



### FIGURE 4: TYPICAL TEMPORARY SEDIMENT BASIN WITH BAFFLES NOT TO SCALE



#### **Description and Purpose**

A check dam is a small barrier constructed of rock, gravel bags, sandbags, fiber rolls, or other proprietary products, placed across a constructed swale or drainage ditch. Check dams reduce the effective slope of the channel, thereby reducing scour and channel erosion by reducing flow velocity and increasing residence time within the channel, allowing sediment to settle.

#### **Suitable Applications**

Check dams may be appropriate in the following situations:

- To promote sedimentation behind the dam.
- To prevent erosion by reducing the velocity of channel flow in small intermittent channels and temporary swales.
- In small open channels that drain 10 acres or less.
- In steep channels where stormwater runoff velocities exceed 5 ft/s.
- During the establishment of grass linings in drainage ditches or channels.
- In temporary ditches where the short length of service does not warrant establishment of erosion-resistant linings.
- To act as a grade control structure.

## EC Erosion Control SE Sediment Control TC Tracking Control WE Wind Erosion Control NS Non-Stormwater Management Control

Waste Management and

Materials Pollution Control
Legend:

☑ Primary Category

☑ Secondary Category

#### **Targeted Constituents**

Sediment

V

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-14 Biofilter Bags



Check Dams SE-4

. 046

#### Limitations

- Not to be used in live streams or in channels with extended base flows.
- Not appropriate in channels that drain areas greater than 10 acres.
- Not appropriate in channels that are already grass-lined unless erosion potential or sediment-laden flow is expected, as installation may damage vegetation.
- Require extensive maintenance following high velocity flows.
- Promotes sediment trapping which can be re-suspended during subsequent storms or removal of the check dam.
- Do not construct check dams with straw bales or silt fence.
- Water suitable for mosquito production may stand behind check dams, particularly if subjected to daily non-stormwater discharges.

#### **Implementation**

#### General

Check dams reduce the effective slope and create small pools in swales and ditches that drain 10 acres or less. Using check dams to reduce channel slope reduces the velocity of stormwater flows, thus reducing erosion of the swale or ditch and promoting sedimentation. Thus, check dams are dual-purpose and serve an important role as erosion controls as well as as sediment controls. Note that use of 1-2 isolated check dams for sedimentation will likely result in little net removal of sediment because of the small detention time and probable scour during longer storms. Using a series of check dams will generally increase their effectiveness. A sediment trap (SE-3) may be placed immediately upstream of the check dam to increase sediment removal efficiency.

#### Design and Layout

Check dams work by decreasing the effective slope in ditches and swales. An important consequence of the reduced slope is a reduction in capacity of the ditch or swale. This reduction in capacity should be considered when using this BMP, as reduced capacity can result in overtopping of the ditch or swale and resultant consequences. In some cases, such as a "permanent" ditch or swale being constructed early and used as a "temporary" conveyance for construction flows, the ditch or swale may have sufficient capacity such that the temporary reduction in capacity due to check dams is acceptable. When check dams reduce capacities beyond acceptable limits, either:

- Don't use check dams. Consider alternative BMPs, or.
- Increase the size of the ditch or swale to restore capacity.

Maximum slope and velocity reduction is achieved when the toe of the upstream dam is at the same elevation as the top of the downstream dam (see "Spacing Between Check Dams" detail at the end of this fact sheet). The center section of the dam should be lower than the edge sections (at least 6 inches), acting as a spillway, so that the check dam will direct flows to the center of

Check Dams SE-4

the ditch or swale (see "Typical Rock Check Dam" detail at the end of this fact sheet). Bypass or side-cutting can occur if a sufficient spillway is not provided in the center of the dam.

Check dams are usually constructed of rock, gravel bags, sandbags, and fiber rolls. A number of products can also be used as check dams (e.g. HDPE check dams, temporary silt dikes (SE-12)), and some of these products can be removed and reused. Check dams can also be constructed of logs or lumber, and have the advantage of a longer lifespan when compared to gravel bags, sandbags, and fiber rolls. Check dams should not be constructed from straw bales or silt fences, since concentrated flows quickly wash out these materials.

Rock check dams are usually constructed of 8 to 12 in. rock. The rock is placed either by hand or mechanically, but never just dumped into the channel. The dam should completely span the ditch or swale to prevent washout. The rock used should be large enough to stay in place given the expected design flow through the channel. It is recommended that abutments be extended 18 in. into the channel bank. Rock can be graded such that smaller diameter rock (e.g. 2-4 in) is located on the upstream side of larger rock (holding the smaller rock in place); increasing residence time.

Log check dams are usually constructed of 4 to 6 in. diameter logs, installed vertically. The logs should be embedded into the soil at least 18 in. Logs can be bolted or wired to vertical support logs that have been driven or buried into the soil.

See fiber rolls, SE-5, for installation of fiber roll check dams.

Gravel bag and sand bag check dams are constructed by stacking bags across the ditch or swale, shaped as shown in the drawings at the end of this fact sheet (see "Gravel Bag Check Dam" detail at the end of this fact sheet).

Manufactured products, such as temporary silt dikes (SE-12), should be installed in accordance with the manufacturer's instructions. Installation typically requires anchoring or trenching of products, as well as regular maintenance to remove accumulated sediment and debris.

If grass is planted to stabilize the ditch or swale, the check dam should be removed when the grass has matured (unless the slope of the swales is greater than 4%).

The following guidance should be followed for the design and layout of check dams:

- Install the first check dam approximately 16 ft from the outfall device and at regular intervals based on slope gradient and soil type.
- Check dams should be placed at a distance and height to allow small pools to form between each check dam.
- For multiple check dam installation, backwater from a downstream check dam should reach the toes of the upstream check dam.
- A sediment trap provided immediately upstream of the check dam will help capture sediment. Due to the potential for this sediment to be resuspended in subsequent storms, the sediment trap should be cleaned following each storm event.

Check Dams SE-4

 High flows (typically a 2-year storm or larger) should safely flow over the check dam without an increase in upstream flooding or damage to the check dam.

■ Where grass is used to line ditches, check dams should be removed when grass has matured sufficiently to protect the ditch or swale.

#### Materials

- Rock used for check dams should typically be 8-12 in rock and be sufficiently sized to stay in place given expected design flows in the channel. Smaller diameter rock (e.g. 2 to 4 in) can be placed on the upstream side of larger rock to increase residence time.
- Gravel bags used for check dams should conform to the requirements of SE-6, Gravel Bag Berms.
- Sandbags used for check dams should conform to SE-8, Sandbag Barrier.
- Fiber rolls used for check dams should conform to SE-5, Fiber Rolls.
- Temporary silt dikes used for check dams should conform to SE-12, Temporary Silt Dikes.

#### Installation

- Rock should be placed individually by hand or by mechanical methods (no dumping of rock) to achieve complete ditch or swale coverage.
- Tightly abut bags and stack according to detail shown in the figure at the end of this section (pyramid approach). Gravel bags and sandbags should not be stacked any higher than 3 ft.
- Upper rows or gravel and sand bags shall overlap joints in lower rows.
- Fiber rolls should be trenched in, backfilled, and firmly staked in place.
- Install along a level contour.
- HDPE check dams, temporary silt dikes, and other manufactured products should be used and installed per manufacturer specifications.

#### Costs

Cost consists of labor costs if materials are readily available (such as gravel on-site). If material must be imported, costs will increase. For other material and installation costs, see SE-5, SE-6, SE-8, SE-12, and SE-14.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Replace missing rock, bags, rolls, etc. Replace bags or rolls that have degraded or have become damaged.

Check Dams SE-4

■ If the check dam is used as a sediment capture device, sediment that accumulates behind the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.

- If the check dam is used as a grade control structure, sediment removal is not required as long as the system continues to control the grade.
- Inspect areas behind check dams for pools of standing water, especially if subjected to daily non-stormwater discharges.
- Remove accumulated sediment prior to permanent seeding or soil stabilization.
- Remove check dam and accumulated sediment when check dams are no longer needed.

#### References

Draft - Sedimentation and Erosion Control, and Inventory of Current Practices, USEPA, April 1990.


Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.


Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

Metzger, M.E. 2004. Managing mosquitoes in stormwater treatment devices. University of California Division of Agriculture and Natural Resources, Publication 8125. On-line: http://anrcatalog.ucdavis.edu/pdf/8125.pdf




ELEVATION





TYPICAL ROCK CHECK DAM SECTION

ROCK CHECK DAM
NOT TO SCALE



GRAVEL BAG CHECK DAM ELEVATION NOT TO SCALE





## Categories

| EC | Erc | sion | C | ontro | lc |  |
|----|-----|------|---|-------|----|--|
|    |     |      |   | _     |    |  |

E Sediment Control

X

 $\square$ 

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

| $\checkmark$ | Primary | Category |
|--------------|---------|----------|
| _            |         |          |

Secondary Category

## **Description and Purpose**

A fiber roll consists of straw, coir, or other biodegradable materials bound into a tight tubular roll wrapped by netting, which can be photodegradable or natural. Additionally, gravel core fiber rolls are available, which contain an imbedded ballast material such as gravel or sand for additional weight when staking the rolls are not feasible (such as use as inlet protection). When fiber rolls are placed at the toe and on the face of slopes along the contours, they intercept runoff, reduce its flow velocity, release the runoff as sheet flow, and provide removal of sediment from the runoff (through sedimentation). By interrupting the length of a slope, fiber rolls can also reduce sheet and rill erosion until vegetation is established.

#### **Suitable Applications**

Fiber rolls may be suitable:

- Along the toe, top, face, and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow.
- At the end of a downward slope where it transitions to a steeper slope.
- Along the perimeter of a project.
- As check dams in unlined ditches with minimal grade.
- Down-slope of exposed soil areas.
- At operational storm drains as a form of inlet protection.

## **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

## **Potential Alternatives**

SE-1 Silt Fence

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-14 Biofilter Bags



Around temporary stockpiles.

#### Limitations

- Fiber rolls are not effective unless trenched in and staked.
- Not intended for use in high flow situations.
- Difficult to move once saturated.
- If not properly staked and trenched in, fiber rolls could be transported by high flows.
- Fiber rolls have a very limited sediment capture zone.
- Fiber rolls should not be used on slopes subject to creep, slumping, or landslide.
- Rolls typically function for 12-24 months depending upon local conditions.

## **Implementation**

#### Fiber Roll Materials

- Fiber rolls should be prefabricated.
- Fiber rolls may come manufactured containing polyacrylamide (PAM), a flocculating agent within the roll. Fiber rolls impregnated with PAM provide additional sediment removal capabilities and should be used in areas with fine, clayey or silty soils to provide additional sediment removal capabilities. Monitoring may be required for these installations.
- Fiber rolls are made from weed free rice straw, flax, or a similar agricultural material bound into a tight tubular roll by netting.
- Typical fiber rolls vary in diameter from 9 in. to 20 in. Larger diameter rolls are available as well.

#### Installation

- Locate fiber rolls on level contours spaced as follows:
  - Slope inclination of 4:1 (H:V) or flatter: Fiber rolls should be placed at a maximum interval of 20 ft.
  - Slope inclination between 4:1 and 2:1 (H:V): Fiber Rolls should be placed at a maximum interval of 15 ft. (a closer spacing is more effective).
  - Slope inclination 2:1 (H:V) or greater: Fiber Rolls should be placed at a maximum interval of 10 ft. (a closer spacing is more effective).
- Prepare the slope before beginning installation.
- Dig small trenches across the slope on the contour. The trench depth should be ¼ to 1/3 of the thickness of the roll, and the width should equal the roll diameter, in order to provide area to backfill the trench.

■ It is critical that rolls are installed perpendicular to water movement, and parallel to the slope contour.

- Start building trenches and installing rolls from the bottom of the slope and work up.
- It is recommended that pilot holes be driven through the fiber roll. Use a straight bar to drive holes through the roll and into the soil for the wooden stakes.
- Turn the ends of the fiber roll up slope to prevent runoff from going around the roll.
- Stake fiber rolls into the trench.
  - Drive stakes at the end of each fiber roll and spaced 4 ft maximum on center.
  - Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum length of 24 in.
- If more than one fiber roll is placed in a row, the rolls should be overlapped, not abutted.
- See typical fiber roll installation details at the end of this fact sheet.

#### Removal

- Fiber rolls can be left in place or removed depending on the type of fiber roll and application (temporary vs. permanent installation). Typically, fiber rolls encased with plastic netting are used for a temporary application because the netting does not biodegrade. Fiber rolls used in a permanent application are typically encased with a biodegradeable material and are left in place. Removal of a fiber roll used in a permanent application can result in greater disturbance.
- Temporary installations should only be removed when up gradient areas are stabilized per General Permit requirements, and/or pollutant sources no longer present a hazard. But, they should also be removed before vegetation becomes too mature so that the removal process does not disturb more soil and vegetation than is necessary.

#### Costs

Material costs for regular fiber rolls range from \$20 - \$30 per 25 ft roll.

Material costs for PAM impregnated fiber rolls range between 7.00-\$9.00 per linear foot, based upon vendor research.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Repair or replace split, torn, unraveling, or slumping fiber rolls.
- If the fiber roll is used as a sediment capture device, or as an erosion control device to maintain sheet flows, sediment that accumulates in the BMP should be periodically removed


in order to maintain BMP effectiveness. Sediment should be removed when sediment accumulation reaches one-third the designated sediment storage depth.

- If fiber rolls are used for erosion control, such as in a check dam, sediment removal should not be required as long as the system continues to control the grade. Sediment control BMPs will likely be required in conjunction with this type of application.
- Repair any rills or gullies promptly.


#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.


Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.



TYPICAL FIBER ROLL INSTALLATION
N.T.S.



ENTRENCHMENT DETAIL N.T.S.



## **Description and Purpose**

A gravel bag berm is a series of gravel-filled bags placed on a level contour to intercept sheet flows. Gravel bags pond sheet flow runoff, allowing sediment to settle out, and release runoff slowly as sheet flow, preventing erosion.

## **Suitable Applications**

Gravel bag berms may be suitable:

- As a linear sediment control measure:
  - Below the toe of slopes and erodible slopes
  - As sediment traps at culvert/pipe outlets:
  - Below other small cleared areas
  - Along the perimeter of a site
  - Down slope of exposed soil areas
  - Around temporary stockpiles and spoil areas
  - Parallel to a roadway to keep sediment off paved areas
  - Along streams and channels
- As a linear erosion control measure:
  - Along the face and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow.

## Categories

EC **Erosion Control**  X  $\checkmark$ 

SE Sediment Control

TC **Tracking Control** 

WE Wind Erosion Control

Non-Stormwater Management Control

Waste Management and WM

Materials Pollution Control

#### Legend:

NS

☑ Primary Category

Secondary Category

## **Targeted Constituents**

Sediment

 $\mathbf{V}$ 

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Roll

SE-8 Sandbag Barrier

SE-14 Biofilter Bags



- At the top of slopes to divert runoff away from disturbed slopes.
- As chevrons (small check dams) across mildly sloped construction roads. For use check dam use in channels, see SE-4, Check Dams.

#### Limitations

- Gravel berms may be difficult to remove.
- Removal problems limit their usefulness in landscaped areas.
- Gravel bag berm may not be appropriate for drainage areas greater than 5 acres.
- Runoff will pond upstream of the berm, possibly causing flooding if sufficient space does not exist.
- Degraded gravel bags may rupture when removed, spilling contents.
- Installation can be labor intensive.
- Durability of gravel bags is somewhat limited and bags may need to be replaced when installation is required for longer than 6 months.
- Easily damaged by construction equipment.
- When used to detain concentrated flows, maintenance requirements increase.

#### **Implementation**

#### General

A gravel bag berm consists of a row of open graded gravel-filled bags placed on a level contour. When appropriately placed, a gravel bag berm intercepts and slows sheet flow runoff, causing temporary ponding. The temporary ponding allows sediment to settle. The open graded gravel in the bags is porous, which allows the ponded runoff to flow slowly through the bags, releasing the runoff as sheet flows. Gravel bag berms also interrupt the slope length and thereby reduce erosion by reducing the tendency of sheet flows to concentrate into rivulets, which erode rills, and ultimately gullies, into disturbed, sloped soils. Gravel bag berms are similar to sand bag barriers, but are more porous. Generally, gravel bag berms should be used in conjunction with temporary soil stabilization controls up slope to provide effective erosion and sediment control.

#### Design and Layout

- Locate gravel bag berms on level contours.
- When used for slope interruption, the following slope/sheet flow length combinations apply:
  - Slope inclination of 4:1 (H:V) or flatter: Gravel bags should be placed at a maximum interval of 20 ft, with the first row near the slope toe.
  - Slope inclination between 4:1 and 2:1 (H:V): Gravel bags should be placed at a maximum interval of 15 ft. (a closer spacing is more effective), with the first row near the slope toe.

Slope inclination 2:1 (H:V) or greater: Gravel bags should be placed at a maximum interval of 10 ft. (a closer spacing is more effective), with the first row near the slope toe.

- Turn the ends of the gravel bag barriers up slope to prevent runoff from going around the berm.
- Allow sufficient space up slope from the gravel bag berm to allow ponding, and to provide room for sediment storage.
- For installation near the toe of the slope, gravel bag barriers should be set back from the slope toe to facilitate cleaning. Where specific site conditions do not allow for a set-back, the gravel bag barrier may be constructed on the toe of the slope. To prevent flows behind the barrier, bags can be placed perpendicular to a berm to serve as cross barriers.
- Drainage area should not exceed 5 acres.
- In Non-Traffic Areas:
  - Height = 18 in. maximum
  - Top width = 24 in. minimum for three or more layer construction
  - Top width = 12 in. minimum for one or two layer construction
  - Side slopes = 2:1 (H:V) or flatter
- In Construction Traffic Areas:
  - Height = 12 in. maximum
  - Top width = 24 in. minimum for three or more layer construction.
  - Top width = 12 in. minimum for one or two layer construction.
  - Side slopes = 2:1 (H:V) or flatter.
- Butt ends of bags tightly.
- On multiple row, or multiple layer construction, overlap butt joints of adjacent row and row beneath.
- Use a pyramid approach when stacking bags.

#### Materials

■ **Bag Material:** Bags should be woven polypropylene, polyethylene or polyamide fabric or burlap, minimum unit weight of 4 ounces/yd², Mullen burst strength exceeding 300 lb/in² in conformance with the requirements in ASTM designation D3786, and ultraviolet stability exceeding 70% in conformance with the requirements in ASTM designation D4355.

- Bag Size: Each gravel-filled bag should have a length of 18 in., width of 12 in., thickness of 3 in., and mass of approximately 33 lbs. Bag dimensions are nominal, and may vary based on locally available materials.
- Fill Material: Fill material should be 0.5 to 1 in. crushed rock, clean and free from clay, organic matter, and other deleterious material, or other suitable open graded, non-cohesive, porous gravel.

#### Costs

Material costs for gravel bags are average and are dependent upon material availability. \$2.50-3.00 per filled gravel bag is standard based upon vendor research.

## **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Gravel bags exposed to sunlight will need to be replaced every two to three months due to degrading of the bags.
- Reshape or replace gravel bags as needed.
- Repair washouts or other damage as needed.
- Sediment that accumulates in the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Remove gravel bag berms when no longer needed and recycle gravel fill whenever possible
  and properly dispose of bag material. Remove sediment accumulation and clean, re-grade,
  and stabilize the area.


#### References

Handbook of Steel Drainage and Highway Construction, American Iron and Steel Institute, 1983.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Pollution Plan Handbook, First Edition, State of California, Department of Transportation Division of New Technology, Materials and Research, October 1992.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.



| <b>J</b> |  |  |  |
|----------|--|--|--|
|          |  |  |  |

## **Description and Purpose**

Street sweeping and vacuuming includes use of self-propelled and walk-behind equipment to remove sediment from streets and roadways, and to clean paved surfaces in preparation for final paving. Sweeping and vacuuming prevents sediment from the project site from entering storm drains or receiving waters.

## **Suitable Applications**

Sweeping and vacuuming are suitable anywhere sediment is tracked from the project site onto public or private paved streets and roads, typically at points of egress. Sweeping and vacuuming are also applicable during preparation of paved surfaces for final paying.

## Limitations

Sweeping and vacuuming may not be effective when sediment is wet or when tracked soil is caked (caked soil may need to be scraped loose).

## **Implementation**

- Controlling the number of points where vehicles can leave the site will allow sweeping and vacuuming efforts to be focused, and perhaps save money.
- Inspect potential sediment tracking locations daily.
- Visible sediment tracking should be swept or vacuumed on a daily basis.
- Do not use kick brooms or sweeper attachments. These tend to spread the dirt rather than remove it.

| Categories |   |      |  |  |
|------------|---|------|--|--|
| EC         | Erosion Control                                     |      |  |  |
| SE         | Sediment Control                                    | X    |  |  |
| TC         | Tracking Control                                    | abla |  |  |
| WE         | Wind Erosion Control                                |      |  |  |
| NS         | Non-Stormwater<br>Management Control                |      |  |  |
| WM         | Waste Management and<br>Materials Pollution Control |      |  |  |
|            |   |      |  |  |

#### Legend:

- ☑ Primary Objective
- Secondary Objective

## **Targeted Constituents**

| • | Sediment       | Ø |
|---|----------------|---|
|   | Nutrients      |   |
|   | Trash          | V |
|   | Metals         |   |
|   | Bacteria       |   |
|   | Oil and Grease | ✓ |
|   | Organics       |   |

#### **Potential Alternatives**

None



# Street Sweeping and Vacuuming S

SE-7

 If not mixed with debris or trash, consider incorporating the removed sediment back into the project

#### Costs

Rental rates for self-propelled sweepers vary depending on hopper size and duration of rental. Expect rental rates from \$58/hour (3 yd³ hopper) to \$88/hour (9 yd³ hopper), plus operator costs. Hourly production rates vary with the amount of area to be swept and amount of sediment. Match the hopper size to the area and expect sediment load to minimize time spent dumping.

## **Inspection and Maintenance**


- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- When actively in use, points of ingress and egress must be inspected daily.
- When tracked or spilled sediment is observed outside the construction limits, it must be removed at least daily. More frequent removal, even continuous removal, may be required in some jurisdictions.
- Be careful not to sweep up any unknown substance or any object that may be potentially hazardous.
- Adjust brooms frequently; maximize efficiency of sweeping operations.
- After sweeping is finished, properly dispose of sweeper wastes at an approved dumpsite.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Labor Surcharge and Equipment Rental Rates, State of California Department of Transportation (Caltrans), April 1, 2002 – March 31, 2003.

# Sandbag Barrier



## Categories

| EÇ | Erosion Control  | × |
|----|------------------|---|
| SE | Sediment Control | ✓ |

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

- ☑ Primary Category
- Secondary Category

## **Description and Purpose**

A sandbag barrier is a series of sand-filled bags placed on a level contour to intercept or to divert sheet flows. Sandbag barriers placed on a level contour pond sheet flow runoff, allowing sediment to settle out.

## **Suitable Applications**

Sandbag barriers may be suitable:

- As a linear sediment control measure:
  - Below the toe of slopes and erodible slopes.
  - As sediment traps at culvert/pipe outlets.
  - Below other small cleared areas.
  - Along the perimeter of a site.
  - Down slope of exposed soil areas.
  - Around temporary stockpiles and spoil areas.
  - Parallel to a roadway to keep sediment off paved areas.
  - Along streams and channels.
- As linear erosion control measure:
  - Along the face and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow.

## **Targeted Constituents**

Sediment

 $\sqrt{\phantom{a}}$ 

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-14 Biofilter Bags



- At the top of slopes to divert runoff away from disturbed slopes.
- As check dams across mildly sloped construction roads.

#### Limitations

- It is necessary to limit the drainage area upstream of the barrier to 5 acres.
- Sandbags are not intended to be used as filtration devices.
- Easily damaged by construction equipment.
- Degraded sandbags may rupture when removed, spilling sand.
- Sand is easily transported by runoff if bag is damaged or ruptured.
- Installation can be labor intensive.
- Durability of sandbags is somewhat limited and bags may need to be replaced when installation is required for longer than 6 months. When used to detain concentrated flows, maintenance requirements increase.
- Burlap should not be used for sandbags.

## **Implementation**

#### General

A sandbag barrier consists of a row of sand-filled bags placed on a level contour. When appropriately placed, a sandbag barrier intercepts and slows sheet flow runoff, causing temporary ponding. The temporary ponding allows sediment to settle. Sand-filled bags have limited porosity, which is further limited as the fine sand tends to quickly plug with sediment, limiting or completely blocking the rate of flow through the barrier. If a porous barrier is desired, consider SE-1, Silt Fence, SE-5, Fiber Rolls, SE-6, Gravel Bag Berms or SE-14, Biofilter Bags. Sandbag barriers also interrupt the slope length and thereby reduce erosion by reducing the tendency of sheet flows to concentrate into rivulets which erode rills, and ultimately gullies, into disturbed, sloped soils. Sandbag barriers are similar to gravel bag berms, but less porous. Generally, sandbag barriers should be used in conjunction with temporary soil stabilization controls up slope to provide effective erosion and sediment control.

## Design and Layout

- Locate sandbag barriers on a level contour.
- When used for slope interruption, the following slope/sheet flow length combinations apply:
  - Slope inclination of 4:1 (H:V) or flatter: Sandbags should be placed at a maximum interval of 20 ft, with the first row near the slope toe.
  - Slope inclination between 4:1 and 2:1 (H:V): Sandbags should be placed at a maximum interval of 15 ft. (a closer spacing is more effective), with the first row near the slope toe.
    - Slope inclination 2:1 (H:V) or greater: Sandbags should be placed at a maximum interval of 10 ft. (a closer spacing is more effective), with the first row near the slope toe.

- Turn the ends of the sandbag barrier up slope to prevent runoff from going around the barrier.
- Allow sufficient space up slope from the barrier to allow ponding, and to provide room for sediment storage.
- For installation near the toe of the slope, sand bag barriers should be set back from the slope toe to facilitate cleaning. Where specific site conditions do not allow for a set-back, the sand bag barrier may be constructed on the toe of the slope. To prevent flows behind the barrier, bags can be placed perpendicular to a berm to serve as cross barriers.
- Drainage area should not exceed 5 acres.
- Stack sandbags at least three bags high.
- Butt ends of bags tightly.
- Overlap butt joints of row beneath with each successive row.
- Use a pyramid approach when stacking bags.
- In non-traffic areas
  - Height = 18 in. maximum
  - Top width = 24 in. minimum for three or more layer construction
  - Side slope = 2:1 (H:V) or flatter
- In construction traffic areas
  - Height = 12 in. maximum
  - Top width = 24 in. minimum for three or more layer construction.
  - Side slopes = 2:1 (H:V) or flatter.
- See typical sandbag barrier installation details at the end of this fact sheet.

#### Materials

- Sandbag Material: Sandbag should be woven polypropylene, polyethylene or polyamide fabric, minimum unit weight of 4 ounces/yd², Mullen burst strength exceeding 300 lb/in² in conformance with the requirements in ASTM designation D3786, and ultraviolet stability exceeding 70% in conformance with the requirements in ASTM designation D4355. Use of burlap is not an acceptable substitute, as sand can more easily mobilize out of burlap.
- Sandbag Size: Each sand-filled bag should have a length of 18 in., width of 12 in., thickness of 3 in., and mass of approximately 33 lbs. Bag dimensions are nominal, and may vary based on locally available materials.

Fill Material: All sandbag fill material should be non-cohesive, Class 3 (Caltrans Standard Specification, Section 25) permeable material free from clay and deleterious material, such as recycled concrete or asphalt..

#### Costs

Empty sandbags cost \$0.25 - \$0.75. Average cost of fill material is \$8 per yd³. Additional labor is required to fill the bags. Pre-filled sandbags are more expensive at \$1.50 - \$2.00 per bag. These costs are based upon vendor research.

## **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Sandbags exposed to sunlight will need to be replaced every two to three months due to degradation of the bags.
- Reshape or replace sandbags as needed.
- Repair washouts or other damage as needed.
- Sediment that accumulates behind the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Remove sandbags when no longer needed and recycle sand fill whenever possible and properly dispose of bag material. Remove sediment accumulation, and clean, re-grade, and stabilize the area.


#### References

Standard Specifications for Construction of Local Streets and Roads, California Department of Transportation (Caltrans), July 2002.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.


Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

ig,




NOTES

- Dimension may vary to fit field condition.
- Sandbag barrier shall be a minimum of 3 bags high.
- and a max of 2/3 the height of
- The end of the barrier shall be turned up slope.
- Sandbag rows and layers shall be staggered to eliminate gaps.



## Straw Bale Barrier



## **Description and Purpose**

A straw bale barrier is a series of straw bales placed on a level contour to intercept sheet flows. Straw bale barriers pond sheet- flow runoff, allowing sediment to settle out.

## **Suitable Applications**

Straw bale barriers may be suitable:

- As a linear sediment control measure:
  - Below the toe of slopes and erodible slopes
  - As sediment traps at culvert/pipe outlets
  - Below other small cleared areas
  - Along the perimeter of a site
  - Down slope of exposed soil areas
  - Around temporary stockpiles and spoil areas
  - Parallel to a roadway to keep sediment off paved areas
  - Along streams and channels
- As linear erosion control measure:
  - Along the face and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow

## **Categories**

EC Erosion Control

|V| |X|

 $\checkmark$ 

SE Sediment Control
TC Tracking Control

WE Wind Erosion Control

Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

Primary Objective

**☒** Secondary Objective

## **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

## **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier



- At the top of slopes to divert runoff away from disturbed slopes
- As check dams across mildly sloped construction roads

#### Limitations

Straw bale barriers:

- Are not to be used for extended periods of time because they tend to rot and fall apart
- Are suitable only for sheet flow on slopes of 10 % or flatter
- Are not appropriate for large drainage areas, limit to one acre or less
- May require constant maintenance due to rotting
- Are not recommended for concentrated flow, inlet protection, channel flow, and live streams
- Cannot be made of bale bindings of jute or cotton
- Require labor-intensive installation and maintenance
- Cannot be used on paved surfaces
- Should not to be used for drain inlet protection
- Should not be used on lined ditches
- May introduce undesirable non-native plants to the area

## **Implementation**

#### General

A straw bale barrier consists of a row of straw bales placed on a level contour. When appropriately placed, a straw bale barrier intercepts and slows sheet flow runoff, causing temporary ponding. The temporary ponding provides quiescent conditions allowing sediment to settle. Straw bale barriers also interrupt the slope length and thereby reduce erosion by reducing the tendency of sheet flows to concentrate into rivulets, which erode rills, and ultimately gullies, into disturbed, sloped soils.

Straw bale barriers have not been as effective as expected due to improper use. These barriers have been placed in streams and drainage ways where runoff volumes and velocities have caused the barriers to wash out. In addition, failure to stake and entrench the straw bale has allowed undercutting and end flow. Use of straw bale barriers in accordance with this BMP should produce acceptable results.

#### Design and Layout

- Locate straw bale barriers on a level contour.
  - Slopes up to 10:1 (H:V): Straw bales should be placed at a maximum interval of 50 ft (a closer spacing is more effective), with the first row near the toe of slope.
  - Slopes greater than 10:1 (H:V): Not recommended.

- Turn the ends of the straw bale barrier up slope to prevent runoff from going around the barrier.
- Allow sufficient space up slope from the barrier to allow ponding, and to provide room for sediment storage.
- For installation near the toe of the slope, consider moving the barrier away from the slope toe to facilitate cleaning. To prevent flow behind the barrier, sand bags can be placed perpendicular to the barrier to serve as cross barriers.
- Drainage area should not exceed 1 acre, or 0.25 acre per 100 ft of barrier.
- Maximum flow path to the barrier should be limited to 100 ft.
- Straw bale barriers should consist of two parallel rows.
  - Butt ends of bales tightly
  - Stagger butt joints between front and back row
  - Each row of bales must be trenched in and firmly staked
- Straw bale barriers are limited in height to one bale laid on its side.
- Anchor bales with either two wood stakes or four bars driven through the bale and into the soil. Drive the first stake towards the butt joint with the adjacent bale to force the bales together.
- See attached figure for installation details.

#### Materials

- Straw Bale Size: Each straw bale should be a minimum of 14 in. wide, 18 in. in height, 36 in. in length and should have a minimum mass of 50 lbs. The straw bale should be composed entirely of vegetative matter, except for the binding material.
- **Bale Bindings:** Bales should be bound by steel wire, nylon or polypropylene string placed horizontally. Jute and cotton binding should not be used. Baling wire should be a minimum diameter of 14 gauge. Nylon or polypropylene string should be approximately 12 gauge in diameter with a breaking strength of 80 lbs force.
- Stakes: Wood stakes should be commercial quality lumber of the size and shape shown on the plans. Each stake should be free from decay, splits or cracks longer than the thickness of the stake, or other defects that would weaken the stakes and cause the stakes to be structurally unsuitable. Steel bar reinforcement should be equal to a #4 designation or greater. End protection should be provided for any exposed bar reinforcement.

#### Costs

Straw bales cost \$5 - \$7 each. Adequate labor should be budgeted for installation and maintenance.


## **Inspection and Maintenance**


#### Maintenance

- Inspect BMPs prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season.
- Straw bales degrade, especially when exposed to moisture. Rotting bales will need to be replaced on a regular basis.
- Replace or repair damaged bales as needed.
- Repair washouts or other damages as needed.
- Sediment that accumulates in the BMP must be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed at an appropriate location.
- Remove straw bales when no longer needed. Remove sediment accumulation, and clean, regrade, and stabilize the area. Removed sediment should be incorporated in the project or disposed of.


#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.





## **Storm Drain Inlet Protection**



## **Description and Purpose**

Storm drain inlet protection consists of a sediment filter or an impounding area in, around or upstream of a storm drain, drop inlet, or curb inlet. Storm drain inlet protection measures temporarily pond runoff before it enters the storm drain, allowing sediment to settle. Some filter configurations also remove sediment by filtering, but usually the ponding action results in the greatest sediment reduction. Temporary geotextile storm drain inserts attach underneath storm drain grates to capture and filter storm water.

## **Suitable Applications**

Every storm drain inlet receiving runoff from unstabilized or otherwise active work areas should be protected. Inlet protection should be used in conjunction with other erosion and sediment controls to prevent sediment-laden stormwater and non-stormwater discharges from entering the storm drain system.

#### Limitations

- Drainage area should not exceed 1 acre.
- In general straw bales should not be used as inlet protection.
- Requires an adequate area for water to pond without encroaching into portions of the roadway subject to traffic.

# EC Erosion Control SE Sediment Control TC Tracking Control WE Wind Erosion Control Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

## Legend:

- ☑ Primary Category
- ▼ Secondary Category

## **Targeted Constituents**

| $ \nabla$ |
|-----------|
|           |
| ×         |
|           |
|           |
|           |
|           |
|           |

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Rolls

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-14 Biofilter Bags



 Sediment removal may be inadequate to prevent sediment discharges in high flow conditions or if runoff is heavily sediment laden. If high flow conditions are expected, use other onsite sediment trapping techniques in conjunction with inlet protection.

4 144

- Frequent maintenance is required.
- Limit drainage area to 1 acre maximum. For drainage areas larger than 1 acre, runoff should be routed to a sediment-trapping device designed for larger flows. See BMPs SE-2, Sediment Basin, and SE-3, Sediment Traps.
- Excavated drop inlet sediment traps are appropriate where relatively heavy flows are expected, and overflow capability is needed.

## **Implementation**

#### General

Inlet control measures presented in this handbook should not be used for inlets draining more than one acre. Runoff from larger disturbed areas should be first routed through SE-2, Sediment Basin or SE-3, Sediment Trap and/or used in conjunction with other drainage control, erosion control, and sediment control BMPs to protect the site. Different types of inlet protection are appropriate for different applications depending on site conditions and the type of inlet. Alternative methods are available in addition to the methods described/shown herein such as prefabricated inlet insert devices, or gutter protection devices.

## Design and Layout

Identify existing and planned storm drain inlets that have the potential to receive sediment-laden surface runoff. Determine if storm drain inlet protection is needed and which method to use.

- The key to successful and safe use of storm drain inlet protection devices is to know where runoff that is directed toward the inlet to be protected will pond or be diverted as a result of installing the protection device.
  - Determine the acceptable location and extent of ponding in the vicinity of the drain inlet. The acceptable location and extent of ponding will influence the type and design of the storm drain inlet protection device.
  - Determine the extent of potential runoff diversion caused by the storm drain inlet protection device. Runoff ponded by inlet protection devices may flow around the device and towards the next downstream inlet. In some cases, this is acceptable; in other cases, serious erosion or downstream property damage can be caused by these diversions. The possibility of runoff diversions will influence whether or not storm drain inlet protection is suitable; and, if suitable, the type and design of the device.
- The location and extent of ponding, and the extent of diversion, can usually be controlled through appropriate placement of the inlet protection device. In some cases, moving the inlet protection device a short distance upstream of the actual inlet can provide more efficient sediment control, limit ponding to desired areas, and prevent or control diversions.

- Six types of inlet protection are presented below. However, it is recognized that other effective methods and proprietary devices exist and may be selected.
  - Silt Fence: Appropriate for drainage basins with less than a 5% slope, sheet flows, and flows under 0.5 cfs.
  - Excavated Drop Inlet Sediment Trap: An excavated area around the inlet to trap sediment (SE-3).
  - Gravel bag barrier: Used to create a small sediment trap upstream of inlets on sloped, paved streets. Appropriate for sheet flow or when concentrated flow may exceed 0.5 cfs, and where overtopping is required to prevent flooding.
  - Block and Gravel Filter: Appropriate for flows greater than 0.5 cfs.
  - Temporary Geotextile Storm drain Inserts: Different products provide different features. Refer to manufacturer details for targeted pollutants and additional features.
  - Biofilter Bag Barrier: Used to create a small retention area upstream of inlets and can be located on pavement or soil. Biofilter bags slowly filter runoff allowing sediment to settle out. Appropriate for flows under 0.5 cfs.
- Select the appropriate type of inlet protection and design as referred to or as described in this fact sheet.
- Provide area around the inlet for water to pond without flooding structures and property.
- Grates and spaces around all inlets should be sealed to prevent seepage of sediment-laden water.
- Excavate sediment sumps (where needed) 1 to 2 ft with 2:1 side slopes around the inlet.

## Installation

- DI Protection Type 1 Silt Fence Similar to constructing a silt fence; see BMP SE-1, Silt Fence. Do not place fabric underneath the inlet grate since the collected sediment may fall into the drain inlet when the fabric is removed or replaced and water flow through the grate will be blocked resulting in flooding. See typical Type 1 installation details at the end of this fact sheet.
  - 1. Excavate a trench approximately 6 in. wide and 6 in. deep along the line of the silt fence inlet protection device.
  - 2. Place 2 in. by 2 in. wooden stakes around the perimeter of the inlet a maximum of 3 ft apart and drive them at least 18 in. into the ground or 12 in. below the bottom of the trench. The stakes should be at least 48 in.
  - 3. Lay fabric along bottom of trench, up side of trench, and then up stakes. See SE-1, Silt Fence, for details. The maximum silt fence height around the inlet is 24 in.
  - 4. Staple the filter fabric (for materials and specifications, see SE-1, Silt Fence) to wooden stakes. Use heavy-duty wire staples at least 1 in. in length.

- 5. Backfill the trench with gravel or compacted earth all the way around.
- DI Protection Type 2 Excavated Drop Inlet Sediment Trap Install filter fabric fence in accordance with DI Protection Type 1. Size excavated trap to provide a minimum storage capacity calculated at the rate 67 yd³/acre of drainage area. See typical Type 2 installation details at the end of this fact sheet.
- **DI Protection Type 3 Gravel bag -** Flow from a severe storm should not overtop the curb. In areas of high clay and silts, use filter fabric and gravel as additional filter media. Construct gravel bags in accordance with SE-6, Gravel Bag Berm. Gravel bags should be used due to their high permeability. See typical Type 3 installation details at the end of this fact sheet.
  - 1. Construct on gently sloping street.
  - 2. Leave room upstream of barrier for water to pond and sediment to settle.
  - 3. Place several layers of gravel bags overlapping the bags and packing them tightly together.
  - 4. Leave gap of one bag on the top row to serve as a spillway. Flow from a severe storm (e.g., 10 year storm) should not overtop the curb.
- DI Protection Type 4 Block and Gravel Filter Block and gravel filters are suitable for curb inlets commonly used in residential, commercial, and industrial construction. See typical Type 4 installation details at the end of this fact sheet.
  - 1. Place hardware cloth or comparable wire mesh with 0.5 in. openings over the drop inlet so that the wire extends a minimum of 1 ft beyond each side of the inlet structure. If more than one strip is necessary, overlap the strips. Place woven geotextile over the wire mesh.
  - 2. Place concrete blocks lengthwise on their sides in a single row around the perimeter of the inlet, so that the open ends face outward, not upward. The ends of adjacent blocks should abut. The height of the barrier can be varied, depending on design needs, by stacking combinations of blocks that are 4 in., 8 in., and 12 in. wide. The row of blocks should be at least 12 in. but no greater than 24 in. high.
  - 3. Place wire mesh over the outside vertical face (open end) of the concrete blocks to prevent stone from being washed through the blocks. Use hardware cloth or comparable wire mesh with 0.5 in. opening.
  - 4. Pile washed stone against the wire mesh to the top of the blocks. Use 0.75 to 3 in.
- DI Protection Type 5 Temporary Geotextile Insert (proprietary) Many types of temporary inserts are available. Most inserts fit underneath the grate of a drop inlet or inside of a curb inlet and are fastened to the outside of the grate or curb. These inserts are removable and many can be cleaned and reused. Installation of these inserts differs between manufacturers. Please refer to manufacturer instruction for installation of proprietary devices.

- **DI Protection Type 6 Biofilter bags** Biofilter bags may be used as a substitute for gravel bags in low-flow situations. Biofilter bags should conform to specifications detailed in SE-14, Biofilter bags.
  - 1. Construct in a gently sloping area.
  - 2. Biofilter bags should be placed around inlets to intercept runoff flows.
  - 3. All bag joints should overlap by 6 in.
  - 4. Leave room upstream for water to pond and for sediment to settle out.
  - 5. Stake bags to the ground as described in the following detail. Stakes may be omitted if bags are placed on a paved surface.

#### Costs

- Average annual cost for installation and maintenance of DI Type 1-4 and 6 (one year useful life) is \$200 per inlet.
- Temporary geotextile inserts are proprietary and cost varies by region. These inserts can often be reused and may have greater than 1 year of use if maintained and kept undamaged. Average cost per insert ranges from \$50-75 plus installation, but costs can exceed \$100. This cost does not include maintenance.

## **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Silt Fences. If the fabric becomes clogged, torn, or degrades, it should be replaced. Make sure the stakes are securely driven in the ground and are in good shape (i.e., not bent, cracked, or splintered, and are reasonably perpendicular to the ground). Replace damaged stakes. At a minimum, remove the sediment behind the fabric fence when accumulation reaches one-third the height of the fence or barrier height.
- Gravel Filters. If the gravel becomes clogged with sediment, it should be carefully removed from the inlet and either cleaned or replaced. Since cleaning gravel at a construction site may be difficult, consider using the sediment-laden stone as fill material and put fresh stone around the inlet. Inspect bags for holes, gashes, and snags, and replace bags as needed. Check gravel bags for proper arrangement and displacement.
- Sediment that accumulates in the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Inspect and maintain temporary geotextile insert devices according to manufacturer's specifications.
- Remove storm drain inlet protection once the drainage area is stabilized.


- Clean and regrade area around the inlet and clean the inside of the storm drain inlet, as it should be free of sediment and debris at the time of final inspection.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management Manual for The Puget Sound Basin, Washington State Department of Ecology, Public Review Draft, 1991.


Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.




DI PROTECTION TYPE 1
NOT TO SCALE

#### NOTES:


- 1. For use in areas where grading has been completed and final soil stabilization and seeding are pending.
- 2. Not applicable in paved areas.
- 3. Not applicable with concentrated flows.






#### Notes

- 1. For use in cleared and grubbed and in graded areas.
- 2. Shope basin so that longest inflow area faces longest length of trap.
- 3. For concentrated flows, shape bosin in 2:1 ratio with length oriented towards direction of flow.



TYPICAL PROTECTION FOR INLET ON SUMP





TYPICAL PROTECTION FOR INLET ON GRADE

#### NOTES:

- 1. Intended for short-term use.
- 2. Use to inhibit non-storm water flow.
- 3. Allow for proper maintenance and cleanup.
- 4. Bags must be removed after adjacent operation is completed
- 5. Not applicable in areas with high silts and clays without filter fabric.

# DI PROTECTION TYPE 3






DI PROTECTION - TYPE 4

NOT TO SCALE

 $\square$ 

 $\square$ 



# **Description and Purpose**

Active Treatment Systems (ATS) reduce turbidity of construction site runoff by introducing chemicals to stormwater through direct dosing or an electrical current to enhance flocculation, coagulation, and settling of the suspended sediment. Coagulants and flocculants are used to enhance settling and removal of suspended sediments and generally include inorganic salts and polymers (USACE, 2001). The increased flocculation aids in sedimentation and ability to remove fine suspended sediments, thus reducing stormwater runoff turbidity and improving water quality.

# **Suitable Applications**

ATS can reliably provide exceptional reductions of turbidity and associated pollutants and should be considered where turbid discharges to sediment and turbidity sensitive waters cannot be avoided using traditional BMPs. Additionally, it may be appropriate to use an ATS when site constraints inhibit the ability to construct a correctly sized sediment basin, when clay and/or highly erosive soils are present, or when the site has very steep or long slope lengths.

#### Limitations

Dischargers choosing to utilize chemical treatment in an ATS must follow all guidelines of the Construction General Permit Attachment F – Active Treatment System Requirements. General limitations are as follows:

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

.... Waste Management and

WM Waste Management and Materials Pollution Control

# Legend:

☑ Primary Category

▼ Secondary Category

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



# **Active Treatment Systems**

- Numeric Effluent Limit (NEL) for all discharges (10 NTU daily flow-weighted average)
- Limited availability of chemical residual testing procedures that meet permit requirements for flow-through treatment
- Specific field and classroom ATS training required to operate equipment
- Batch treatment requires extensive toxicity testing of effluent
- Batch treatment requires large footprint to accommodate treatment cells
- Requires additional filtration to remove residual floc and treatment chemicals prior to discharge
- Petroleum based polymers should not be used
- Requires site-specific design and equipment
- Limited discharge rates depending on receiving water body
- Labor intensive operation and maintenance
- ATS costs are higher on a unit basis for smaller sites that would be expected to have a lower volume of treated runoff
- ATS costs are seasonably variable due to increases or decreases in rainfall volumes

#### **Implementation**

Turbidity is difficult to control once fine particles are suspended in stormwater runoff from a construction site. Sedimentation ponds are effective at removing larger particulate matter by gravity settling, but are ineffective at removing smaller particulates such as clay and fine silt. Sediment ponds are typically designed to remove sediment no smaller than medium silt (0.02 mm). ATS may be used to reduce the turbidity of stormwater runoff. With an ATS, very high turbidities can be reduced to levels comparable to what is found in streams during dry weather.

#### Criteria for ATS Product Use

Chemically treated stormwater discharged from construction sites must be non-toxic to aquatic organisms. The following protocol should be used to evaluate chemicals proposed for stormwater treatment at construction sites. Authorization to use a chemical in the field based on this protocol does not relieve the applicant from responsibility for meeting all discharge and receiving water criteria applicable to a site.

An ATS Plan, which includes an Operation and Maintenance component, a Monitoring, Sampling and Reporting component, a Health and Safety component, and a Spill Prevention component must be prepared and submitted to the Regional Water Quality Control Board (RWQCB).

- Treatment chemicals should be approved by EPA for potable water use or otherwise be demonstrated to be protective of human health and the environment. Chemical residual or whole effluent toxicity testing is required.
- Prior to field use of chemical treatment, jar tests are to be conducted to demonstrate that turbidity reduction necessary to meet the NELs and receiving water criteria can be achieved. Test conditions, including but not limited to raw water quality and jar test procedures, should be indicative of field conditions. Although these small-scale tests cannot be expected to reproduce performance under field conditions, they are indicative of treatment capability. A minimum of six site-specific jar tests must be conducted per chemical.
- The proposed maximum dosage should be at least a factor of five lower than the no observed effects concentration (NOEC).
- Effluent discharge from an ATS to a receiving water is conditional upon the favorable results of full-scale whole effluent bioassay/toxicity testing for batch treatment systems and upon chemical residuals testing for flow-through systems.
- Contact the RWQCB for a list of treatment chemicals that may be pre-approved for use.

# Active Treatment System Design Considerations

The design and operation of an ATS should take into consideration the factors that determine optimum, cost-effective performance. While site characteristics will influence system design, it is important to recognize the following overriding considerations:

- The right chemical must be used at the right dosage. A dosage that is either too low or too high will not produce the lowest turbidity. There is an optimum dosage rate. This is a situation where the adage "adding more is always better" is not the case.
- The coagulant must be mixed rapidly into the water to insure proper dispersion.
- The mixing system for batch treatment must be sized to provide adequate mixing for the design storage volume. Lack of adequate mixing during the flocculation phase results in flocs that are too small and/or insufficiently dense. Too much mixing can rapidly destroy floc as it is formed.
- Care must be taken in the design of the withdrawal system to minimize outflow velocities and to prevent floc discharge. The discharge should be directed through a filtration system such as sand, bag, or cartridge filter that would catch any unintended floc discharge.
- ATS is also regulated for pH of the discharge. A pH-adjusting chemical should be added into the treated water to control pH if the selected coagulant requires alteration of the pH of the discharge outside of the acceptable range.

#### Active Treatment System Design

ATS can be designed as batch treatment systems using either ponds or portable trailer-mounted tanks, or as flow-through systems using any number of proprietary designed systems.




Figure has been adapted from Port of Seattle response to Washington Dept. of Ecology Action Order 2948

#### **Batch Treatment**

Batch Treatment systems consist of the stormwater collection system (either temporary diversion or the permanent site drainage system); a sediment basin, trap or holding tanks; pumps; a chemical feed system; treatment cells; and, interconnecting piping.

Batch treatment systems should use a minimum of two lined treatment cells. Multiple treatment cells allow for clarification of treated water while other cells are being filled or emptied. Treatment cells may be basins, traps, or tanks. Portable tanks may also be suitable for some sites.

The following equipment should be located in a secured, covered location:

- The chemical injector
- Secondary contaminant for acid, caustic, buffering compound, and treatment chemical
- Emergency shower and eyewash
- Monitoring equipment which consists of a pH meter and a turbidimeter (if not already within the instrumentation panel of the chemical injector)

#### Flow-through Treatment

At a minimum, a flow-through ATS system consists of the stormwater collection system (either temporary diversion or the permanent site drainage system), an untreated stormwater storage pond or holding tank, and a chemically enhanced filtration system.

Stormwater is collected at interception point(s) on the site and is diverted by gravity or by pumping to an untreated stormwater storage pond or other untreated stormwater holding area.

The stormwater is stored until treatment occurs. It is important that the holding pond be large enough to provide adequate storage.

Stormwater is then pumped from the untreated stormwater storage pond to the chemically enhanced filtration system where polymer is added. Adjustments to pH may be necessary before chemical addition. The filtration system continually monitors the stormwater for turbidity and pH. If the discharge water is out of the acceptable turbidity or pH range, the water is recycled to the untreated stormwater pond (or holding tank) where it can be retreated. Flow through systems must ensure that:

- Cumulative flow volume shall be recorded daily. The data recording system shall have the capacity to record a minimum of seven days of continuous data.
- Instrumentation systems are interfaced with system control to provide auto shutoff or recirculation in the event that effluent measurements exceed turbidity or pH.
- Upon system upset, power failure, or other catastrophic event, the ATS will default to a recirculation mode or safe shut down.
- The instrumentation system provides a method for controlling coagulant dose, to prevent potential overdosing.

## Sizing Criteria

An ATS shall be designed and approved by a Certified Professional in Erosion and Sediment Control (CPESC), a Certified Professional in Storm Water Quality (CPSWQ); a California registered civil engineer; or any other California registered engineer.

ATS must be designed to capture and treat (within 72 hours) runoff from the 10-year 24-hour storm event. The runoff volume of the watershed area to be treated from this size storm event is required to be calculated using the Rational Method with a runoff coefficient of 1.

If sediment basins are used to capture flow-through or batch treatment, see SE-2, Sediment Basin, for design criteria. Bypass should be provided around the ATS to accommodate extreme storm events. Primary settling should be encouraged in the sediment basin/storage pond. A forebay with access for maintenance may be beneficial.

The permissible discharge rate governed by potential downstream effect should be used to calculate the recommended size of the treatment cells. Local requirements related to Phase I or Phase II NPDES permit thresholds should be considered in developing maximum discharge rates the ATS Plan.

#### Costs

Costs for ATS may be significant due to equipment rental requirements and cost of chemicals. ATS cost is lower on a treated unit-basis for large construction sites with large volumes of runoff.

# **Inspection and Maintenance**

ATS must be operated and maintained by individuals with experience in their use and trained in accordance with training requirements below. ATS should be monitored continuously while in

use. A designated responsible person shall be on site daily at all times during treatment operations. Daily on-site visual monitoring of the system for proper performance shall be conducted and recorded in the project data log. The name, phone number, and training documentation of the person responsible for system operation and monitoring shall be included in the project data log.

The following monitoring requirements and results should be recorded in the data log:

## Operational and Compliance Monitoring

- Effluent flow rate and volume shall be continuously monitored and recorded at 15- minute or less intervals.
- Influent and effluent pH must be continuously monitored and recorded at 15-minute or less intervals.
- Influent and effluent turbidity (expressed in NTU) must be continuously monitored and recorded at 15-minute or less intervals.
- The type and amount of chemical used for pH adjustment, if any, shall be monitored and recorded.
- Dose rate of chemical used in the ATS system (expressed in mg/L) shall be monitored and reported 15-minutes after startup and every 8 hours of operation.
- Laboratory duplicates monthly laboratory duplicates for residual coagulant analysis must be performed and records shall be maintained onsite.
- Effluent shall be monitored and recorded for residual chemical/additive levels.
- If a residual chemical/additive test does not exist and the ATS is operating in a batch treatment mode of operation refer to the toxicity monitoring requirements below.

#### **Toxicity Monitoring**

#### **Batch Treatment**

Toxicity testing for systems operated in batch treatment mode should be made in accordance with the following:

- Acute toxicity testing on effluent samples representing effluent from each batch prior to discharge shall be undertaken. All bioassays shall be sent to a laboratory certified by the Department of Health Services (DHS) Environmental Laboratory Accreditation Program (ELAP). The required field of testing number for Whole Effluent Toxicity (WET) testing is E113.
- Acute toxicity tests shall be conducted with the following species and protocols. The methods to be used in the acute toxicity testing shall be those outlined for a 96-hour acute test in "Methods for Measuring the Acute Toxicity of Effluents and Receiving Water to Freshwater and Marine Organisms, USEPA-841-R-02-012" for Fathead minnow, *Pimephales promelas*. Rainbow trout, *Oncorhynchus mykiss*, may be used as a substitute for fathead minnow.

All toxicity tests shall meet quality assurance criteria and test acceptability criteria in the most recent versions of the EPA test method for WET testing.

## Flow-through Treatment

Toxicity testing for systems operated in flow-through treatment mode should be made in accordance with the following:

- A residual chemical test method shall be used that has a method detection limit (MDL) of 10% or less than the maximum allowable threshold concentration (MATC) for the specific coagulant in use and for the most sensitive species of the chemical used. The MATC is equal to the geometric mean of the No Observed Effect Concentration (NOEC) and Lowest Observed Effect Concentration (LOEC) Acute and Chronic toxicity results for most sensitive species determined for the specific coagulant.
- The residual chemical test method shall produce a result within one hour of sampling.
- A California State certified laboratory shall validate the selected residual chemical test. Specifically the lab will review the test protocol, test parameters, and the detection limit of the coagulant. The discharger shall electronically submit this documentation as part of the ATS Plan.

## Numeric Effluent Limit (NEL) Compliance:

All chemically treated stormwater must be sampled and tested for compliance with pH and turbidity limits. These limits have been established by the Construction General Permit. Sampling and testing for other pollutants may also be necessary at some sites. Turbidity limits have been set as 10 NTU as a daily flow-weighted average or 20 NTU from a single sample. pH must be within the range of 6.0 to 9.0 standard units. It is often possible to discharge treated stormwater that has a lower turbidity than the receiving water and that matches the pH.

Treated stormwater samples and measurements should be taken from the discharge pipe or another location representative of the nature of the treated stormwater discharge. Samples used for determining compliance with the water quality standards in the receiving water should not be taken from the treatment pond prior to decanting. Compliance with the water quality standards is determined in the receiving water.

#### Operator Training:

Operators shall have training specific to using an ATS and liquid coagulants for stormwater discharges in California. The training shall be in the form of a formal class with a certificate and requirements for testing and certificate renewal. Training shall include a minimum of eight hours classroom and 32 hours field training.

#### Standard BMPs:

Erosion and sediment control BMPs should be implemented throughout the site to prevent erosion and discharge of sediment to the ATS. Some types of chemical coagulation and flocculation are only achievable in water below a certain turbidity; therefore minimizing the amount of sediment reaching the system will increase the likelihood of meeting effluent limits and will potentially lower costs of chemical dosing.

# Sediment Removal and Disposal

- Sediment shall be removed from the storage or treatment cells as necessary to ensure that the cells maintain their required water storage (i.e., volume) capability.
- Handling and disposal of all solids generated during ATS operations shall be done in accordance with all local, state, and federal laws and regulations.
- If sediment is determined to be non-toxic, it may be incorporated into the site away from drainages.

#### References

Engineering and Design – Precipitation/Coagulation/Flocculation. United States Army Corps of Engineers, EM 1110-1-4012, 2001.

Evaluation of Active Treatment Systems (ATS) for Construction Site Runoff. California Building and Industry Association (prepared by Geosyntec Consultants), 2008.

Stormwater Management Manual for Western Washington, Volume II – Construction Stormwater Pollution Prevention, Washington State Department of Ecology, August 2001.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.



#### **Categories**

| EC | Erosion Control  | X |
|----|------------------|---|
| SE | Sediment Control | V |
| TC | Tracking Control |   |

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

**☒** Secondary Category

# **Description and Purpose**

Temporary silt dikes are pre-manufactured devices that are typically specified and installed for semi-permanent drainage and sediment control on the perimeter of disturbed sites or stockpiles and as check dams within channels.

# **Suitable Applications**

Temporary silt dikes are generally used in areas as a substitute for fiber rolls and silt fences to slow down runoff water, divert drainage or contain fines and sediment. A temporary silt dike typically consists of a triangular foam or recycled rubber core covered in geotextile fabric. Temporary silt dikes are a linear control and have a variety of profiles (triangular, round, and square). Temporary silt dikes may be suitable for:

- On paved surfaces for perimeter protection.
- As check structures in channels.
- Along the perimeter of disturbed sites in lieu of silt fence.
- At operational storm drains as a form of inlet protection.
- Around temporary stockpiles or material/equipment storage areas.
- At the interface between graveled driveways and pavement.
- Along the toe of exposed and erodible slopes.

# **Targeted Constituents**

Sediment 
☑

X

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Roll

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier



#### Limitations

- Temporary silt dikes require additional measures to adhere to asphalt in cold and windy climates, as glue may not adhere adequately to the pavement.
- Temporary silt dikes may not be appropriate for drainage areas greater than 5 acres.
- Runoff will pond upstream of the barrier, possibly causing flooding or bypass if sufficient space does not exist to accommodate ponding.
- Temporary silt dikes may require frequent maintenance especially when used near vehicle traffic or to detain concentrated flows (e.g. check dams or inlet protection).
- When used to detain concentrated flows, maintenance requirements increase.

## **Implementation**

#### General

When appropriately placed, temporary silt dikes intercept and slow sheet flow runoff, causing temporary ponding. The temporary ponding provides quiescent conditions allowing sediment to settle. The core is porous, which allows the ponded runoff to flow slowly through the silt dike, releasing the runoff as sheet flows. Generally, temporary silt dikes should be used in conjunction with temporary soil stabilization controls up slope to provide effective erosion and sediment control or as a non-stormwater perimeter control.

## Design and Layout

- Temporary silt dikes used on soil should be attached to the ground per manufacturer specifications.
- Temporary silt dikes used on asphalt or concrete may be attached using a variety of methods, including nailing the dikes to the payement, or using a high strength adhesive.
- Follow manufacturer specifications when installing temporary silt dikes.
- Allow sufficient space up slope from the silt dikes to allow ponding, and to provide room for sediment storage.
- For installation near the toe of the slope, temporary silt dike should be set back three feet from the slope toe to facilitate cleaning. Where site conditions do not allow set back, the silt dike may be constructed on the toe of the slope. To prevent flows behind the barrier, bags can be placed perpendicular to a berm to serve as cross barriers.
- Drainage area should not exceed 5 acres.
- Butt ends of temporary silt dike tightly. Overlaps should be sealed in accordance with the manufacturer's detail.

#### Materials

Several manufactured products are available.

#### Costs

Silt dike averages \$35-45 per 7 ft. section.

# **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Temporary silt dike exposed to sunlight will need to be replaced more frequently due to photo-degradation.
- Reshape or replace sections of damaged temporary silt dike as needed.
- Repair washouts or other damage as needed.
- Sediment that accumulates behind the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Remove temporary silt dikes when no longer needed. Remove sediment accumulation and clean, re-grade, and stabilize the area. Removed sediment should be incorporated in the project or disposed of properly.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

# **Compost Socks and Berms**



## **Description and Purpose**

Compost socks and berms act as three-dimensional biodegradable filtering structures to intercept runoff where sheet flow occurs and are generally placed at the site perimeter. or at intervals on sloped areas. Compost socks are generally a mesh sock containing compost and a compost berm is a dike of compost, trapezoidal in cross section. When employed to intercept sheet flow, both BMPs are placed perpendicular to the flow of runoff, allowing filtered runoff to pass through the compost and retaining sediment (and potentially other pollutants). A compost sock can be assembled on site by filling a mesh sock (e.g. with a pneumatic blower). The compost berm should be constructed using a backhoe or equivalent and/or a pneumatic delivery (blower) system and should be properly compacted. Compost socks and berms act as filters, reduce runoff velocities, and in some cases, aid in establishing vegetation.

Compost is organic, biodegradable, and renewable. Compost provides soil structure that allows water to infiltrate the compost medium which helps prevent rill erosion and the retained moisture promotes seed germination and vegetation growth, in addition to providing organic matter and nutrients important for fostering vegetation. Compost improves soil quality and productivity, as well as erosion and sediment control. The compost of the compost sock or berm can be selected that targets site specific objectives in capturing sediment and other pollutants, supporting vegetation, or additional erosion control.

|    | egories     |  |
|----|-------------|--|
| EC | Erosion Con |  |

EC Erosion Control 

SE Sediment Control 

✓

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

✓ Secondary Category

# **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-1 Silt Fence

SE-5 Fiber Roll

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-14 Biofilter Bags



Compost is typically derived from combinations of feedstocks, biosolids, leaf and yard trimmings, manure, wood, or mixed solid waste. Many types of compost are products of municipal recycle or "Greenwaste" programs. Compost is organic and biodegradable and can be left onsite. There are many types of compost with a variety of properties with specific functions, and accordingly compost selection is an important design consideration in the application of this type of erosion and sediment control.

# **Suitable Applications**

- Along the toe, top, face, and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow (compost berms should only be used at the top of slopes or on slopes 4:1 (H:V) or flatter, all other slope applications should use compost socks)
- Along the perimeter of a project
- As check dams in unlined ditches (compost socks only)
- Down-slope of exposed soil areas
- At operational storm drains as a form of inlet protection (compost socks only)
- Around temporary stockpiles

Compost socks and berms do not require special trenching or BMP removal compared to other sediment control methods (e.g. silt fence or fiber rolls). Compost socks and berms can remain in place after earth disturbing activities are completed or the compost components can be spread over the site providing nutrients for plant growth and augmenting soil structure. BMPs that remain in place are particularly advantageous below embankments, especially adjacent streams, by limiting re-entry and the disturbance to sensitive areas.

Compost can be pre-seeded prior to application (recommended by the EPA for construction site stormwater runoff control and required for compost socks) or seeded after installation (for compost berms only). The compost medium can also remove pollutants in stormwater including heavy metals; oil and grease; and hydrocarbons.

#### **Limitations**

- Compost can potentially leach nutrients (dissolved phosphorus and nitrogen) into runoff and potentially impact water quality. Compost should not be used directly upstream from nutrient impaired waterbodies (Adams et. al, 2008).
- Compost may also contain other undesirable constituents that are detrimental to water quality. Compost should be obtained from a supplier certified by the California Integrated Waste Management Board or compost should otherwise meet the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7. Carefully consider the qualifications and experience of any compost producer/supplier.
- Application by hand is more time intensive and potentially costly. Using a pneumatic blower truck is the recommended cost effective method of assembly.
- Compost socks and berms should not be employed at the base of slopes greater than 2:1
   (H:V). They can be employed with other erosion control methods for steeper slopes.

# **Compost Socks and Berms**

- Difficult to move once saturated.
- Compost berms should not be applied in areas of concentrated flows.
- Compost socks and berms are easy to fix; however, they are susceptible to damage by frequent traffic. Compost socks can be used around heavy machinery, but regular disturbance decreases sock performance.

# **Implementation**

#### **Compost Materials**

- California Compost Regulations (Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3) define and require a quality of compost for application. Compost should comply with all physical and chemical requirements. Specific requirements are provided in Table 1, taken from Caltrans Standard Special Provision 10-1 (SSP 10-1), Erosion Control (Compost Blanket).
- The compost producer should be fully permitted as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility should certify that it follows guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
- The compost producer should be a participant in United States Composting Council's Seal of Testing Assurance program.
- Compost medium parameter specifications for compost socks and berms have been developed to assist in compost selection, such as those provided by the American Association of State Highway Transportation Officials (AASHTO).
- Particle size is important parameter for selecting compost. Well consolidated coarser grades
  of compost (e.g. small and large pieces) perform better for filtration objectives, while finer
  grades better support vegetation. Particle size of the compost should be selected based on
  site conditions, such as expected precipitation, and filtration goals and / or long term plant
  nutrients.
- Compost moisture should be considered for composition quality and application purposes. A range of 30-50% is typical. Compost that is too dry is hard to apply and compost that is too wet is more difficult (and more expensive) to transport. For arid or semi-arid areas, or for application during the dry season, use compost with greater moisture content than areas with wetter climates. For wetter or more humid climates or for application during the wet season, drier composts can be used as the compost will absorb moisture from the ambient air.
- If vegetation establishment is a desired function of the compost, a compost sample should be inspected by a qualified individual. Vegetation has different nutrient and moisture needs.
- Organic content of the compost is also important and should range from 30 to 65% depending on site conditions.

# **Compost Socks and Berms**

- Compost should not be derived from mixed municipal solid waste and should be reasonably free of visible contaminates.
- Compost should not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Metal concentrations in compost should not exceed the maximum metal concentrations listed under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.
- Compost should not possess objectionable odors.
- Compost should be weed free.

Table 1. Physical/Chemical Requirements of Compost Reference - Caltrans SSP-10 Erosion Control Blanket (Compost)

|                           | Reference - Caurans 55F-10 Erosion Control Blanket (Comp  | 031)   |
|---------------------------|---|--|
| Property                  | Test Method   | Requirement  |
| рН                        | *TMECC 04.11-A<br>Elastometric pH 1:5 Slurry Method<br>pH Units   | 6.0-8.0  |
| Soluble Salts             | TMECC 04.10-A<br>Electrical Conductivity 1:5 Slurry Method<br>dS/m (mmhos/cm)   | 0-10.0   |
| Moisture Content          | TMECC 03.09-A<br>Total Solids & Moisture at 70+/- 5 deg C<br>% Wet Weight Basis   | 30-60  |
| Organic Matter<br>Content | TMECC 05,07-A<br>Loss-On-Ignition Organic Matter Method (LOI)<br>% Dry Weight Basis   | 30-65  |
| Maturity                  | TMECC 05.05-A<br>Germination and Vigor<br>Seed Emergence<br>Seedling Vigor<br>% Relative to Positive Control                              | 80 or Above<br>80 or Above   |
| Stability                 | TMECC 05.08-B<br>Carbon Dioxide Evolution Rate<br>mg CO2-C/g OM per day   | 8 or below   |
| Particle Size             | TMECC 02:02-B<br>Sample Sieving for Aggregate Size Classification<br>% Dry Weight Basis   | 100% Passing, 3 inch<br>90-100% Passing, 1 inch<br>65-100% Passing, 3/4 inch<br>0 - 75% Passing, 1/4 inch<br>Maximum length 6 inches |
| Pathogen                  | TMECC 07.01-B<br>Fecal Coliform Bacteria<br>< 1000 MPN/gram dry wt.   | Pass   |
| Pathogen                  | TMECC 07.01-B<br>Salmonella<br>< 3 MPN/4 grams dry wt.  | Pass   |
| Physical Contaminants     | TMECC 02.02-C<br>Man Made Inert Removal and Classification:<br>Plastic, Glass and Metal<br>% > 4mm fraction                               | Combined Total:<br>< 1.0   |
| Physical Contaminants     | TMECC 02.02-C  Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles)  % > 4mm fraction | None Detected  |

<sup>\*</sup>TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

# Installation

- Prior to application, prepare locations for socks and berms by removing brush and thick vegetation. The compost of the sock and/or berm should be allowed to come in full contact with the ground surface.
- Select method to apply the compost sock or berm. A pneumatic blower is most cost effective and most adaptive in applying compost to steep, rough terrain, and hard to reach locations.
- The compost of the berm should be distributed evenly to the surface, compacted, and shaped trapezoidal in cross section. Berm design is generally consists of a base two times the height. AASHTO specification MP 9-03 provides compost berm dimensions based on anticipated site precipitation (AASHTO, 2003 and USEPA, 2009). State agencies, such as Oregon

# **Compost Socks and Berms**

Department of Environmental Quality (ODEQ) have developed berm dimension based on slope steepness and length (ODEQ, 2004).

- Compost socks can be assembled on site by filling mesh socks with the selected compost. Mesh socks can be tied at one end, filled, and then tied at the other end. The ends of socks can be interlocked until the desired length is achieved. The sock diameter is a function of slope steepness and length. Again, ASSHTO provides specifications for various parameters. Compost socks range from 8" to 18", but are typically 12" to 18" in diameter.
- Compost socks are typically placed in contours perpendicular to sheet flow. They can also be placed in V formation on a slope. Compost socks need to be anchored, typically stakes, through the center of the sock. To prevent water flowing around them, the ends of compost socks should be placed upslope.
- Locate compost socks and berms on level contours spaced as follows:
  - Slope inclination of 4:1 (H:V) or flatter: Socks and/or berms should be placed at a maximum interval of 20 ft.
  - Slope inclination between 4:1 and 2:1 (H:V): Socks should be placed at a maximum interval of 15 ft. (a closer spacing is more effective).
  - Slope inclination 2:1 (H:V) or greater: Socks should be placed at a maximum interval of 10 ft. (a closer spacing is more effective).
- Place perimeter socks and berms using a j-hook installation. Use of vegetation will also provide additional anchoring.
- Compost socks and berms can be placed around the perimeter of an affected area, like a silt fence, if the area is flat or on a contour. Do not place these socks and berms where ponded water could become an issue.
- If used at the toe of slopes, the compost sock or berm should at a minimum of 5 to 10 feet away.
- Use additional anchoring and erosion control BMPS in conjunction of the compost socks and berms as needed.
- Consider using compost berms or socks as necessary at the top and/or bottom of the slope for additional erosion control performance.
- Compost socks and berms can also be effective over rocky and frozen ground if installed properly.
- It is recommended that the drainage areas of these compost BMPs do not exceed 0.25 acre per 100 feet placement interval and runoff does not exceed 1 cubic foot per second.

#### Costs

Recently obtained vendor costs indicated \$3.50 per linear foot for compost berm application and \$2.00 per linear foot for 8" socks and \$2.50 per linear foot for 12" socks. Costs do not include final compost sock or berm functions at the end of construction activities, including spreading or removal, if required. ODEQ estimates that compost berms cost 30 percent less than silt fences to install.

## **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Once damage is identified, mend or reapply the sock or berm as needed. Washed out areas should be replaced. If the sock or berm height is breached during a storm, an additional sock can be stacked to increase the sock height and similarly the berm dimensions can be increased, as applicable. An additional sock or berm may be installed upslope, as needed. It may be necessary to apply an additional type of stormwater BMP, such as a compost blanket.
- Sediment contained by the sock or berm should be removed prior reaching 1/3 of the exposed height of the BMP. The sediment can be stabilized with the compost sock or berm with vegetation at the end of construction activities.
- Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs.
- Limit traffic to minimize damage to BMPs or impede vegetation establishment.

#### References

An analysis of Composting as an Environmental Remediation Technology, U.S. Environmental Protection Agency (USEPA), Solid Waste and Emergency Response (5305W), EPA530-R-8-008, 1998.

Characteristics of Compost: Moisture Holding and Water Quality Improvement, Center for Research in Water Resources, Kirchoff, C., Malina, J., and Barrett, M., 2003.

Compost Utilization for Erosion Control, The University of Georgia College of Agricultural and Environmental Sciences, pubs.caes.uga.edu/caespubs/pubcd/B1200.htm, Faucette, B. and Risse, M., 2001.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

Standard Special Provision 10-1, Erosion Control (Compost Blanket), State of California Department of Transportation (Caltrans). 2007 Update.

Evaluation of Environmental Benefits and Impacts of Compost and Industry Standard Erosion and Sediment Controls Measures Used in Construction Activities, Dissertation, Institute of Ecology, University of Georgia, Faucette, B., 2004.

# **Compost Socks and Berms**

National Pollutant Discharge Elimination System (NPDES), Compost Blankets, U.S. Environmental Protection Agency (USEPA).

http://cfpub.epa.gov/npdes/stormwater/menuofbmps/index.cfm?action=factsheet\_results&view=specific&bmp=118, 2009.

Standard Specifications for Transportation Materials and Methods of Sampling and Testing, Designation MP-9, Compost for Erosion/Sediment Control (Filter Berms), Provisional, American Association of State Highway Transportation Officials (AASHTO), 2003.

Stormwater Best Management Practices (BMPs) Field Trials of Erosion Control Compost in Reclamation of Rock Quarry Operations, Nonpoint Source Protection Program CWA §319(h), Texas Commission on Environmental Quality, Adams, T., McFarland, A., Hauck, L., Barrett, M., and Eck, B., 2008.

 $\square$ 



# **Description and Purpose**

Biofilter bags, or bio-bags, are a multi-purpose sediment control BMP consisting of a plastic mesh bag filled with 100% recycled wood product waste. Biofilter bags come in a variety of sizes (30" X 18" and 30" X 9" being common) and generally have between 1-2 cubic yards of recycled wood waste (or wood chips). Biofilter bags work by detaining flow and allowing a slow rate of discharge through the wood media. This action removes suspended sediment through gravity settling of the detained water and filtration within the bag.

# **Suitable Applications**

Biofilter bags are a short-term BMP that can be rapidly deployed, maintained, and replaced. Biofilter bags can be an effective short-term solution to place in developed rills to prevent further erosion until permanent measures can be established. Suitable short-term applications include:

- As a linear sediment control measure:
  - Below the toe of slopes and erodible slopes
  - Below other small cleared areas
  - Along the perimeter of a site (with low-expected flow)
  - Down slope of exposed soil areas
  - Around temporary stockpiles and spoil areas
  - Parallel to a roadway to keep sediment off paved areas

## **Categories**

EC Erosion Control

SE Sediment Control

0----

TR Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Category

**☒** Secondary Category

# **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

SE-1 Silt Fence

SE-4 Check Dams

SE-5 Fiber Roll

SE-6 Gravel Bag Berm

SE-8 Sandbag Barrier

SE-10 Storm Drain Inlet Protection



- Along streams and channels
- As linear erosion control measure:
  - Along the face and at grade breaks of exposed and erodible slopes to shorten slope length and spread runoff as sheet flow
  - At the top of slopes to divert runoff away from disturbed slopes
  - As check dams across mildly sloped construction roads
- Inlet Protection (See SE-10)
- Supplement to silt fences or other sediment control devices

#### Limitations

- Short life-span (2-3 months); regular maintenance and replacement required to ensure effectiveness. Bags will rapidly fill with sediment and reduce permeability.
- Easily damaged by construction vehicles.
- If not properly staked, will fail on slope applications.
- If improperly installed can allow undercutting or side-cutting flow.
- Not effective where water velocities or volumes are high.
- Potentially buoyant and easily displaced if not properly installed.

#### **Implementation**

## General

Biofilter bags are a relatively low cost temporary BMP that are easily deployed and have a simple installation that can be performed by hand. Without proper installation, however, biofilter bags can fail due to their light weight, potential displacement, and multiple joint locations. One of the benefits of utilizing biofilter bags is that the media (wood-product) can be recycled or used onsite when no longer needed (where acceptable).

# Design and Layout – Linear control

- Locate biofilter bags on level contours.
  - Slopes between 20:1 and 4:1 (H:V): Biofilter bags should be placed at a maximum interval of 20 ft, with the first row near the slope toe.
  - Slopes between 4:1 and 2:1 (H:V): Biofilter bags should be placed at a maximum interval of 15 ft, with the first row near the slope toe.
  - Slopes 2:1 (H:V) or steeper: Biofilter bags should be placed at a maximum interval of 10 ft., with the first row placed the slope toe.

- Turn the ends of the biofilter bag barriers up slope to prevent runoff from going around the berm.
- Allow sufficient space up slope from the biofilter bag berm to allow ponding, and to provide room for sediment storage.
- Stake biofilter bags into a 1 to 2 in. deep trench with a width equal to the bag.
  - Drive one stake at each end of the bag.
  - Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum length of 24 in.
- Biofilter bags should be overlapped (6 in.), not abutted.

#### Costs

Pre-filled biofilter bags cost approximately \$2.50-\$3.50 per bag, dependent upon size.

## **Inspection and Maintenance**


- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Biofilter bags exposed to sunlight will need to be replaced every two to three months due to degrading of the bags.
- Reshape or replace biofilter bags as needed.
- Repair washouts or other damage as needed.
- Sediment that is retained by the BMP should be periodically removed in order to maintain BMP effectiveness. Sediment should be removed when the sediment accumulation reaches one-third of the barrier height.
- Remove biofilter bag berms when no longer needed. Remove sediment accumulation and clean, re-grade, and stabilize the area. Biofilter media may be used on-site, if allowed.

#### References

Catalog of Stormwater Best Management Practices for Idaho Cities and Counties. Volume 2, Section 7, BMP 34 – Biofilter Bags, Idaho Department of Environmental Quality, 2005.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.



# **Description and Purpose**

Wind erosion or dust control consists of applying water or other chemical dust suppressants as necessary to prevent or alleviate dust nuisance generated by construction activities. Covering small stockpiles or areas is an alternative to applying water or other dust palliatives.

California's Mediterranean climate, with a short "wet" season and a typically long, hot "dry" season, allows the soils to thoroughly dry out. During the dry season, construction activities are at their peak, and disturbed and exposed areas are increasingly subject to wind erosion, sediment tracking and dust generated by construction equipment. Site conditions and climate can make dust control more of an erosion problem than water based erosion. Additionally, many local agencies, including Air Quality Management Districts, require dust control and/or dust control permits in order to comply with local nuisance laws, opacity laws (visibility impairment) and the requirements of the Clean Air Act. Wind erosion control is required to be implemented at all construction sites greater than 1 acre by the General Permit.

# **Suitable Applications**

Most BMPs that provide protection against water-based erosion will also protect against wind-based erosion and dust control requirements required by other agencies will generally meet wind erosion control requirements for water quality protection. Wind erosion control BMPs are suitable during the following construction activities:

| Categories |   |      |  |  |
|------------|---|------|--|--|
| EC         | Erosion Control                                     |      |  |  |
| SE         | Sediment Control                                    | X    |  |  |
| TC         | Tracking Control                                    |      |  |  |
| WE         | Wind Erosion Control                                | abla |  |  |
| NS         | Non-Stormwater<br>Management Control                |      |  |  |
| WM         | Waste Management and<br>Materials Pollution Control |      |  |  |

#### Legend:

- ☑ Primary Category
- **☒** Secondary Category

# **Targeted Constituents**

Ø

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### **Potential Alternatives**

EC-5 Soll Binders



- Construction vehicle traffic on unpaved roads
- Drilling and blasting activities
- Soils and debris storage piles
- Batch drop from front-end loaders
- Areas with unstabilized soil
- Final grading/site stabilization

#### Limitations

- Watering prevents dust only for a short period (generally less than a few hours) and should be applied daily (or more often) to be effective.
- Over watering may cause erosion and track-out.
- Oil or oil-treated subgrade should not be used for dust control because the oil may migrate into drainageways and/or seep into the soil.
- Chemical dust suppression agents may have potential environmental impacts. Selected chemical dust control agents should be environmentally benign.
- Effectiveness of controls depends on soil, temperature, humidity, wind velocity and traffic.
- Chemical dust suppression agents should not be used within 100 feet of wetlands or water bodies.
- Chemically treated subgrades may make the soil water repellant, interfering with long-term infiltration and the vegetation/re-vegetation of the site. Some chemical dust suppressants may be subject to freezing and may contain solvents and should be handled properly.
- In compacted areas, watering and other liquid dust control measures may wash sediment or other constituents into the drainage system.
- If the soil surface has minimal natural moisture, the affected area may need to be pre-wetted so that chemical dust control agents can uniformly penetrate the soil surface.

# **Implementation**

#### **Dust Control Practices**

Dust control BMPs generally stabilize exposed surfaces and minimize activities that suspend or track dust particles. The following table presents dust control practices that can be applied to varying site conditions that could potentially cause dust. For heavily traveled and disturbed areas, wet suppression (watering), chemical dust suppression, gravel asphalt surfacing, temporary gravel construction entrances, equipment wash-out areas, and haul truck covers can be employed as dust control applications. Permanent or temporary vegetation and mulching can be employed for areas of occasional or no construction traffic. Preventive measures include minimizing surface areas to be disturbed, limiting onsite vehicle traffic to 15 mph or less, and controlling the number and activity of vehicles on a site at any given time.

Chemical dust suppressants include: mulch and fiber based dust palliatives (e.g. paper mulch with gypsum binder), salts and brines (e.g. calcium chloride, magnesium chloride), non-petroleum based organics (e.g. vegetable oil, lignosulfonate), petroleum based organics (e.g. asphalt emulsion, dust oils, petroleum resins), synthetic polymers (e.g. polyvinyl acetate, vinyls, acrylic), clay additives (e.g. bentonite, montimorillonite) and electrochemical products (e.g. enzymes, ionic products).

|   |                         |          | 000000000000000000000000000000000000000 | Dust Con                        | trol Practic            |  | 50/4/5/6/91-        |  |
|---|-------------------------|----------|---|---------------------------------|-------------------------|--|---------------------|--|
| Site<br>Condition                               | Permanent<br>Vegetation | Mulching | Wet<br>Suppression<br>(Watering)        | Chemical<br>Dust<br>Suppression | Gravel<br>or<br>Asphalt | Temporary Gravel<br>Construction<br>Entrances/Equipment,<br>Wasii Down | Synthetic<br>Covers | Minimize<br>Extent of<br>Disturbed<br>Area |
| Disturbed<br>Areas not<br>Subject to<br>Traffic | х                       | х        | х                                       | х                               | х                       |  |                     | х  |
| Disturbed<br>Areas<br>Subject to                |                         |          | х                                       | х                               | х                       | х  |                     | х  |
| Traffic<br>Material<br>Stockpiles               |                         | х        | x                                       | х                               |                         |  | х                   | х  |
| Pemplition                                      |                         |          | х                                       |                                 |                         | х  | х                   |  |
| e Clearing/<br>Exervation                       |                         |          | x                                       | x in                            |                         |  |                     | х  |
| Truck<br>Traffic on<br>Unpayed<br>Roads         |                         |          | х                                       | x                               | х                       | х  | x                   |  |
| Tracking  |                         |          |   |                                 | х                       | х  |                     | <u> </u>                                   |

#### Additional preventive measures include:

- Schedule construction activities to minimize exposed area (see EC-1, Scheduling).
- Quickly treat exposed soils using water, mulching, chemical dust suppressants, or stone/gravel layering.
- Identify and stabilize key access points prior to commencement of construction.
- Minimize the impact of dust by anticipating the direction of prevailing winds.
- Restrict construction traffic to stabilized roadways within the project site, as practicable.
- Water should be applied by means of pressure-type distributors or pipelines equipped with a spray system or hoses and nozzles that will ensure even distribution.
- All distribution equipment should be equipped with a positive means of shutoff.
- Unless water is applied by means of pipelines, at least one mobile unit should be available at all times to apply water or dust palliative to the project.
- If reclaimed waste water is used, the sources and discharge must meet California
   Department of Health Services water reclamation criteria and the Regional Water Quality

Control Board (RWQCB) requirements. Non-potable water should not be conveyed in tanks or drain pipes that will be used to convey potable water and there should be no connection between potable and non-potable supplies. Non-potable tanks, pipes, and other conveyances should be marked, "NON-POTABLE WATER - DO NOT DRINK."

- Pave or chemically stabilize access points where unpaved traffic surfaces adjoin paved roads.
- Provide covers for haul trucks transporting materials that contribute to dust.
- Provide for rapid clean up of sediments deposited on paved roads. Furnish stabilized construction road entrances and wheel wash areas.
- Stabilize inactive areas of construction sites using temporary vegetation or chemical stabilization methods.

For chemical stabilization, there are many products available for chemically stabilizing gravel roadways and stockpiles. If chemical stabilization is used, the chemicals should not create any adverse effects on stormwater, plant life, or groundwater and should meet all applicable regulatory requirements.

#### Costs

Installation costs for water and chemical dust suppression vary based on the method used and the length of effectiveness. Annual costs may be high since some of these measures are effective for only a few hours to a few days.

# **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Check areas protected to ensure coverage.
- Most water-based dust control measures require frequent application, often daily or even multiple times per day. Obtain vendor or independent information on longevity of chemical dust suppressants.

#### References

Best Management Practices and Erosion Control Manual for Construction Sites, Flood Control District of Maricopa County, Arizona, September 1992.


California Air Pollution Control Laws, California Air Resources Board, updated annually.

Construction Manual, Chapter 4, Section 10, "Dust Control"; Section 17, "Watering"; and Section 18, "Dust Palliative", California Department of Transportation (Caltrans), July 2001.

# **Wind Erosion Control**

Prospects for Attaining the State Ambient Air Quality Standards for Suspended Particulate Matter (PM10), Visibility Reducing Particles, Sulfates, Lead, and Hydrogen Sulfide, California Air Resources Board, April 1991.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.



| Description | and Purpose |
|-------------|-------------|
|-------------|-------------|

A stabilized construction access is defined by a point of entrance/exit to a construction site that is stabilized to reduce the tracking of mud and dirt onto public roads by construction vehicles.

# **Suitable Applications**

Use at construction sites:

- Where dirt or mud can be tracked onto public roads.
- Adjacent to water bodies.
- Where poor soils are encountered.
- Where dust is a problem during dry weather conditions.

#### Limitations

- Entrances and exits require periodic top dressing with additional stones.
- This BMP should be used in conjunction with street sweeping on adjacent public right of way.
- Entrances and exits should be constructed on level ground only.
- Stabilized construction entrances are rather expensive to construct and when a wash rack is included, a sediment trap of some kind must also be provided to collect wash water

# EC Erosion Control SE Sediment Control TC Tracking Control WE Wind Erosion Control NS Non-Stormwater Management Control Waste Management and

Materials Pollution Control

#### Legend:

- ☑ Primary Objective
- **☒** Secondary Objective

# **Targeted Constituents**

Sedlment Nutrients

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

## **Potential Alternatives**

None



runoff.

# **Implementation**

#### General

A stabilized construction entrance is a pad of aggregate underlain with filter cloth located at any point where traffic will be entering or leaving a construction site to or from a public right of way, street, alley, sidewalk, or parking area. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking of sediment onto public rights of way or streets. Reducing tracking of sediments and other pollutants onto paved roads helps prevent deposition of sediments into local storm drains and production of airborne dust.

Where traffic will be entering or leaving the construction site, a stabilized construction entrance should be used. NPDES permits require that appropriate measures be implemented to prevent tracking of sediments onto paved roadways, where a significant source of sediments is derived from mud and dirt carried out from unpaved roads and construction sites.

Stabilized construction entrances are moderately effective in removing sediment from equipment leaving a construction site. The entrance should be built on level ground. Advantages of the Stabilized Construction Entrance/Exit is that it does remove some sediment from equipment and serves to channel construction traffic in and out of the site at specified locations. Efficiency is greatly increased when a washing rack is included as part of a stabilized construction entrance/exit.

## Design and Layout

- Construct on level ground where possible.
- Select 3 to 6 in. diameter stones.
- Use minimum depth of stones of 12 in. or as recommended by soils engineer.
- Construct length of 50 ft minimum, and 30 ft minimum width.
- Rumble racks constructed of steel panels with ridges and installed in the stabilized entrance/exit will help remove additional sediment and to keep adjacent streets clean.
- Provide ample turning radii as part of the entrance.
- Limit the points of entrance/exit to the construction site.
- Limit speed of vehicles to control dust.
- Properly grade each construction entrance/exit to prevent runoff from leaving the construction site.
- Route runoff from stabilized entrances/exits through a sediment trapping device before discharge.
- Design stabilized entrance/exit to support heaviest vehicles and equipment that will use it.

- Select construction access stabilization (aggregate, asphaltic concrete, concrete) based on longevity, required performance, and site conditions. Do not use asphalt concrete (AC) grindings for stabilized construction access/roadway.
- If aggregate is selected, place crushed aggregate over geotextile fabric to at least 12 in. depth, or place aggregate to a depth recommended by a geotechnical engineer. A crushed aggregate greater than 3 in. but smaller than 6 in. should be used.
- Designate combination or single purpose entrances and exits to the construction site.
- Require that all employees, subcontractors, and suppliers utilize the stabilized construction access.
- Implement SE-7, Street Sweeping and Vacuuming, as needed.
- All exit locations intended to be used for more than a two-week period should have stabilized construction entrance/exit BMPs.

# **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMPs are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect local roads adjacent to the site daily. Sweep or vacuum to remove visible accumulated sediment.
- Remove aggregate, separate and dispose of sediment if construction entrance/exit is clogged with sediment.
- Keep all temporary roadway ditches clear.
- Check for damage and repair as needed.
- Replace gravel material when surface voids are visible.
- Remove all sediment deposited on paved roadways within 24 hours.
- Remove gravel and filter fabric at completion of construction

#### Costs

Average annual cost for installation and maintenance may vary from \$1,200 to \$4,800 each, averaging \$2,400 per entrance. Costs will increase with addition of washing rack, and sediment trap. With wash rack, costs range from \$1,200 - \$6,000 each, averaging \$3,600 per entrance.

## References

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

National Management Measures to Control Nonpoint Source Pollution from Urban Areas, USEPA Agency, 2002.

Proposed Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, Work Group Working Paper, USEPA, April 1992.


Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.


Virginia Erosion and Sedimentation Control Handbook, Virginia Department of Conservation and Recreation, Division of Soil and Water Conservation, 1991.


Guidance Specifying Management Measures for Nonpoint Pollution in Coastal Waters, EPA 840-B-9-002, USEPA, Office of Water, Washington, DC, 1993.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.




# SECTION B-B







# SECTION B-B



## SECTION A-A NOT TO SCALE





|        |       |     | _   |      |
|--------|-------|-----|-----|------|
| Descri | ption | and | Pur | pose |

Access roads, subdivision roads, parking areas, and other onsite vehicle transportation routes should be stabilized immediately after grading, and frequently maintained to prevent erosion and control dust.

# **Suitable Applications**

This BMP should be applied for the following conditions:

- Temporary Construction Traffic:
  - Phased construction projects and offsite road access
  - Construction during wet weather
- Construction roadways and detour roads:
  - Where mud tracking is a problem during wet weather
  - Where dust is a problem during dry weather.
  - Adjacent to water bodies
  - Where poor soils are encountered

#### Limitations

- The roadway must be removed or paved when construction is complete.
- Certain chemical stabilization methods may cause stormwater or soil pollution and should not be used. See WE-1, Wind Erosion Control.

## Categories

| EÇ | Erosion Control                      | ×    |
|----|--------------------------------------|------|
| SE | Sediment Control                     | X    |
| TC | Tracking Control                     | abla |
| WE | Wind Erosion Control                 |      |
| NS | Non-Stormwater<br>Management Control |      |

Waste Management and Materials Pollution Control

# Legend:

- ☑ Primary Objective
- **☒** Secondary Objective

# **Targeted Constituents**

| raigeted constituen |            |
|---------------------|------------|
| Sediment            | Į <b>⊘</b> |
| Nutrients           |            |
| Trash               |            |
| Metals              |            |
| Bacteria            |            |
| Oil and Grease      |            |
| Organics            |            |

## **Potential Alternatives**

None



- Management of construction traffic is subject to air quality control measures. Contact the local air quality management agency.
- Materials will likely need to be removed prior to final project grading and stabilization.
- Use of this BMP may not be applicable to very short duration projects.

# **Implementation**

#### General

Areas that are graded for construction vehicle transport and parking purposes are especially susceptible to erosion and dust. The exposed soil surface is continually disturbed, leaving no opportunity for vegetative stabilization. Such areas also tend to collect and transport runoff waters along their surfaces. During wet weather, they often become muddy quagmires that generate significant quantities of sediment that may pollute nearby streams or be transported offsite on the wheels of construction vehicles. Dirt roads can become so unstable during wet weather that they are virtually unusable.

Efficient construction road stabilization not only reduces onsite erosion but also can significantly speed onsite work, avoid instances of immobilized machinery and delivery vehicles, and generally improve site efficiency and working conditions during adverse weather

# Installation/Application Criteria

Permanent roads and parking areas should be paved as soon as possible after grading. As an alternative where construction will be phased, the early application of gravel or chemical stabilization may solve potential erosion and stability problems. Temporary gravel roadway should be considered during the rainy season and on slopes greater than 5%.

Temporary roads should follow the contour of the natural terrain to the maximum extent possible. Slope should not exceed 15%. Roadways should be carefully graded to drain transversely. Provide drainage swales on each side of the roadway in the case of a crowned section or one side in the case of a super elevated section. Simple gravel berms without a trench can also be used.

Installed inlets should be protected to prevent sediment laden water from entering the storm sewer system (SE-10, Storm Drain Inlet Protection). In addition, the following criteria should be considered.

- Road should follow topographic contours to reduce erosion of the roadway.
- The roadway slope should not exceed 15%.
- Chemical stabilizers or water are usually required on gravel or dirt roads to prevent dust (WE-1, Wind Erosion Control).
- Properly grade roadway to prevent runoff from leaving the construction site.
- Design stabilized access to support heaviest vehicles and equipment that will use it.

# Stabilized Construction Roadway TC-2

- Stabilize roadway using aggregate, asphalt concrete, or concrete based on longevity, required performance, and site conditions. The use of cold mix asphalt or asphalt concrete (AC) grindings for stabilized construction roadway is not allowed.
- Coordinate materials with those used for stabilized construction entrance/exit points.
- If aggregate is selected, place crushed aggregate over geotextile fabric to at least 12 in. depth. A crushed aggregate greater than 3 in. but smaller than 6 in. should be used.

## **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, impact weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Keep all temporary roadway ditches clear.
- When no longer required, remove stabilized construction roadway and re-grade and repair slopes.
- Periodically apply additional aggregate on gravel roads.
- Active dirt construction roads are commonly watered three or more times per day during the dry season.

#### Costs

Gravel construction roads are moderately expensive, but cost is often balanced by reductions in construction delay. No additional costs for dust control on construction roads should be required above that needed to meet local air quality requirements.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Coastal Nonpoint Pollution Control Program; Program Development and Approval Guidance, Working Group, Working Paper; USEPA, April 1992.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.

Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

Stormwater Management of the Puget Sound Basin, Technical Manual, Publication #91-75, Washington State Department of Ecology, February 1992.


# **Stabilized Construction Roadway** TC-2

Virginia Erosion and Sedimentation Control Handbook, Virginia Department of Conservation and Recreation, Division of Soil and Water Conservation, 1991.

Water Quality Management Plan for the Lake Tahoe Region, Volume II, Handbook of Management Practices, Tahoe Regional Planning Agency, November 1988.

X

M



### **Description and Purpose**

A tire wash is an area located at stabilized construction access points to remove sediment from tires and under carriages and to prevent sediment from being transported onto public roadways.

### **Suitable Applications**

Tire washes may be used on construction sites where dirt and mud tracking onto public roads by construction vehicles may occur.

### Limitations

- The tire wash requires a supply of wash water.
- A turnout or doublewide exit is required to avoid having entering vehicles drive through the wash area.
- Do not use where wet tire trucks leaving the site leave the road dangerously slick.

### **Implementation**

- Incorporate with a stabilized construction entrance/exit.
   See TC-1, Stabilized Construction Entrance/Exit.
- Construct on level ground when possible, on a pad of coarse aggregate greater than 3 in. but smaller than 6 in. A geotextile fabric should be placed below the aggregate.
- Wash rack should be designed and constructed/manufactured for anticipated traffic loads.

### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater
Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

- ☑ Primary Objective
- ▼ Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

### **Potential Alternatives**

TC-1 Stabilized Construction Entrance/Exit



- Provide a drainage ditch that will convey the runoff from the wash area to a sediment trapping device. The drainage ditch should be of sufficient grade, width, and depth to carry the wash runoff.
- Use hoses with automatic shutoff nozzles to prevent hoses from being left on.
- Require that all employees, subcontractors, and others that leave the site with mud caked tires and undercarriages to use the wash facility.
- Implement SC-7, Street Sweeping and Vacuuming, as needed.

#### Costs

Costs are low for installation of wash rack.

### **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.
- Remove accumulated sediment in wash rack and/or sediment trap to maintain system performance.
- Inspect routinely for damage and repair as needed.

### References


Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Coastal Nonpoint Pollution Control Program; Program Development and Approval Guidance, Working Group, Working Paper; USEPA, April 1992.

Manual of Standards of Erosion and Sediment Control Measures, Association of Bay Area Governments, May 1995.


Stormwater Quality Handbooks Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



SECTION A-A NOT TO SCALE

SECTION B-B



NOT TO SCALE



### Categories

| EC | Erosion Control  | X |
|----|------------------|---|
| SE | Sediment Control | × |

SE Sediment Control
TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

- ☑ Primary Objective
- **☒** Secondary Objective

### **Description and Purpose**

Water conservation practices are activities that use water during the construction of a project in a manner that avoids causing erosion and the transport of pollutants offsite. These practices can reduce or eliminate non-stormwater discharges.

### **Suitable Applications**

Water conservation practices are suitable for all construction sites where water is used, including piped water, metered water, trucked water, and water from a reservoir.

#### Limitations

None identified.

### **Implementation**

- Keep water equipment in good working condition.
- Stabilize water truck filling area.
- Repair water leaks promptly.
- Washing of vehicles and equipment on the construction site is discouraged.
- Avoid using water to clean construction areas. If water must be used for cleaning or surface preparation, surface should be swept and vacuumed first to remove dirt. This will minimize amount of water required.
- Direct construction water runoff to areas where it can soak

### **Targeted Constituents**

Sediment

Nutrients Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



into the ground or be collected and reused.

- Authorized non-stormwater discharges to the storm drain system, channels, or receiving waters are acceptable with the implementation of appropriate BMPs.
- Lock water tank valves to prevent unauthorized use.

#### Costs


The cost is small to none compared to the benefits of conserving water.

### **Inspection and Maintenance**

- Inspect and verify that activity based BMPs are in place prior to the commencement of authorized non-stormwater discharges.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges are occuring.
- Repair water equipment as needed to prevent unintended discharges.
  - Water trucks
  - Water reservoirs (water buffalos)
  - Irrigation systems
  - Hydrant connections

### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.



| Categories |   |   |  |
|------------|---|---|--|
| EC         | Erosion Control                                     |   |  |
| SE         | Sediment Control                                    | × |  |
| TC         | Tracking Control                                    |   |  |
| WE         | Wind Erosion Control                                |   |  |
| NS         | Non-Stormwater<br>Management Control                | V |  |
| WM         | Waste Management and<br>Materials Pollution Control |   |  |
| Lege       | end:  |   |  |

☑ Primary Category

**Description and Purpose** 

Dewatering operations are practices that manage the discharge of pollutants when non-stormwater and accumulated precipitation (stormwater) must be removed from a work location to proceed with construction work or to provide vector control.

The General Permit incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for turbidity (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements).

Discharges from dewatering operations can contain high levels of fine sediment that, if not properly treated, could lead to exceedences of the General Permit requirements.

### Suitable Applications

These practices are implemented for discharges of nonstormwater from construction sites. Non-stormwaters include, but are not limited to, groundwater, water from cofferdams, water diversions, and waters used during construction activities that must be removed from a work area to facilitate construction.

Practices identified in this section are also appropriate for implementation when managing the removal of accumulated precipitation (stormwater) from depressed areas at a construction site.

Stormwater mixed with non-stormwater should be managed as non-stormwater.

### **Targeted Constituents**

**Secondary Category** 

| Sediment       |           |
|----------------|-----------|
| Nutrients      |           |
| Trash          |           |
| Metals         |           |
| Bacteria       |           |
| Oil and Grease | $\square$ |
| Organics       |           |
|                |           |

#### **Potential Alternatives**

SE-5: Fiber Roll SE-6: Gravel Bag Berm



## **Dewatering Operations**

#### Limitations

- Dewatering operations will require, and should comply with applicable local and projectspecific permits and regulations. In some areas, all dewatering activities, regardless of the discharge volume, require a dewatering permit.
- Site conditions will dictate design and use of dewatering operations.
- The controls discussed in this fact sheet primarily address sediment. Other secondary pollutant removal benefits are discussed where applicable.
- The controls detailed in this fact sheet only allow for minimal settling time for sediment particles. Use only when site conditions restrict the use of the other control methods.
- Avoid dewatering discharges where possible by using the water for dust control.

### **Implementation**

- A Construction Site Monitoring Plan (CSMP) should be included in the project Stormwater Pollution Prevention Plan (SWPPP).
- Regional Water Quality Control Board (RWQCB) Regions may require notification and approval prior to any discharge of water from construction sites.
- The destination of discharge from dewatering activities will typically determine the type of permit required by the discharger. For example, when discharging to a water of the U.S., a groundwater extraction permit will be required through the site's governing RWQCB. When discharging to a sanitary sewer or Municipal Separate Storm Sewer System (MS4), a permit may need to be obtained through the owner of the sanitary sewer or MS4 in addition to obtaining an RWQCB dewatering permit. Additional permits or permissions from other agencies may be required for dewatering cofferdams or diversions.
- Dewatering discharges should not cause erosion at the discharge point. Appropriate BMPs should be implemented to maintain compliance with all applicable permits.
- Maintain dewatering records in accordance with all local and project-specific permits and regulations.

### Sediment Treatment

A variety of methods can be used to treat water during dewatering operations. Several devices are presented below and provide options to achieve sediment removal. The sediment particle size and permit or receiving water limitations on sediment are key considerations for selecting sediment treatment option(s); in some cases, the use of multiple devices may be appropriate. Use of other enhanced treatment methods (i.e., introduction of chemicals or electric current to enhance flocculation and removal of sediment) must comply with: 1) for storm drain or surface water discharges, the requirements for Active Treatment Systems (SE-11); or 2) for sanitary sewer discharge, the requirements of applicable sanitary sewer discharge permits.

#### Sediment Basin (see also SE-2)

### Description:

A sediment basin is a temporary basin with a controlled release structure that is formed by excavation or construction of an embankment to detain sediment-laden runoff and allow sediment to settle out before discharging. Sediment basins are generally larger than Sediment Traps (SE-3) and have a designed outlet structure.

### Appropriate Applications:

■ Effective for the removal of trash, gravel, sand, silt, some metals that settle out with the sediment.

### Implementation:

- Excavation and construction of related facilities is required.
- Temporary sediment basins should be fenced if safety is a concern.
- Outlet protection is required to prevent erosion at the outfall location.

#### Maintenance:

- Maintenance is required for safety fencing, vegetation, embankment, inlet and outlet, as well as other features.
- Removal of sediment is required when the storage volume is reduced by one-third.

### Sediment Trap (See also SE-3)

### Description:

■ A sediment trap is a temporary basin formed by excavation and/or construction of an earthen embankment across a waterway or low drainage area to detain sediment-laden runoff and allow sediment to settle out before discharging. Sediment traps are generally smaller than Sediment Basins (SE-2) and do not have a designed outlet (but do have a spillway or overflow).

### Appropriate Applications:


Effective for the removal of large and medium sized particles (sand and gravel) and some metals that settle out with the sediment.

### Implementation:

- Excavation and construction of related facilities is required.
- Trap inlets should be located to maximize the travel distance to the trap outlet.
- Use rock or vegetation to protect the trap outlets against erosion.

- Maintenance is required for vegetation, embankment, inlet and outfall structures, as well as other features.
- Removal of sediment is required when the storage volume is reduced by one-third.

#### Weir Tanks



### Description:

• A weir tank separates water and waste by using weirs. The configuration of the weirs (over and under weirs) maximizes the residence time in the tank and determines the waste to be removed from the water, such as oil, grease, and sediments.

### Appropriate Applications:


■ The tank removes trash, some settleable solids (gravel, sand, and silt), some visible oil and grease, and some metals (removed with sediment). To achieve high levels of flow, multiple tanks can be used in parallel. If additional treatment is desired, the tanks can be placed in series or as pre-treatment for other methods.

### Implementation:

- Tanks are delivered to the site by the vendor, who can provide assistance with set-up and operation.
- Tank size will depend on flow volume, constituents of concern, and residency period required. Vendors should be consulted to appropriately size tank.
- Treatment capacity (i.e., volume and number of tanks) should provide at a minimum the required volume for discrete particle settling for treatment design flows.

- Periodic cleaning is required based on visual inspection or reduced flow.
- Oil and grease disposal should be conducted by a licensed waste disposal company.

### **Dewatering Tanks**



### Description:

A dewatering tank removes debris and sediment. Flow enters the tank through the top, passes through a fabric filter, and is discharged through the bottom of the tank. The filter separates the solids from the liquids.

### Appropriate Applications:


The tank removes trash, gravel, sand, and silt, some visible oil and grease, and some metals (removed with sediment). To achieve high levels of flow, multiple tanks can be used in parallel. If additional treatment is desired, the tanks can be placed in series or as pretreatment for other methods.


#### Implementation:

- Tanks are delivered to the site by the vendor, who can provide assistance with set-up and operation.
- Tank size will depend on flow volume, constituents of concern, and residency period required. Vendors should be consulted to appropriately size tank.

- Periodic cleaning is required based on visual inspection or reduced flow.
- Oil and grease disposal should be conducted by licensed waste disposal company.

### **Gravity Bag Filter**





### Description:

A gravity bag filter, also referred to as a dewatering bag, is a square or rectangular bag made of non-woven geotextile fabric that collects gravel, sand, silt, and fines.

### Appropriate Applications:


■ Effective for the removal of sediments (gravel, sand, silt, and fines). Some metals are removed with the sediment.


### Implementation:

- Water is pumped into one side of the bag and seeps through the top, bottom, and sides of the bag.
- Place filter bag on pavement or a gravel bed or paved surface. Avoid placing a dewatering bag on unprotected bare soil. If placing the bag on bare soil is unavoidable, a secondary barrier should be used, such as a rock filter bed placed beneath and beyond the edges of the bag to, prevent erosion and capture sediments that escape the bag.
- Perimeter control around the downstream end of the bag should be implemented. Secondary sediment controls are important especially in the initial stages of discharge, which tend to allow fines to pass through the bag.

- Inspection of the flow conditions, bag condition, bag capacity, and the secondary barrier (as applicable) is required.
- Replace the bag when it no longer filters sediment or passes water at a reasonable rate.
- Caution should be taken when removing and disposing of the bag, to prevent the release of captured sediment
- Properly dispose of the bag offsite. If sediment is removed from the bag prior to disposal (bags can potentially be reused depending upon their condition), dispose of sediment in accordance with the general maintenance procedures described at the end of this BMP Fact Sheet.

#### Sand Media Particulate Filter





### Description:

Water is treated by passing it through canisters filled with sand media. Generally, sand filters provide a final level of treatment. They are often used as a secondary or higher level of treatment after a significant amount of sediment and other pollutants have been removed using other methods.

### Appropriate Applications:


- Effective for the removal of trash, gravel, sand, and silt and some metals, as well as the reduction of biochemical oxygen demand (BOD) and turbidity.
- Sand filters can be used for stand-alone treatment or in conjunction with bag and cartridge filtration if further treatment is required.
- Sand filters can also be used to provide additional treatment to water treated via settling or basic filtration.


#### Implementation:

The filters require delivery to the site and initial set up. The vendor can provide assistance with installation and operation.

- The filters require regular service to monitor and maintain the level of the sand media. If subjected to high loading rates, filters can plug quickly.
- Venders generally provide data on maximum head loss through the filter. The filter should be monitored daily while in use, and cleaned when head loss reaches target levels.
- If cleaned by backwashing, the backwash water may need to be hauled away for disposal, or returned to the upper end of the treatment train for another pass through the series of dewatering BMPs.

### **Pressurized Bag Filter**





### Description:

A pressurized bag filter is a unit composed of single filter bags made from polyester felt material. The water filters through the unit and is discharged through a header. Vendors provide bag filters in a variety of configurations. Some units include a combination of bag filters and cartridge filters for enhanced contaminant removal.

### Appropriate Applications:

- Effective for the removal of sediment (sand and silt) and some metals, as well as the reduction of BOD, turbidity, and hydrocarbons. Oil absorbent bags are available for hydrocarbon removal.
- Filters can be used to provide secondary treatment to water treated via settling or basic filtration.


### *Implementation:*

■ The filters require delivery to the site and initial set up. The vendor can provide assistance with installation and operation.

#### Maintenance:

• The filter bags require replacement when the pressure differential equals or exceeds the manufacturer's recommendation.

### Cartridge Filter



### Description:

Cartridge filters provide a high degree of pollutant removal by utilizing a number of individual cartridges as part of a larger filtering unit. They are often used as a secondary or higher (polishing) level of treatment after a significant amount of sediment and other pollutants are removed. Units come with various cartridge configurations (for use in series with bag filters) or with a larger single cartridge filtration unit (with multiple filters within).

### Appropriate Applications:

- Effective for the removal of sediment (sand, silt, and some clays) and metals, as well as the reduction of BOD, turbidity, and hydrocarbons. Hydrocarbons can effectively be removed with special resin cartridges.
- Filters can be used to provide secondary treatment to water treated via settling or basic filtration.

#### Implementation:

• The filters require delivery to the site and initial set up. The vendor can provide assistance.

#### Maintenance:

 The cartridges require replacement when the pressure differential equals or exceeds the manufacturer's recommendation.

#### Costs

Sediment control costs vary considerably depending on the dewatering and sediment treatment system that is selected. Pressurized filters tend to be more expensive than gravity settling, but are often more effective. Simple tanks are generally rented on a long-term basis (one or more months) and can range from \$360 per month for a 1,000 gallon tank to \$2,660 per month for a 10,000 gallon tank. Mobilization and demobilization costs vary considerably.

### **Inspection and Maintenance**

- Inspect and verify that dewatering BMPs are in place and functioning prior to the commencement of activities requiring dewatering.
- Inspect dewatering BMPs daily while dewatering activities are being conducted.

## **Dewatering Operations**

- Inspect all equipment before use. Monitor dewatering operations to ensure they do not cause offsite discharge or erosion.
- Sample dewatering discharges as required by the General Permit.
- Unit-specific maintenance requirements are included with the description of each unit.
- Sediment removed during the maintenance of a dewatering device may be either spread onsite and stabilized, or disposed of at a disposal site as approved by the owner.
- Sediment that is commingled with other pollutants should be disposed of in accordance with all applicable laws and regulations and as approved by the owner.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003; Updated March 2004.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

Labor Surcharge & Equipment Rental Rates, April 1, 2002 through March 31, 2003, California Department of Transportation (Caltrans).


Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

 $\square$ 

X

 $\square$ 

囨



### **Description and Purpose**

Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent runon and runoff pollution, properly disposing of wastes, and training employees and subcontractors.

The General Permit incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for pH and turbidity (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements).

Many types of construction materials associated with paving and grinding operations, including mortar, concrete, and cement and their associated wastes have basic chemical properties that can raise pH levels outside of the permitted range. Additional care should be taken when managing these materials to prevent them from coming into contact with stormwater flows, which could lead to exceedances of the General Permit requirements.

### **Suitable Applications**

These procedures are implemented where paving, surfacing, resurfacing, or sawcutting, may pollute stormwater runoff or discharge to the storm drain system or watercourses.

#### **Limitations**

- Paving opportunities may be limited during wet weather.
- Discharges of freshly paved surfaces may raise pH to environmentally harmful levels and trigger permit violations.

### Categories

- EC Erosion Control
- SE Sediment Control
- TC Tracking Control
- WE Wind Erosion Control
- Non-Stormwater
  - Management Control
- Waste Management and Materials Pollution Control

### Legend:

- ☑ Primary Category
- Secondary Category

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

**Organics** 

Oil and Grease

...

#### **Potential Alternatives**

None



### **Implementation**

### General

- Avoid paving during the wet season when feasible.
- Reschedule paving and grinding activities if rain is forecasted.
- Train employees and sub-contractors in pollution prevention and reduction.
- Store materials away from drainage courses to prevent stormwater runon (see WM-1, Material Delivery and Storage).
- Protect drainage courses, particularly in areas with a grade, by employing BMPs to divert runoff or to trap and filter sediment.
- Stockpile material removed from roadways away from drain inlets, drainage ditches, and watercourses. These materials should be stored consistent with WM-3, Stockpile Management.
- Disposal of PCC (Portland cement concrete) and AC (asphalt concrete) waste should be in conformance with WM-8, Concrete Waste Management.

### Saw Cutting, Grinding, and Pavement Removal

- Shovel or vacuum saw-cut slurry and remove from site. Cover or barricade storm drains during saw cutting to contain slurry.
- When paving involves AC, the following steps should be implemented to prevent the discharge of grinding residue, uncompacted or loose AC, tack coats, equipment cleaners, or unrelated paving materials:
  - AC grindings, pieces, or chunks used in embankments or shoulder backing should not be allowed to enter any storm drains or watercourses. Install inlet protection and perimeter controls until area is stabilized (i.e. cutting, grinding or other removal activities are complete and loose material has been properly removed and disposed of)or permanent controls are in place. Examples of temporary perimeter controls can be found in EC-9, Earth Dikes and Drainage Swales; SE-1, Silt Fence; SE-5, Fiber Rolls, or SE-13 Compost Socks and Berms
  - Collect and remove all broken asphalt and recycle when practical. Old or spilled asphalt should be recycled or disposed of properly.
- Do not allow saw-cut slurry to enter storm drains or watercourses. Residue from grinding operations should be picked up by a vacuum attachment to the grinding machine, or by sweeping, should not be allowed to flow across the pavement, and should not be left on the surface of the pavement. See also WM-8, Concrete Waste Management, and WM-10, Liquid Waste Management.
- Payement removal activities should not be conducted in the rain.
- Collect removed pavement material by mechanical or manual methods. This material may be recycled for use as shoulder backing or base material.

■ If removed pavement material cannot be recycled, transport the material back to an approved storage site.

### Asphaltic Concrete Paving

- If paving involves asphaltic cement concrete, follow these steps:
  - Do not allow sand or gravel placed over new asphalt to wash into storm drains, streets, or creeks. Vacuum or sweep loose sand and gravel and properly dispose of this waste by referring to WM-5, Solid Waste Management.
  - Old asphalt should be disposed of properly. Collect and remove all broken asphalt from the site and recycle whenever possible.

### Portland Cement Concrete Paving

■ Do not wash sweepings from exposed aggregate concrete into a storm drain system. Collect waste materials by dry methods, such as sweeping or shoveling, and return to aggregate base stockpile or dispose of properly. Allow aggregate rinse to settle. Then, either allow rinse water to dry in a temporary pit as described in WM-8, Concrete Waste Management, or pump the water to the sanitary sewer if authorized by the local wastewater authority.

### **Sealing Operations**

- During chip seal application and sweeping operations, petroleum or petroleum covered
  aggregate should not be allowed to enter any storm drain or water courses. Apply temporary
  perimeter controls until structure is stabilized (i.e. all sealing operations are complete and
  cured and loose materials have been properly removed and disposed).
- Inlet protection (SE-10, Storm Drain Inlet Protection) should be used during application of seal coat, tack coat, slurry seal, and fog seal.
- Seal coat, tack coat, slurry seal, or fog seal should not be applied if rainfall is predicted to occur during the application or curing period.

### Paving Equipment

- Leaks and spills from paving equipment can contain toxic levels of heavy metals and oil and grease. Place drip pans or absorbent materials under paving equipment when not in use. Clean up spills with absorbent materials and dispose of in accordance with the applicable regulations. See NS-10, Vehicle and Equipment Maintenance, WM-4, Spill Prevention and Control, and WM-10, Liquid Waste Management.
- Substances used to coat asphalt transport trucks and asphalt spreading equipment should not contain soap and should be non-foaming and non-toxic.
- Paving equipment parked onsite should be parked over plastic to prevent soil contamination.
- Clean asphalt coated equipment offsite whenever possible. When cleaning dry, hardened asphalt from equipment, manage hardened asphalt debris as described in WM-5, Solid Waste Management. Any cleaning onsite should follow NS-8, Vehicle and Equipment Cleaning.

1.0

### Thermoplastic Striping

- Thermoplastic striper and pre-heater equipment shutoff valves should be inspected to ensure that they are working properly to prevent leaking thermoplastic from entering drain inlets, the stormwater drainage system, or watercourses.
- Pre-heaters should be filled carefully to prevent splashing or spilling of hot thermoplastic. Leave six inches of space at the top of the pre-heater container when filling thermoplastic to allow room for material to move.
- Do not pre-heat, transfer, or load thermoplastic near drain inlets or watercourses.
- Clean truck beds daily of loose debris and melted thermoplastic. When possible, recycle thermoplastic material.

### Raised/Recessed Pavement Marker Application and Removal

- Do not transfer or load bituminous material near drain inlets, the stormwater drainage system, or watercourses.
- Melting tanks should be loaded with care and not filled to beyond six inches from the top to leave room for splashing.
- When servicing or filling melting tanks, ensure all pressure is released before removing lids to avoid spills.
- On large-scale projects, use mechanical or manual methods to collect excess bituminous material from the roadway after removal of markers.

#### Costs

All of the above are low cost measures.

### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of paving and grinding operations.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Sample stormwater runoff required by the General Permit.
- Keep ample supplies of drip pans or absorbent materials onsite.
- Inspect and maintain machinery regularly to minimize leaks and drips.

### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

# **Paving and Grinding Operations**


NS-3

Hot Mix Asphalt-Paving Handbook AC 150/5370-14, Appendix I, U.S. Army Corps of Engineers, July 1991.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.

## **Temporary Stream Crossing**



### **Description and Purpose**

A temporary stream crossing is a temporary culvert, ford or bridge placed across a waterway to provide access for construction purposes for a period of less than one year. Temporary access crossings are not intended to maintain traffic for the public. The temporary access will eliminate erosion and downstream sedimentation caused by vehicles.

### Suitable Applications

Temporary stream crossings should be installed at all designated crossings of perennial and intermittent streams on the construction site, as well as for dry channels that may be significantly eroded by construction traffic.

Temporary streams crossings are installed at sites:

- Where appropriate permits have been secured (404 Permits, and 401 Certifications)
- Where construction equipment or vehicles need to frequently cross a waterway
- When alternate access routes impose significant constraints
- When crossing perennial streams or waterways causes significant erosion
- Where construction activities will not last longer than one year
- Where appropriate permits have been obtained for the

### Categories

| EC | Erosion Control                      | X         |
|----|--------------------------------------|-----------|
| SE | Sediment Control                     | ×         |
| TC | Tracking Control                     | X         |
| WE | Wind Erosion Control                 |           |
| NS | Non-Stormwater<br>Management Control | $\square$ |

WM Waste Management and Materials Pollution Control

#### Legend:

- ☑ Primary Objective
- **☒** Secondary Objective

### **Targeted Constituents**

 $\mathbf{A}$ 

Sediment

Nutrients

Trash Metals

IVICIAIS

Bacteria

Oil and Grease

Organics

### **Potential Alternatives**

None



stream crossing

#### Limitations

The following limitations may apply:

- Installation and removal will usually disturb the waterway.
- Installation may require Regional Water Quality Control Board (RWQCB) 401 Certification, U.S. Army Corps of Engineers 404 permit and approval by California Department of Fish and Game. If numerical-based water quality standards are mentioned in any of these and other related permits, testing and sampling may be required.
- Installation may require dewatering or temporary diversion of the stream. See NS-2, Dewatering Operations and NS-5, Clear Water Diversion.
- Installation may cause a constriction in the waterway, which can obstruct flood flow and cause flow backups or washouts. If improperly designed, flow backups can increase the pollutant load through washouts and scouring.
- Use of natural or other gravel in the stream for construction of Cellular Confinement System (CCS) ford crossing will be contingent upon approval by fisheries agencies.
- Ford crossings may degrade water quality due to contact with vehicles and equipment.
- May be expensive for a temporary improvement.
- Requires other BMPs to minimize soil disturbance during installation and removal.
- Fords should only be used in dry weather.

### **Implementation**

#### General

The purpose of this BMP is to provide a safe, erosion-free access across a stream for construction equipment. Minimum standards and specifications for the design, construction, maintenance, and removal of the structure should be established by an engineer registered in California. Temporary stream crossings may be necessary to prevent construction equipment from causing erosion of the stream and tracking sediment and other pollutants into the stream.

Temporary stream crossings are used as access points to construction sites when other detour routes may be too long or burdensome for the construction equipment. Often heavy construction equipment must cross streams or creeks, and detour routes may impose too many constraints such as being too narrow or poor soil strength for the equipment loadings. Additionally, the contractor may find a temporary stream crossing more economical for light—duty vehicles to use for frequent crossings, and may have less environmental impact than construction of a temporary access road.

Location of the temporary stream crossing should address:

■ Site selection where erosion potential is low.

• Areas where the side slopes from site runoff will not spill into the side slopes of the crossing.

The following types of temporary stream crossings should be considered:

- Culverts A temporary culvert is effective in controlling erosion but will cause erosion during installation and removal. A temporary culvert can be easily constructed and allows for heavy equipment loads.
- Fords Appropriate during the dry season in arid areas. Used on dry washes and ephemeral streams, and low-flow perennial streams. CCS, a type of ford crossing, is also appropriate for use in streams that would benefit from an influx of gravels. A temporary ford provides little sediment and erosion control and is ineffective in controlling erosion in the stream channel. A temporary ford is the least expensive stream crossing and allows for maximum load limits. It also offers very low maintenance. Fords are more appropriate during the dry ice season and in arid areas of California.
- **Bridges** Appropriate for streams with high flow velocities, steep gradients and where temporary restrictions in the channel are not allowed.

#### Design

During the long summer construction season in much of California, rainfall is infrequent and many streams are dry. Under these conditions, a temporary ford may be sufficient. A ford is not appropriate if construction will continue through the winter rainy season, if summer thunderstorms are likely, or if the stream flows during most of the year. Temporary culverts and bridges should then be considered and, if used, should be sized to pass a significant design storm (i.e., at least a 10-year storm). The temporary stream crossing should be protected against erosion, both to prevent excessive sedimentation in the stream and to prevent washout of the crossing.

Design and installation requires knowledge of stream flows and soil strength. Designs should be prepared under direction of, and approved by, a registered civil engineer and for bridges, a registered structural engineer. Both hydraulic and construction loading requirements should be considered with the following:

- Comply with any special requirements for culvert and bridge crossings, particularly if the temporary stream crossing will remain through the rainy season.
- Provide stability in the crossing and adjacent areas to withstand the design flow. The design flow and safety factor should be selected based on careful evaluation of the risks due to over topping, flow backups, or washout.
- Install sediment traps immediately downstream of crossings to capture sediments. See SE-3, Sediment Trap.
- Avoid oil or other potentially hazardous materials for surface treatment.
- Culverts are relatively easy to construct and able to support heavy equipment loads.
- Fords are the least expensive of the crossings, with maximum load limits.

- CCS crossing structures consist of clean, washed gravel and cellular confinement system blocks. CCS are appropriate for streams that would benefit from an influx of gravel; for example, salmonid streams, streams or rivers below reservoirs, and urban, channelized streams. Many urban stream systems are gravel-deprived due to human influences, such as dams, gravel mines, and concrete channels.
- CCS allow designers to use either angular or naturally occurring rounded gravel, because the cells provide the necessary structure and stability. In fact, natural gravel is optimal for this technique, because of the habitat improvement it will provide after removal of the CCS.
- A gravel depth of 6 to 12 in. for a CCS structure is sufficient to support most construction equipment.
- An advantage of a CCS crossing structure is that relatively little rock or gravel is needed, because the CCS provides the stability.
- Bridges are generally more expensive to design and construct, but provide the least disturbance of the streambed and constriction of the waterway flows.

#### Construction and Use

- Stabilize construction roadways, adjacent work area, and stream bottom against erosion.
- Construct during dry periods to minimize stream disturbance and reduce costs.
- Construct at or near the natural elevation of the streambed to prevent potential flooding upstream of the crossing.
- Install temporary erosion control BMPs in accordance with erosion control BMP fact sheets to minimize erosion of embankment into flow lines.
- Any temporary artificial obstruction placed within flowing water should only be built from material, such as clean gravel or sandbags, that will not introduce sediment or silt into the watercourse.
- Temporary water body crossings and encroachments should be constructed to minimize scour. Cobbles used for temporary water body crossings or encroachments should be clean, rounded river cobble.
- Vehicles and equipment should not be driven, operated, fueled, cleaned, maintained, or stored in the wet or dry portions of a water body where wetland vegetation, riparian vegetation, or aquatic organisms may be destroyed.
- The exterior of vehicles and equipment that will encroach on the water body within the project should be maintained free of grease, oil, fuel, and residues.
- Drip pans should be placed under all vehicles and equipment placed on docks, barges, or other structures over water bodies when the vehicle or equipment is planned to be idle for more than one hour.

- Disturbance or removal of vegetation should not exceed the minimum necessary to complete
  operations. Precautions should be taken to avoid damage to vegetation by people or
  equipment. Disturbed vegetation should be replaced with the appropriate soil stabilization
  measures.
- Riparian vegetation, when removed pursuant to the provisions of the work, should be cut off no lower than ground level to promote rapid re-growth. Access roads and work areas built over riparian vegetation should be covered by a sufficient layer of clean river run cobble to prevent damage to the underlying soil and root structure. The cobble must be removed upon completion of project activities.
- Conceptual temporary stream crossings are shown in the attached figures.

#### Costs

Caltrans Construction Cost index for temporary bridge crossings is \$45-\$95/ft².


### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two week intervals in the non-rainy season to verify continued BMP implementation.
- Check for blockage in the channel, sediment buildup or trapped debris in culverts, blockage behind fords or under bridges
- Check for erosion of abutments, channel scour, riprap displacement, or piping in the soil
- Check for structural weakening of the temporary crossings, such as cracks, and undermining of foundations and abutments
- Remove sediment that collects behind fords, in culverts, and under bridges periodically
- Replace lost or displaced aggregate from inlets and outlets of culverts and cellular confinement systems
- Remove temporary crossing promptly when it is no longer needed

#### References


California Bank and Shore Rock Slope Protection Design – Practitioners Guide and Field Evaluations of Riprap Methods, Caltrans Study No. F90TL03, October 2000.


Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.




NOTE: Surface flow of road diverted by swale and/or dike.

TYPICAL BRIDGE CROSSING
NOT TO SCALE






Aggregate approch 1:5 (V:H) Maximum slope on road



 $\square$ 

 $\square$ 

## **Clear Water Diversion**



### **Description and Purpose**

Clear water diversion consists of a system of structures and measures that intercept clear surface water runoff upstream of a project, transport it around the work area, and discharge it downstream with minimal water quality degradation from either the project construction operations or the construction of the diversion. Clear water diversions are used in a waterway to enclose a construction area and reduce sediment pollution from construction work occurring in or adjacent to water. Structures commonly used as part of this system include diversion ditches, berms, dikes, slope drains, rock, gravel bags, wood, aqua barriers, cofferdams, filter fabric or turbidity curtains, drainage and interceptor swales, pipes, or flumes.

### **Suitable Applications**

A clear water diversion is typically implemented where appropriate permits (1601 Agreement) have been secured and work must be performed in a flowing stream or water body.

- Clear water diversions are appropriate for isolating construction activities occurring within or near a water body such as streambank stabilization, or culvert, bridge, pier or abutment installation. They may also be used in combination with other methods, such as clear water bypasses and/or pumps.
- Pumped diversions are suitable for intermittent and low flow streams.
- Excavation of a temporary bypass channel, or passing the

### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

### Legend:

☑ Primary Objective

■ Secondary Objective

### **Targeted Constituents**

Sediment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



flow through a heavy pipe (called a "flume") with a trench excavated under it, is appropriate for the diversion of streams less than 20 ft wide, with flow rates less than 100 cfs.

• Clear water diversions incorporating clean washed gravel may be appropriate for use in salmonid spawning streams.

#### Limitations

- Diversion and encroachment activities will usually disturb the waterway during installation and removal of diversion structures.
- Installation may require Regional Water Quality Control Board (RWQCB) 401 Certification, U.S. Army Corps of Engineers 404 permit and approval by California Department of Fish and Game. If numerical-based water quality standards are mentioned in any of these and other related permits, testing and sampling may be required.
- Diversion and encroachment activities may constrict the waterway, which can obstruct flood flows and cause flooding or washouts. Diversion structures should not be installed without identifying potential impacts to the stream channel.
- Diversion or isolation activities are not appropriate in channels where there is insufficient stream flow to support aquatic species in the area dewatered as a result of the diversion.
- Diversion or isolation activities are inappropriate in deep water unless designed or reviewed by an engineer registered in California.
- Diversion or isolation activities should not completely dam stream flow.
- Dewatering and removal may require additional sediment control or water treatment. See NS-2, Dewatering Operations.
- Not appropriate if installation, maintenance, and removal of the structures will disturb sensitive aquatic species of concern.

### **Implementation**

#### General

- Implement guidelines presented in NS-17, Streambank Stabilization to minimize impacts to streambanks.
- Where working areas encroach on flowing streams, barriers adequate to prevent the flow of muddy water into streams should be constructed and maintained between working areas and streams. During construction of the barriers, muddying of streams should be held to a minimum.
- Diversion structures must be adequately designed to accommodate fluctuations in water depth or flow volume due to tides, storms, flash floods, etc.
- Heavy equipment driven in wet portions of a water body to accomplish work should be completely clean of petroleum residue, and water levels should be below the fuel tanks, gearboxes, and axles of the equipment unless lubricants and fuels are sealed such that inundation by water will not result in discharges of fuels, oils, greases, or hydraulic fluids.

- Excavation equipment buckets may reach out into the water for the purpose of removing or placing fill materials. Only the bucket of the crane/excavator/backhoe may operate in a water body. The main body of the crane/excavator/backhoe should not enter the water body except as necessary to cross the stream to access the work site.
- Stationary equipment such as motors and pumps located within or adjacent to a water body, should be positioned over drip pans.
- When any artificial obstruction is being constructed, maintained, or placed in operation, sufficient water should, at all times, be allowed to pass downstream to maintain aquatic life.
- Equipment should not be parked below the high water mark unless allowed by a permit.
- Disturbance or removal of vegetation should not exceed the minimum necessary to complete operations. Precautions should be taken to avoid damage to vegetation by people or equipment. Disturbed vegetation should be replaced with the appropriate erosion control measures.
- Riparian vegetation approved for trimming as part of the project should be cut off no lower than ground level to promote rapid re-growth. Access roads and work areas built over riparian vegetation should be covered by a sufficient layer of clean river run cobble to prevent damage to the underlying soil and root structure. The cobble should be removed upon completion of project activities.
- Drip pans should be placed under all vehicles and equipment placed on docks, barges, or other structures over water bodies when the vehicle or equipment is planned to be idle for more than 1 hour.
- Where possible, avoid or minimize diversion and encroachment impacts by scheduling construction during periods of low flow or when the stream is dry. Scheduling should also consider seasonal releases of water from dams, fish migration and spawning seasons, and water demands due to crop irrigation.
- Construct diversion structures with materials free of potential pollutants such as soil, silt, sand, clay, grease, or oil.

### Temporary Diversions and Encroachments

- Construct diversion channels in accordance with EC-9, Earth Dikes and Drainage Swales.
- In high flow velocity areas, stabilize slopes of embankments and diversion ditches using an appropriate liner, in accordance with EC-7, Geotextiles and Mats, or use rock slope protection.
- Where appropriate, use natural streambed materials such as large cobbles and boulders for temporary embankment and slope protection, or other temporary soil stabilization methods.
- Provide for velocity dissipation at transitions in the diversion, such as the point where the stream is diverted to the channel and the point where the diverted stream is returned to its natural channel. See also EC-10, Velocity Dissipation Devices.

### Temporary Dry Construction Areas

- When dewatering behind temporary structures to create a temporary dry construction area, such as cofferdams, pass pumped water through a sediment-settling device, such as a portable tank or settling basin, before returning water to the water body. See also NS-2, Dewatering Operations.
- Any substance used to assemble or maintain diversion structures, such as form oil, should be non-toxic and non-hazardous.
- Any material used to minimize seepage underneath diversion structures, such as grout, should be non-toxic, non-hazardous, and as close to a neutral pH as possible.

### Comparison of Diversion and Isolation Techniques:

- Gravel bags are relatively inexpensive, but installation and removal can be labor intensive. It is also difficult to dewater the isolated area. Sandbags should not be used for this technique in rivers or streams, as sand should never be put into or adjacent to a stream, even if encapsulated in geotextile.
- Gravel Bag Berms (SE-6) used in conjunction with an impermeable membrane are cost effective, and can be dewatered relatively easily. If spawning gravel is used, the impermeable membrane can be removed from the stream, and the gravel can be spread out and left as salmonid spawning habitat if approved in the permit. Only clean, washed gravel should be used for both the gravel bag and gravel berm techniques.
- Cofferdams are relatively expensive, but frequently allow full dewatering. Also, many options now available are relatively easy to install.
- Sheet pile enclosures are a much more expensive solution, but do allow full dewatering. This technique is not well suited to small streams, but can be effective on large rivers or lakes, and where staging and heavy equipment access areas are available.
- K-rails are an isolation method that does not allow full dewatering, but can be used in small to large watercourses, and in fast-water situations.
- A relatively inexpensive isolation method is filter fabric isolation. This method involves placement of gravel bags or continuous berms to 'key-in' the fabric, and subsequently staking the fabric in place. This method should be used in relatively calm water, and can be used in smaller streams. Note that this is not a dewatering method, but rather a sediment isolation method.
- Turbidity curtains should be used where sediment discharge to a stream is unavoidable.

  They can also be used for in-stream construction, when dewatering an area is not required.
- When used in watercourses or streams, cofferdams must be used in accordance with permit requirements.
- Manufactured diversion structures should be installed following manufacturer's specifications.

Filter fabric and turbidity curtain isolation installation methods can be found in the specific technique descriptions that follow.

### Filter Fabric Isolation Technique

### Definition and Purpose

A filter fabric isolation structure is a temporary structure built into a waterway to enclose a construction area and reduce sediment pollution from construction work in or adjacent to water. This structure is composed of filter fabric, gravel bags, and steel t-posts.

### Appropriate Applications

- Filter fabric may be used for construction activities such as streambank stabilization, or culvert, bridge, pier or abutment installation. It may also be used in combination with other methods, such as clean water bypasses and/or pumps.
- Filter fabric isolation is relatively inexpensive. This method involves placement of gravel bags or continuous berms to 'key-in' the fabric, and subsequently staking the fabric in place.
- If spawning gravel is used, all other components of the isolation can be removed from the stream, and the gravel may be spread out and left as salmonid spawning habitat if approved in the permit. Whether spawning gravel or other types of gravel are used, only clean washed gravel should be used as infill for the gravel bags or continuous berm.
- This method should be used in relatively calm water, and can be used in smaller streams. This is not a dewatering method, but rather a sediment isolation method.
- Water levels inside and outside the fabric curtain must be about the same, as differential heads will cause the curtain to collapse.

#### Limitations

- Do not use if the installation, maintenance and removal of the structures will disturb sensitive aquatic species of concern.
- Filter fabrics are not appropriate for projects where dewatering is necessary.
- Filter fabrics are not appropriate to completely dam stream flow.

#### Design and Installation

- For the filter fabric isolation method, a non-woven or heavy-duty fabric is recommended over standard silt fence. Using rolled geotextiles allows non-standard widths to be used.
- Anchor filter fabric with gravel bags filled with clean, washed gravel. Do not use sand. If a bag should split open, the gravel can be left in the stream, where it can provide aquatic habitat benefits. If a sandbag splits open in a watercourse, the sand could cause a decrease in water quality, and could bury sensitive aquatic habitat.
- Another anchor alternative is a continuous berm, made with the Continuous Berm Machine. This is a gravel-filled bag that can be made in very long segments. The length of the berms is usually limited to 18 ft for ease of handling (otherwise, it gets too heavy to move).

- Place the fabric on the bottom of the stream, and place either a bag of clean, washed gravel or a continuous berm over the bottom of the silt fence fabric, such that a bag-width of fabric lies on the stream bottom. The bag should be placed on what will be the outside of the isolation area.
- Pull the fabric up, and place a metal t-post immediately behind the fabric, on the inside of the isolation area; attach the silt fence to the post with three diagonal nylon ties.
- Continue placing fabric as described above until the entire work area has been isolated, staking the fabric at least every 6 ft.

### Inspection and Maintenance

- Immediately repair any gaps, holes or scour.
- Remove and properly dispose of sediment buildup.
- Remove BMP upon completion of construction activity. Recycle or reuse if applicable.
- Revegetate areas disturbed by BMP removal if needed.

### Turbidity Curtain Isolation Technique

### Definition and Purpose

A turbidity curtain is a fabric barrier used to isolate the near shore work area. The barriers are intended to confine the suspended sediment. The curtain is a floating barrier, and thus does not prevent water from entering the isolated area; rather, it prevents suspended sediment from getting out.

#### Appropriate Applications

Turbidity curtains should be used where sediment discharge to a stream is unavoidable. They are used when construction activities adjoin quiescent waters, such as lakes, ponds, and slow flowing rivers. The curtains are designed to deflect and contain sediment within a limited area and provide sufficient retention time so that the sediment particles will fall out of suspension.

#### Limitations

- Turbidity curtains should not be used in flowing water; they are best suited for use in ponds, lakes, and very slow-moving rivers.
- Turbidity curtains should not be placed across the width of a channel.
- Removing sediment that has been deflected and settled out by the curtain may create a discharge problem through the resuspension of particles and by accidental dumping by the removal equipment.

### Design and Installation

- Turbidity curtains should be oriented parallel to the direction of flow.
- The curtain should extend the entire depth of the watercourse in calm-water situations.
- In wave conditions, the curtain should extend to within 1 ft of the bottom of the watercourse, such that the curtain does not stir up sediment by hitting the bottom repeatedly. If it is

desirable for the curtain to reach the bottom in an active-water situation, a pervious filter fabric may be used for the bottom 1 ft.

- The top of the curtain should consist of flexible flotation buoys, and the bottom should be held down by a load line incorporated into the curtain fabric. The fabric should be a brightly colored impervious mesh.
- The curtain should be held in place by anchors placed at least every 100 ft.
- First, place the anchors, then tow the fabric out in a furled condition, and connect to the anchors. The anchors should be connected to the flotation devices, and not to the bottom of the curtain. Once in place, cut the furling lines, and allow the bottom of the curtain to sink.
- Consideration must be given to the probable outcome of the removal procedure. It must be determined if it will create more of a sediment problem through re-suspension of the particles or by accidental dumping of material during removal. It is recommended that the soil particles trapped by the turbidity curtain only be removed if there has been a significant change in the original contours of the affected area in the watercourse.
- Particles should always be allowed to settle for a minimum of 6 to 12 hours prior to their removal or prior to removal of the turbidity curtain.

### Maintenance and Inspection:

- The curtain should be inspected for holes or other problems, and any repairs needed should be made promptly.
- Allow sediment to settle for 6 to 12 hours prior to removal of sediment or curtain. This means that after removing sediment, wait an additional 6 to 12 hours before removing the curtain.
- To remove, install furling lines along the curtain, detach from anchors, and tow out of the water.

#### K-rail River Isolation

### Definition and Purpose

This temporary sediment control or stream isolation method uses K-rails to form the sediment deposition area, or to isolate the in-stream or near-bank construction area.

Barriers are placed end-to-end in a pre-designed configuration and gravel-filled bags are used at the toe of the barrier and at their abutting ends to seal and prevent movement of sediment beneath or through the barrier walls.

### Appropriate Applications

The K-rail isolation can be used in streams with higher water velocities than many other isolation techniques.

• This technique is also useful at the toe of embankments, and cut or fill slopes.

#### Limitations

■ The K-rail method should not be used to dewater a project site, as the barrier is not watertight.

#### Design and Installation

- To create a floor for the K-rail, move large rocks and obstructions. Place washed gravel and gravel-filled bags to create a level surface for K-rails to sit. Washed gravel should always be used.
- Place the bottom two K-rails adjacent to each other, and parallel to the direction of flow; fill the center portion with gravel bags. Then place the third K-rail on top of the bottom two. There should be sufficient gravel bags between the bottom K-rails such that the top rail is supported by the gravel. Place plastic sheeting around the K-rails, and secure at the bottom with gravel bags.
- Further support can be added by pinning and cabling the K-rails together. Also, large riprap and boulders can be used to support either side of the K-rail, especially where there is strong current.

## Inspection and Maintenance:

- The barrier should be inspected and any leaks; holes, or other problems should be addressed immediately.
- Sediment should be allowed to settle for at least 6 to 12 hours prior to removal of sediment, and for 6 to 12 hours prior to removal of the barrier.

#### Stream Diversions

The selection of which stream diversion technique to use will depend upon the type of work involved, physical characteristics of the site, and the volume of water flowing through the project.

#### Advantages of a Pumped Diversion

- Downstream sediment transport can be nearly eliminated.
- Dewatering of the work area is possible.
- Pipes can be moved around to allow construction operations.
- The dams can serve as temporary access to the site.
- Increased flows can be managed by adding more pumping capacity.

### Disadvantages of a Pumped Diversion

- Flow volume is limited by pump capacity.
- A pumped diversion requires 24 hour monitoring of pumps.
- Sudden rain could overtop dams.
- Erosion at the outlet.

Minor in-stream disturbance is required to install and remove dams.

### Advantages of Excavated Channels and Flumes

- Excavated channels isolate work from water flow and allow dewatering.
- Excavated channels can handle larger flows than pumps.

#### Disadvantages of Excavated Channels and Flumes

- Bypass channel or flume must be sized to handle flows, including possible floods.
- Channels must be protected from erosion.
- Flow diversion and re-direction with small dams involves in-stream disturbance and mobilization of sediment.

#### Design and Installation

- Installation guidelines will vary based on existing site conditions and type of diversion used.
- Pump capacity must be sufficient for design flow.
- A standby pump is required in case a primary pump fails.
- Dam materials used to create dams upstream and downstream of diversion should be erosion resistant; materials such as steel plate, sheet pile, sandbags, continuous berms, inflatable water bladders, etc., would be acceptable.

When constructing a diversion channel, begin excavation of the channel at the proposed downstream end, and work upstream. Once the watercourse to be diverted is reached and the excavated channel is stable, breach the upstream end and allow water to flow down the new channel. Once flow has been established in the diversion channel, install the diversion weir in the main channel; this will force all water to be diverted from the main channel.

#### Inspection and Maintenance

- Pumped diversions require 24 hour monitoring of pumps.
- Inspect embankments and diversion channels for damage to the linings, accumulating debris, sediment buildup, and adequacy of the slope protection. Remove debris and repair linings and slope protection as required. Remove holes, gaps, or scour.
- Upon completion of work, the diversion or isolation structure should be removed and flow should be redirected through the new culvert or back into the original stream channel. Recycle or reuse if applicable.
- Revegetate areas disturbed by BMP removal if needed.

#### **Costs**

Costs of clear water diversion vary considerably and can be very high.

#### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Refer to BMP-specific inspection and maintenance requirements.


#### References

California Bank and Shore Rock Slope Protection Design – Practitioners Guide and Field Evaluations of Riprap Methods, Caltrans Study No. F90TL03, October, 2000.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

 $\square$ 

## Illicit Connection/Discharge



## **Description and Purpose**

Procedures and practices designed for construction contractors to recognize illicit connections or illegally dumped or discharged materials on a construction site and report incidents.

## **Suitable Applications**

This best management practice (BMP) applies to all construction projects. Illicit connection/discharge and reporting is applicable anytime an illicit connection or discharge is discovered or illegally dumped material is found on the construction site.

#### Limitations

Illicit connections and illegal discharges or dumping, for the purposes of this BMP, refer to discharges and dumping caused by parties other than the contractor. If pre-existing hazardous materials or wastes are known to exist onsite, they should be identified in the SWPPP and handled as set forth in the SWPPP.

## Implementation

#### **Planning**

- Review the SWPPP. Pre-existing areas of contamination should be identified and documented in the SWPPP.
- Inspect site before beginning the job for evidence of illicit connections, illegal dumping or discharges. Document any pre-existing conditions and notify the owner.
- Inspect site regularly during project execution for evidence

#### **Categories**

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

■ Secondary Objective

## **Targeted Constituents**

| Sediment       |           |
|----------------|-----------|
| Nutrients      | $\square$ |
| Trash          |           |
| Metals         |           |
| Bacteria       | abla      |
| Oil and Grease | $\square$ |
| Organics       | <b>V</b>  |

#### **Potential Alternatives**

None



- 54 TWO 18

of illicit connections, illegal dumping or discharges.

• Observe site perimeter for evidence for potential of illicitly discharged or illegally dumped material, which may enter the job site.

## Identification of Illicit Connections and Illegal Dumping or Discharges

- General unlabeled and unidentifiable material should be treated as hazardous.
- Solids Look for debris, or rubbish piles. Solid waste dumping often occurs on roadways with light traffic loads or in areas not easily visible from the traveled way.
- **Liquids** signs of illegal liquid dumping or discharge can include:
  - Visible signs of staining or unusual colors to the pavement or surrounding adjacent soils
  - Pungent odors coming from the drainage systems
  - Discoloration or oily substances in the water or stains and residues detained within ditches, channels or drain boxes
  - Abnormal water flow during the dry weather season
- **Urban Areas** Evidence of illicit connections or illegal discharges is typically detected at storm drain outfall locations or at manholes. Signs of an illicit connection or illegal discharge can include:
  - Abnormal water flow during the dry weather season
  - Unusual flows in sub drain systems used for dewatering
  - Pungent odors coming from the drainage systems
  - Discoloration or oily substances in the water or stains and residues detained within ditches, channels or drain boxes
  - Excessive sediment deposits, particularly adjacent to or near active offsite construction projects
- Rural Areas Illicit connections or illegal discharges involving irrigation drainage ditches are detected by visual inspections. Signs of an illicit discharge can include:
  - Abnormal water flow during the non-irrigation season
  - Non-standard junction structures
  - Broken concrete or other disturbances at or near junction structures

#### Reporting

Notify the owner of any illicit connections and illegal dumping or discharge incidents at the time of discovery. For illicit connections or discharges to the storm drain system, notify the local stormwater management agency. For illegal dumping, notify the local law enforcement agency.

#### Cleanup and Removal

The responsibility for cleanup and removal of illicit or illegal dumping or discharges will vary by location. Contact the local stormwater management agency for further information.

#### Costs

Costs to look for and report illicit connections and illegal discharges and dumping are low. The best way to avoid costs associated with illicit connections and illegal discharges and dumping is to keep the project perimeters secure to prevent access to the site, to observe the site for vehicles that should not be there, and to document any waste or hazardous materials that exist onsite before taking possession of the site.

#### **Inspection and Maintenance**


- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect the site regularly to check for any illegal dumping or discharge.
- Prohibit employees and subcontractors from disposing of non-job related debris or materials at the construction site.
- Notify the owner of any illicit connections and illegal dumping or discharge incidents at the time of discovery.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



## **Description and Purpose**

Potable Water/Irrigation consists of practices and procedures to manage the discharge of potential pollutants generated during discharges from irrigation water lines, landscape irrigation, lawn or garden watering, planned and unplanned discharges from potable water sources, water line flushing, and hydrant flushing.

## **Suitable Applications**

Implement this BMP whenever potable water or irrigation water discharges occur at or enter a construction site.

#### Limitations

None identified.

#### **Implementation**

- Direct water from offsite sources around or through a construction site, where feasible, in a way that minimizes contact with the construction site.
- Discharges from water line flushing should be reused for landscaping purposes where feasible.
- Shut off the water source to broken lines, sprinklers, or valves as soon as possible to prevent excess water flow.
- Protect downstream stormwater drainage systems and watercourses from water pumped or bailed from trenches excavated to repair water lines.
- Inspect irrigated areas within the construction limits for

#### Categories

EC Erosion Control
SE Sediment Control
TC Tracking Control
WE Wind Erosion Control
NS Non-Stormwater
Management Control
Waste Management and
Materials Pollution Control

#### Legend:

✓ Primary Objective✓ Secondary Objective

## **Targeted Constituents**

| rangetea constituents |              |  |
|-----------------------|--------------|--|
| Sediment              | Ø            |  |
| Nutrients             | V            |  |
| Trash                 |              |  |
| Metals                | $\square$    |  |
| Bacteria              |              |  |
| Oil and Grease        |              |  |
| Organics              | $\checkmark$ |  |
|                       |              |  |

#### **Potential Alternatives**



## **Potable Water/Irrigation**

excess watering. Adjust watering times and schedules to ensure that the appropriate amount of water is being used and to minimize runoff. Consider factors such as soil structure, grade, time of year, and type of plant material in determining the proper amounts of water for a specific area.

#### Costs

Cost to manage potable water and irrigation are low and generally considered to be a normal part of related activities.

## **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Repair broken water lines as soon as possible.
- Inspect irrigated areas regularly for signs of erosion and/or discharge.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

 $\square$ 



## **Description and Purpose**

Vehicle and equipment cleaning procedures and practices eliminate or reduce the discharge of pollutants to stormwater from vehicle and equipment cleaning operations. Procedures and practices include but are not limited to: using offsite facilities; washing in designated, contained areas only; eliminating discharges to the storm drain by infiltrating the wash water; and training employees and subcontractors in proper cleaning procedures.

## **Suitable Applications**

These procedures are suitable on all construction sites where vehicle and equipment cleaning is performed.

#### Limitations

Even phosphate-free, biodegradable soaps have been shown to be toxic to fish before the soap degrades. Sending vehicles/equipment offsite should be done in conjunction with TC-1, Stabilized Construction Entrance/Exit.

#### **Implementation**

Other options to washing equipment onsite include contracting with either an offsite or mobile commercial washing business. These businesses may be better equipped to handle and dispose of the wash waters properly. Performing this work offsite can also be economical by eliminating the need for a separate washing operation onsite.

If washing operations are to take place onsite, then:

#### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

Non-Stormwater

Management Control

Waste Management and
Materials Pollution Control

#### Legend:

☑ Primary Objective

**☒** Secondary Objective

## **Targeted Constituents**

SedIment

Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

## **Potential Alternatives**



- Use phosphate-free, biodegradable soaps.
- Educate employees and subcontractors on pollution prevention measures.
- Do not permit steam cleaning onsite. Steam cleaning can generate significant pollutant concentrates.
- Cleaning of vehicles and equipment with soap, solvents or steam should not occur on the project site unless resulting wastes are fully contained and disposed of. Resulting wastes should not be discharged or buried, and must be captured and recycled or disposed according to the requirements of WM-10, Liquid Waste Management or WM-6, Hazardous Waste Management, depending on the waste characteristics. Minimize use of solvents. Use of diesel for vehicle and equipment cleaning is prohibited.
- All vehicles and equipment that regularly enter and leave the construction site must be cleaned offsite.
- When vehicle and equipment washing and cleaning must occur onsite, and the operation cannot be located within a structure or building equipped with appropriate disposal facilities, the outside cleaning area should have the following characteristics:
  - Located away from storm drain inlets, drainage facilities, or watercourses
  - Paved with concrete or asphalt and bermed to contain wash waters and to prevent runon and runoff
  - Configured with a sump to allow collection and disposal of wash water
  - No discharge of wash waters to storm drains or watercourses
  - Used only when necessary
- When cleaning vehicles and equipment with water:
  - Use as little water as possible. High-pressure sprayers may use less water than a hose and should be considered
  - Use positive shutoff valve to minimize water usage
  - Facility wash racks should discharge to a sanitary sewer, recycle system or other approved discharge system and must not discharge to the storm drainage system, watercourses, or to groundwater

#### Costs

Cleaning vehicles and equipment at an offsite facility may reduce overall costs for vehicle and equipment cleaning by eliminating the need to provide similar services onsite. When onsite cleaning is needed, the cost to establish appropriate facilities is relatively low on larger, long-duration projects, and moderate to high on small, short-duration projects.

### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Inspection and maintenance is minimal, although some berm repair may be necessary.
- Monitor employees and subcontractors throughout the duration of the construction project to ensure appropriate practices are being implemented.
- Inspect sump regularly and remove liquids and sediment as needed.
- Prohibit employees and subcontractors from washing personal vehicles and equipment on the construction site.


#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Swisher, R.D. Surfactant Biodegradation, Marcel Decker Corporation, 1987.

abla

# Vehicle and Equipment Fueling



## **Description and Purpose**

Vehicle equipment fueling procedures and practices are designed to prevent fuel spills and leaks, and reduce or eliminate contamination of stormwater. This can be accomplished by using offsite facilities, fueling in designated areas only, enclosing or covering stored fuel, implementing spill controls, and training employees and subcontractors in proper fueling procedures.

### **Suitable Applications**

These procedures are suitable on all construction sites where vehicle and equipment fueling takes place.

#### Limitations

Onsite vehicle and equipment fueling should only be used where it is impractical to send vehicles and equipment offsite for fueling. Sending vehicles and equipment offsite should be done in conjunction with TC-1, Stabilized Construction Entrance/Exit.

## **Implementation**

- Use offsite fueling stations as much as possible. These businesses are better equipped to handle fuel and spills properly. Performing this work offsite can also be economical by eliminating the need for a separate fueling area at a site.
- Discourage "topping-off" of fuel tanks.
- Absorbent spill cleanup materials and spill kits should be available in fueling areas and on fueling trucks, and should

#### Categories

EC Erosion Control
SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

Secondary Objective

### **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**



be disposed of properly after use.

- Drip pans or absorbent pads should be used during vehicle and equipment fueling, unless the fueling is performed over an impermeable surface in a dedicated fueling area.
- Use absorbent materials on small spills. Do not hose down or bury the spill. Remove the adsorbent materials promptly and dispose of properly.
- Avoid mobile fueling of mobile construction equipment around the site; rather, transport the equipment to designated fueling areas. With the exception of tracked equipment such as bulldozers and large excavators, most vehicles should be able to travel to a designated area with little lost time.
- Train employees and subcontractors in proper fueling and cleanup procedures.
- When fueling must take place onsite, designate an area away from drainage courses to be used. Fueling areas should be identified in the SWPPP.
- Dedicated fueling areas should be protected from stormwater runon and runoff, and should be located at least 50 ft away from downstream drainage facilities and watercourses. Fueling must be performed on level-grade areas.
- Protect fueling areas with berms and dikes to prevent runon, runoff, and to contain spills.
- Nozzles used in vehicle and equipment fueling should be equipped with an automatic shutoff to control drips. Fueling operations should not be left unattended.
- Use vapor recovery nozzles to help control drips as well as air pollution where required by Air Quality Management Districts (AQMD).
- Federal, state, and local requirements should be observed for any stationary above ground storage tanks.

#### Costs

All of the above measures are low cost except for the capital costs of above ground tanks that meet all local environmental, zoning, and fire codes.

## **Inspection and Maintenance**

- Vehicles and equipment should be inspected each day of use for leaks. Leaks should be repaired immediately or problem vehicles or equipment should be removed from the project site.
- Keep ample supplies of spill cleanup materials onsite.
- Immediately clean up spills and properly dispose of contaminated soil and cleanup materials.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Coastal Nonpoint Pollution Control Program: Program Development and Approval Guidance, Working Group Working Paper; USEPA, April 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



## Legend:

SE

NS

Categories

Erosion Control
Sediment Control

Tracking Control
Wind Erosion Control
Non-Stormwater

Management Control
Waste Management and
Materials Pollution Control

 $\square$ 

M

Primary Objective

Secondary Objective

## **Description and Purpose**

Prevent or reduce the contamination of stormwater resulting from vehicle and equipment maintenance by running a "dry and clean site". The best option would be to perform maintenance activities at an offsite facility. If this option is not available then work should be performed in designated areas only, while providing cover for materials stored outside, checking for leaks and spills, and containing and cleaning up spills immediately. Employees and subcontractors must be trained in proper procedures.

## Suitable Applications

These procedures are suitable on all construction projects where an onsite yard area is necessary for storage and maintenance of heavy equipment and vehicles.

#### Limitations

Onsite vehicle and equipment maintenance should only be used where it is impractical to send vehicles and equipment offsite for maintenance and repair. Sending vehicles/equipment offsite should be done in conjunction with TC-1, Stabilized Construction Entrance/Exit.

Outdoor vehicle or equipment maintenance is a potentially significant source of stormwater pollution. Activities that can contaminate stormwater include engine repair and service, changing or replacement of fluids, and outdoor equipment storage and parking (engine fluid leaks). For further information on vehicle or equipment servicing, see NS-8, Vehicle and Equipment Cleaning, and NS-9, Vehicle and

## **Targeted Constituents**

Sediment
Nutrients
✓
Trash
Metals
Bacteria
Oil and Grease

#### **Potential Alternatives**

None

Organics



Equipment Fueling.

#### **Implementation**

- Use offsite repair shops as much as possible. These businesses are better equipped to handle vehicle fluids and spills properly. Performing this work offsite can also be economical by eliminating the need for a separate maintenance area.
- If maintenance must occur onsite, use designated areas, located away from drainage courses. Dedicated maintenance areas should be protected from stormwater runon and runoff, and should be located at least 50 ft from downstream drainage facilities and watercourses.
- Drip pans or absorbent pads should be used during vehicle and equipment maintenance work that involves fluids, unless the maintenance work is performed over an impermeable surface in a dedicated maintenance area.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- All fueling trucks and fueling areas are required to have spill kits and/or use other spill protection devices.
- Use adsorbent materials on small spills. Remove the absorbent materials promptly and dispose of properly.
- Inspect onsite vehicles and equipment daily at startup for leaks, and repair immediately.
- Keep yehicles and equipment clean; do not allow excessive build-up of oil and grease.
- Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic and transmission fluids. Provide secondary containment and covers for these materials if stored onsite.
- Train employees and subcontractors in proper maintenance and spill cleanup procedures.
- Drip pans or plastic sheeting should be placed under all vehicles and equipment placed on docks, barges, or other structures over water bodies when the vehicle or equipment is planned to be idle for more than 1 hour.
- For long-term projects, consider using portable tents or covers over maintenance areas if maintenance cannot be performed offsite.
- Consider use of new, alternative greases and lubricants, such as adhesive greases, for chassis lubrication and fifth-wheel lubrication.
- Properly dispose of used oils, fluids, lubricants, and spill cleanup materials.
- Do not place used oil in a dumpster or pour into a storm drain or watercourse.
- Properly dispose of or recycle used batteries.
- Do not bury used tires.

Repair leaks of fluids and oil immediately.

Listed below is further information if you must perform vehicle or equipment maintenance onsite.

#### Safer Alternative Products

- Consider products that are less toxic or hazardous than regular products. These products are often sold under an "environmentally friendly" label.
- Consider use of grease substitutes for lubrication of truck fifth-wheels. Follow manufacturers label for details on specific uses.
- Consider use of plastic friction plates on truck fifth-wheels in lieu of grease. Follow manufacturers label for details on specific uses.

#### Waste Reduction

Parts are often cleaned using solvents such as trichloroethylene, trichloroethane, or methylene chloride. Many of these cleaners are listed in California Toxic Rule as priority pollutants. These materials are harmful and must not contaminate stormwater. They must be disposed of as a hazardous waste. Reducing the number of solvents makes recycling easier and reduces hazardous waste management costs. Often, one solvent can perform a job as well as two different solvents. Also, if possible, eliminate or reduce the amount of hazardous materials and waste by substituting non-hazardous or less hazardous materials. For example, replace chlorinated organic solvents with non-chlorinated solvents. Non-chlorinated solvents like kerosene or mineral spirits are less toxic and less expensive to dispose of properly. Check the list of active ingredients to see whether it contains chlorinated solvents. The "chlor" term indicates that the solvent is chlorinated. Also, try substituting a wire brush for solvents to clean parts.

#### Recycling and Disposal

Separating wastes allows for easier recycling and may reduce disposal costs. Keep hazardous wastes separate, do not mix used oil solvents, and keep chlorinated solvents (like,-trichloroethane) separate from non-chlorinated solvents (like kerosene and mineral spirits). Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around. Provide cover and secondary containment until these materials can be removed from the site.

Oil filters can be recycled. Ask your oil supplier or recycler about recycling oil filters.

Do not dispose of extra paints and coatings by dumping liquid onto the ground or throwing it into dumpsters. Allow coatings to dry or harden before disposal into covered dumpsters.

Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries, even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Costs

All of the above are low cost measures. Higher costs are incurred to setup and maintain onsite maintenance areas.

a b

#### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Keep ample supplies of spill cleanup materials onsite.
- Maintain waste fluid containers in leak proof condition.
- Vehicles and equipment should be inspected on each day of use. Leaks should be repaired immediately or the problem vehicle(s) or equipment should be removed from the project site.
- Inspect equipment for damaged hoses and leaky gaskets routinely. Repair or replace as needed.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.


Coastal Nonpoint Pollution Control Program; Program Development and Approval Guidance, Working Group, Working Paper; USEPA, April 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

 $\square$ 

 $\square$ 

## **Pile Driving Operations**



## **Description and Purpose**

The construction and retrofit of bridges and retaining walls often include driving piles for foundation support and shoring operations. Driven piles are typically constructed of precast concrete, steel, or timber. Driven sheet piles are also used for shoring and cofferdam construction. Proper control and use of equipment, materials, and waste products from pile driving operations will reduce or eliminate the discharge of potential pollutants to the storm drain system, watercourses, and waters of the United States.

## **Suitable Applications**

These procedures apply to all construction sites near or adjacent to a watercourse or groundwater where permanent and temporary pile driving (impact and vibratory) takes place, including operations using pile shells as well as construction of cast-in-steel-shell and cast-in-drilled-hole piles.

#### Limitations

None identified.

#### **Implementation**

- Use drip pans or absorbent pads during vehicle and equipment operation, maintenance, cleaning, fueling, and storage. Refer to NS-8, Vehicle and Equipment Cleaning, NS-9, Vehicle and Equipment Fueling, and NS-10, Vehicle and Equipment Maintenance.
- Have spill kits and cleanup materials available at all locations of pile driving. Refer to WM-4, Spill Prevention

## Categories

EC Erosion Control
SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

☑ Primary Objective

☑ Secondary Objective

## **Targeted Constituents**

Sediment

**Nutrients** 

Trash

Metals

Bacteria

Oil and Grease

**Organics** 

#### Potential Alternatives



and Control.

- Equipment that is stored or in use in streambeds, or on docks, barges, or other structures over water bodies should be kept leak free.
- Park equipment over plastic sheeting or equivalent where possible. Plastic is not a substitute for drip pans or absorbent pads. The storage or use of equipment in streambeds or other bodies of water must comply with all applicable permits.
- Implement other BMPs as applicable, such as NS-2, Dewatering Operations, WM-5, Solid Waste Management, WM-6, Hazardous Waste Management, and WM-10, Liquid Waste Management.
- When not in use, store pile-driving equipment away from concentrated flows of stormwater, drainage courses, and inlets. Protect hammers and other hydraulic attachments from runon and runoff by placing them on plywood and covering them with plastic or a comparable material prior to the onset of rain.
- Use less hazardous products, e.g., vegetable oil, when practicable.

#### Costs

All of the above measures can be low cost.


#### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and at two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Inspect equipment every day at startup and repair equipment as needed (i.e., worn or damaged hoses, fittings, and gaskets). Recheck equipment at shift changes or at the end of the day and scheduled repairs as needed.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



## **Description and Purpose**

Concrete curing is used in the construction of structures such as bridges, retaining walls, pump houses, large slabs, and structured foundations. Concrete curing includes the use of both chemical and water methods.

Concrete and its associated curing materials have basic chemical properties that can raise the pH of water to levels outside of the permitted range. Discharges of stormwater and non-stormwater exposed to concrete during curing may have a high pH and may contain chemicals, metals, and fines. The General Permit incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for pH (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements).

Proper procedures and care should be taken when managing concrete curing materials to prevent them from coming into contact with stormwater flows, which could result in a high pH discharge.

## **Suitable Applications**

Suitable applications include all projects where Portland Cement Concrete (PCC) and concrete curing chemicals are placed where they can be exposed to rainfall, runoff from other areas, or where runoff from the PCC will leave the site.

| Categories |   |   |
|------------|---|---|
| EC         | Erosion Control                                     |   |
| SE         | Sediment Control                                    |   |
| TC         | Tracking Control                                    |   |
| WE         | Wind Erosion Control                                |   |
| NS         | Non-Stormwater<br>Management Control                | ✓ |
| WM         | Waste Management and<br>Materials Pollution Control | V |

#### Legend:

- ☑ Primary Category
- ☑ Secondary Category

## **Targeted Constituents**

| Sediment       | Ø         |
|----------------|-----------|
| Nutrients      |           |
| Trash          |           |
| Metals         | $\Box$    |
| Bacteria       |           |
| Oil and Grease | $\square$ |
| Organics       |           |

#### **Potential Alternatives**



#### Limitations

 Runoff contact with concrete waste can raise pH levels in the water to environmentally harmful levels and trigger permit violations.

## **Implementation**

## **Chemical Curing**

- Avoid over spray of curing compounds.
- Minimize the drift by applying the curing compound close to the concrete surface. Apply an amount of compound that covers the surface, but does not allow any runoff of the compound.
- Use proper storage and handling techniques for concrete curing compounds. Refer to WM Material Delivery and Storage.
- Protect drain inlets prior to the application of curing compounds.
- Refer to WM-4, Spill Prevention and Control.

#### Water Curing for Bridge Decks, Retaining Walls, and other Structures

- Direct cure water away from inlets and watercourses to collection areas for evaporation or other means of removal in accordance with all applicable permits. See WM-8 Concrete Waste Management.
- Collect cure water at the top of slopes and transport to a concrete waste management area in a non-erosive manner. See EC-9 Earth Dikes and Drainage Swales, EC-10, Velocity Dissipation Devices, and EC-11, Slope Drains.
- Utilize wet blankets or a similar method that maintains moisture while minimizing the use and possible discharge of water.

#### Education

- Educate employees, subcontractors, and suppliers on proper concrete curing techniques to prevent contact with discharge as described herein.
- Arrange for the QSP or the appropriately trained contractor's superintendent or representative to oversee and enforce concrete curing procedures.

#### Costs

All of the above measures are generally low cost.

#### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.

- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Sample non-stormwater discharges and stormwater runoff that contacts uncured and partially cured concrete as required by the General Permit.
- Ensure that employees and subcontractors implement appropriate measures for storage, handling, and use of curing compounds.
- Inspect cure containers and spraying equipment for leaks.


#### References

Blue Print for a Clean Bay-Construction-Related Industries: Best Management Practices for Stormwater Pollution Prevention; Santa Clara Valley Non Point Source Pollution Control Program, 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

Erosion and Sediment Control Manual, Oregon Department of Environmental Quality, February 2005.



| Description | and | Durnose |
|-------------|-----|---------|
| Description | anu | ruipuse |

Concrete finishing methods are used for bridge deck rehabilitation, paint removal, curing compound removal, and final surface finish appearances. Methods include sand blasting, shot blasting, grinding, or high pressure water blasting. Stormwater and non-stormwater exposed to concrete finishing by-products may have a high pH and may contain chemicals, metals, and fines. Proper procedures and implementation of appropriate BMPs can minimize the impact that concrete-finishing methods may have on stormwater and non-stormwater discharges.

The General Permit incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for pH (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements).

Concrete and its associated curing materials have basic chemical properties that can raise pH levels outside of the permitted range. Additional care should be taken when managing these materials to prevent them from coming into contact with stormwater flows, which could lead to exceedances of the General Permit requirements.

#### Suitable Applications

These procedures apply to all construction locations where concrete finishing operations are performed.

| Categories |   |   |  |
|------------|---|---|--|
| EC         | Erosion Control                                     |   |  |
| SE         | Sediment Control                                    |   |  |
| TC         | Tracking Control                                    |   |  |
| WE         | Wind Erosion Control                                |   |  |
| NS         | Non-Stormwater<br>Management Control                | V |  |
| WM         | Waste Management and<br>Materials Pollution Control | V |  |
| Loge       | and:  |   |  |

#### Legend:

- ☑ Primary Category
- Secondary Category

## **Targeted Constituents**

|   | rargeted Constituents | ' |
|---|-----------------------|---|
| - | Sediment              | V |
|   | Nutrients             |   |
|   | Trash                 |   |
|   | Metals                | ⊻ |
|   | Bacteria              |   |
|   | Oil and Grease        |   |
|   | Organics              | ✓ |
|   |                       |   |

#### **Potential Alternatives**



#### Limitations

 Runoff contact with concrete waste can raise pH levels in the water to environmentally harmful levels and trigger permit violations.

,i

#### **Implementation**

- Collect and properly dispose of water from high-pressure water blasting operations.
- Collect contaminated water from blasting operations at the top of slopes. Transport or dispose of contaminated water while using BMPs such as those for erosion control. Refer to EC-9, Earth Dikes and Drainage Swales, EC-10, Velocity Dissipation Devices, and EC-11, Slope Drains.
- Direct water from blasting operations away from inlets and watercourses to collection areas for infiltration or other means of removal (dewatering). Refer to NS-2 Dewatering Operations.
- Protect inlets during sandblasting operations. Refer to SE-10, Storm Drain Inlet Protection.
- Refer to WM-8, Concrete Waste Management for disposal of concrete debris.
- Minimize the drift of dust and blast material as much as possible by keeping the blasting nozzle close to the surface.
- When blast residue contains a potentially hazardous waste, refer to WM-6, Hazardous Waste Management.

#### Education

- Educate employees, subcontractors, and suppliers on proper concrete finishing techniques to prevent contact with discharge as described herein.
- Arrange for the QSP or the appropriately trained contractor's superintendent or representative to oversee and enforce concrete finishing procedures.

#### Costs

These measures are generally of low cost.

### **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- Sample non-stormwater discharges and stormwater runoff that contacts concrete dust and debris as required by the General Permit.

- Sweep or vacuum up debris from sandblasting at the end of each shift.
- At the end of each work shift, remove and contain liquid and solid waste from containment structures, if any, and from the general work area.
- Inspect containment structures for damage prior to use and prior to onset of forecasted rain.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

www.casqa.org



## **Description and Purpose**

Procedures for the proper use, storage, and disposal of materials and equipment on barges, boats, temporary construction pads, or similar locations that minimize or eliminate the discharge of potential pollutants to a watercourse.

## **Suitable Applications**

Applies where materials and equipment are used on barges, boats, docks, and other platforms over or adjacent to a watercourse including waters of the United States. These procedures should be implemented for construction materials and wastes (solid and liquid), soil or dredging materials, or any other materials that may cause or contribute to exceedances of water quality standards.

#### Limitations

Dredge and fill activities are regulated by the US Army Corps of Engineers and Regional Boards under Section 404/401 of the Clean Water Act.

### **Implementation**

- Refer to WM-1, Material Delivery and Storage and WM-4, Spill Prevention and Control.
- Use drip pans and absorbent materials for equipment and vehicles and ensure that an adequate supply of spill clean up materials is available.
- Drip pans should be placed under all vehicles and equipment placed on docks, barges, or other structures over

## Categories

EC **Erosion Control** SE Sediment Control TC **Tracking Control** WE Wind Erosion Control Non-Stormwater NS  $\mathbf{V}$ Management Control Waste Management and WW  $\square$ Materials Pollution Control

#### Legend:

- Primary Objective
- Secondary Objective

## **Targeted Constituents**

| Sediment       | Ø         |
|----------------|-----------|
| Nutrients      |           |
| Trash          |           |
| Metals         |           |
| Bacteria       |           |
| Oil and Grease | $\square$ |
| Organics       | abla      |
|                |           |

#### **Potential Alternatives**



water bodies when the vehicle or equipment is expected to be idle for more than 1 hour.

- Maintain equipment in accordance with NS-10, Vehicle and Equipment Maintenance. If a leaking line cannot be repaired, remove equipment from over the water.
- Provide watertight curbs or toe boards to contain spills and prevent materials, tools, and debris from leaving the barge, platform, dock, etc.
- Secure all materials to prevent discharges to receiving waters via wind.
- Identify types of spill control measures to be employed, including the storage of such materials and equipment. Ensure that staff is trained regarding the use of the materials, deployment and access of control measures, and reporting measures.
- In case of spills, contact the local Regional Board as soon as possible but within 48 hours.
- Refer to WM-5, Solid Waste Management (non-hazardous) and WM-6, Hazardous Waste Management. Ensure the timely and proper removal of accumulated wastes
- Comply with all necessary permits required for construction within or near the watercourse, such as Regional Water Quality Control Board, U.S. Army Corps of Engineers, Department of Fish and Game or and other local permitting.
- Discharges to waterways should be reported to the Regional Water Quality Control Board immediately upon discovery. A written discharge notification must follow within 7 days. Follow the spill reporting procedures contained in SWPPP.

#### Costs

These measures are generally of low to moderate cost. Exceptions are areas for temporary storage of materials, engine fluids, or wastewater pump out.

## **Inspection and Maintenance**


- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.
- Ensure that employees and subcontractors implement the appropriate measures for storage and use of materials and equipment.
- Inspect and maintain all associated BMPs and perimeter controls to ensure continuous protection of the water courses, including waters of the United States.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

## **Demolition Adjacent to Water**



## **Description and Purpose**

Procedures to protect water bodies from debris and wastes associated with structure demolition or removal over or adjacent to watercourses.

## **Suitable Applications**

Full bridge demolition and removal, partial bridge removal (barrier rail, edge of deck) associated with bridge widening projects, concrete channel removal, or any other structure removal that could potentially affect water quality.

#### Limitations

None identified.

### **Implementation**

- Refer to NS-5, Clear Water Diversion, to direct water away from work areas.
- Use attachments on construction equipment such as backhoes to catch debris from small demolition operations.
- Use covers or platforms to collect debris.
- Platforms and covers are to be approved by the owner.
- Stockpile accumulated debris and waste generated during demolition away from watercourses and in accordance with WM-3, Stockpile Management.
- Ensure safe passage of wildlife, as necessary.

#### Categories

| EC | Erosion Control                                     |   |
|----|---|---|
| SE | Sediment Control                                    |   |
| TC | Tracking Control                                    |   |
| WE | Wind Erosion Control                                |   |
| NS | Non-Stormwater<br>Management Control                | Ø |
| WM | Waste Management and<br>Materials Pollution Control |   |

#### Legend:

- Primary Objective
- ▼ Secondary Objective

#### **Targeted Constituents**

| Sediment       | Ø                 |
|----------------|-------------------|
| Nutrients      | $\mathbf{\nabla}$ |
| Trash          | 囟                 |
| Metals         |                   |
| Bacteria       | $\square$         |
| Oil and Grease | $\square$         |
| Organics       |                   |

#### **Potential Alternatives**



- Discharges to waterways shall be reported to the Regional Water Quality Control Board immediately upon discovery. A written discharge notification must follow within 7 days.
   Follow the spill reporting procedures in the SWPPP.
- For structures containing hazardous materials, i.e., lead paint or asbestos, refer to BMP WM-6, Hazardous Waste Management. For demolition work involving soil excavation around lead-painted structures, refer to WM-7, Contaminated Soil Management.

#### Costs

Cost may vary according to the combination of practices implemented.

## **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.
- Any debris-catching devices shall be emptied regularly. Collected debris shall be removed and stored away from the watercourse and protected from runon and runoff.

#### References


Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.

abla

 $\square$ 

 $\square$ 



## **Description and Purpose**

The construction of roads, bridges, retaining walls, and other large structures in remote areas, often requires temporary batch plant facilities to manufacture Portland Cement Concrete (PCC) or asphalt cement (AC). Temporary batch plant facilities typically consist of silos containing fly ash, lime, and cement; heated tanks of liquid asphalt; sand and gravel material storage areas; mixing equipment; above ground storage tanks containing concrete additives and water; and designated areas for sand and gravel truck unloading, concrete truck loading, and concrete truck washout. Proper control and use of equipment, materials, and waste products from temporary batch plant facilities will reduce the discharge of potential pollutants to the storm drain system or watercourses, reduce air emissions, and mitigate noise impacts.

The General Permit draft incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for pH (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements). Many types of batch plant materials, including mortar, concrete, cement and block and their associated wastes have basic chemical properties that can raise pH levels outside of the permitted range. Additional care should be taken when managing these materials to prevent them from coming into contact with stormwater flows which may cause an exceedence of the General Permit Requirements.

#### Categories

- **Erosion Control**
- SE Sediment Control
- **Tracking Control** TC
- WE Wind Erosion Control
- Non-Stormwater NS Management Control
- Waste Management and
- Materials Pollution Control

### Legend:

- ☑ Primary Category
- Secondary Category

## **Targeted Constituents**

- Sediment  $\square$
- Nutrients
- Trash
- Metals
- Bacteria
- Oil and Grease
- **Organics**

#### **Potential Alternatives**



### **Suitable Applications**

These procedures typically apply to construction sites where temporary batch plant facilities are used; however, some of the practices described are applicable to construction sites with general concrete use.

#### Limitations

The General Permit for discharges of stormwater associated with industrial activities (General Industrial Permit) may be applicable to temporary batch plants.

Specific permit requirements or mitigation measures such as Air Resources Board (ARB), Air Quality Management District (AQMD), Air Pollution Control District (APCD, Regional Water Quality Control Board (RWQCB), county ordinances and city ordinances may require alternative mitigation measures for temporary batch plants. Contact the local regulatory agencies to determine if a permit is required.

#### **Implementation**

### **Planning**

- Temporary batch plants may be subject to the General Industrial Permit. To obtain a copy of this permit and the application forms, visit http://www.waterboards.ca.gov or contact the State Water Resources Control Board.
- Proper planning, design, and construction of temporary batch plants should be implemented to minimize potential water quality, air pollution, and noise impacts associated with temporary batch plants.
- BMPs and a Construction Site Monitoring Plan (CSMP) should be included in the project Stormwater Pollution Prevention Plan (SWPPP). BMPs should be implemented, inspected, and maintained in accordance with these plans.
- Temporary batch plants should be managed to comply with AQMD Statewide Registration Program and/or local AQMD Portable Equipment Registration requirements.
- Construct temporary batch plants downwind of existing developments whenever possible.
- Placement of access roads should be planned to mitigate water and air quality impacts.

#### Layout and Design

- Temporary batch plants should be properly located and designed to mitigate water quality impacts to receiving water bodies. Batch plants should be located away from watercourses, drainage courses, and drain inlets. Batch plants should be located to minimize the potential for stormwater runon onto the site.
- Temporary batch plant facilities (including associated stationary equipment and stockpiles) should be located at least 300 ft from any recreational area, school, residence, or other structure not associated with the construction project.
- Construct continuous interior AC or PCC berms around batch plant equipment (mixing equipment, silos, concrete drop points, conveyor belts, admixture tanks, etc.) to facilitate

- proper containment and cleanup of releases. Rollover or flip top curbs or dikes should be placed at ingress and egress points (SE-12, Temporary Silt Dike).
- Direct runoff from the paved or unpaved portion of the batch plant into a sump and pipe to a lined washout area or dewatering tank.
- Direct stormwater and non-stormwater runoff from unpaved portions of batch plant facility to catchment ponds or tanks.
- Construct and remove concrete washout facilities in accordance with WM-8, Concrete Waste Management.
- Layout of a typical batch plant and associated BMP is located at the end of this BMP fact sheet.

## Operational Procedures

- Washout of concrete trucks should be conducted in a designated area in accordance with WM-8, Concrete Waste Management.
- Do not dispose of concrete into drain inlets, the stormwater drainage system, or watercourses.
- Washing of concrete mixing and transport equipment (including concrete truck washout) should occur in a designated area in accordance with WM-8, Concrete Waste Management.
- Washing equipment, tools, or vehicles to remove PCC should be conducted in accordance with NS-7, Potable Water/Irrigation, NS-8, Vehicle and Equipment Cleaning, and WM-8, Concrete Waste Management..
- All dry material transfer points should be ducted through a fabric or cartridge type filter unless there are no visible emissions from the transfer point.
- Equip all bulk storage silos, including auxiliary bulk storage trailers, with fabric or cartridge type filter(s).
- Maintain silo vent filters in proper operating condition.
- Equip silos and auxiliary bulk storage trailers with dust-tight service hatches.
- Fabric dust collection system should be capable of controlling particulate matter in accordance with the California Air Resources Control Board and local Air Pollution Control District Regulations.
- Fabric dust collectors (except for vent filters) should be equipped with an operational pressure differential gauge to measure the pressure drop across the filters.
- All transfer points should be equipped with a wet suppression system to control fugitive particulate emissions unless there are no visible emissions.
- All conveyors should be covered, unless the material being transferred results in no visible emissions.

- There should be no visible emissions beyond the property line, while the equipment is being operated.
- Collect dust emissions from the loading of open-bodied trucks, at the drip point of dry batch plants, or dust emissions from the drum feed for central mix plants.
- Equip silos and auxiliary bulk storage trailers with a visible and/or audible warning mechanism to warn operators that the silo or trailer is full.
- All open-bodied vehicles transporting material should be loaded with a final layer of wet sand and the truck should be covered with a tarp to reduce emissions.

#### **Tracking Control**

- Plant roads (batch truck and material delivery truck roads) and areas between stockpiles and conveyor hoppers should be stabilized (TC-2, Stabilized Construction Roadway), watered, treated with dust-suppressant chemicals (WE-1, Wind Erosion Control), or paved with a cohesive hard surface that can be repeatedly swept, maintained intact, and cleaned as necessary to control dust emissions.
- Trucks should not track PCC from plants onto public roads. Use appropriate practices from TC-1, Stabilized Construction Entrance/Exit, to prevent tracking.

#### **Materials Storage**

- WM-1, Material Delivery and Storage, should be implemented at all batch plants using concrete components or compounds. An effective strategy is to cover and contain materials.
- WM-2, Material Use should be conducted in a way to minimize or eliminate the discharge of materials to storm drain system or watercourse.
- Ensure that finer materials are not dispersed into the air during operations, such as unloading of cement delivery trucks.
- Stockpiles should be covered and enclosed with perimeter sediment barriers per WM-3, Stockpile Management. Uncovered stockpiles should be sprayed with water and/or dust-suppressant chemicals as necessary to control dust emissions, unless the stockpiled material results in no visible emissions. An operable stockpile watering system should be onsite at all times.
- Store bagged and boxed materials on pallets and cover or store in a completely enclosed storage area on non-working days and prior to rain.
- Minimize stockpiles of demolished PCC by recycling them in a timely manner.
- Provide secondary containment for liquid materials (WM-1, Material Delivery and Storage, WM-10, Liquid Waste Management). Containment should provide sufficient volume to contain precipitation from a 25-year storm plus 10% of the aggregate volume of all containers or plus 100% of the largest container, whichever is greater.
- Handle solid and liquid waste in accordance with WM-5, Solid Waste Management, WM-10, Liquid Waste Management, and WM-8, Concrete Waste Management.

- Maintain adequate supplies of spill cleanup materials and train staff to respond to spills per WM-4, Spill Prevention and Control.
- Immediately contain and clean up spilled cement and fly ash and contain.

## Equipment Maintenance

- Equipment should be maintained to prevent fluid leaks and spills per NS-9, Vehicle and Equipment Fueling, and NS-10, Vehicle and Equipment Maintenance.
- Maintain adequate supplies of spill cleanup materials and train staff to respond to spills per WM-4, Spill Prevention and Control.
- Incorporate other BMPs such as WM-5, Solid Waste Management, WM-6, Hazardous Waste Management, and WM-10, Liquid Waste Management.

#### Costs

Costs will vary depending on the size of the facility and combination of BMPs implemented.


### **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.
- Sample non-stormwater discharges and stormwater runoff that contacts cementitious materials or fly ash as required by the General Permit.
- Inspect and repair equipment (for damaged hoses, fittings, and gaskets).
- Inspect and maintain a Stabilized Construction Entrance/Exit (TC-1) as needed.
- Inspect and maintain stabilized haul roads as needed (TC-2, Stabilized Construction Roadway).
- Inspect and maintain materials and waste storage areas as needed.


#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices, EPA 832-R-92005; USEPA, April 1992.



**Typical Temporary Batch** 



# **Description and Purpose**

Prevent, reduce, or eliminate the discharge of pollutants from material delivery and storage to the stormwater system or watercourses by minimizing the storage of hazardous materials onsite, storing materials in watertight containers and/or a completely enclosed designated area, installing secondary containment, conducting regular inspections, and training employees and subcontractors.

This best management practice covers only material delivery and storage. For other information on materials, see WM-2, Material Use, or WM-4, Spill Prevention and Control. For information on wastes, see the waste management BMPs in this section.

# **Suitable Applications**

These procedures are suitable for use at all construction sites with delivery and storage of the following materials:

- Soil stabilizers and binders
- Pesticides and herbicides
- **■** Fertilizers
- Detergents
- Plaster
- Petroleum products such as fuel, oil, and grease

## Categories

| EÇ | Erosion Control                                     |   |
|----|---|---|
| SE | Sediment Control                                    |   |
| TC | Tracking Control                                    |   |
| WE | Wind Erosion Control                                |   |
| NS | Non-Stormwater<br>Management Control                |   |
| WM | Waste Management and<br>Materials Pollution Control | V |

## Legend:

- ☑ Primary Category
- ▼ Secondary Category

## **Targeted Constituents**

| Trash Metals Bacteria Oil and Grease |                |           |
|--------------------------------------|----------------|-----------|
| Trash Metals Bacteria Oil and Grease | Sediment       | $\square$ |
| Metals Bacteria Oil and Grease       | Nutrients      | abla      |
| Bacteria Oil and Grease              | Trash          |           |
| Oil and Grease                       | Metals         | ✓         |
|                                      | Bacteria       |           |
| O                                    | Oil and Grease | abla      |
| Organics                             | Organics       |           |

#### **Potential Alternatives**



# **Material Delivery and Storage**

- Asphalt and concrete components
- Hazardous chemicals such as acids, lime, glues, adhesives, paints, solvents, and curing compounds
- Concrete compounds
- Other materials that may be detrimental if released to the environment

#### Limitations

- Space limitation may preclude indoor storage:
- Storage sheds often must meet building and fire code requirements.

## **Implementation**

The following steps should be taken to minimize risk:

- Chemicals must be stored in water tight containers with appropriate secondary containment or in a storage shed.
- When a material storage area is located on bare soil, the area should be lined and bermed.
- Use containment pallets or other practical and available solutions, such as storing materials within newly constructed buildings or garages, to meet material storage requirements.
- Stack erodible landscape material on pallets and cover when not in use.
- Contain all fertilizers and other landscape materials when not in use.
- Temporary storage areas should be located away from vehicular traffic.
- Material Safety Data Sheets (MSDS) should be available on-site for all materials stored that have the potential to effect water quality.
- Construction site areas should be designated for material delivery and storage.
- Material delivery and storage areas should be located away from waterways, if possible.
  - Avoid transport near drainage paths or waterways.
  - Surround with earth berms or other appropriate containment BMP. See EC-9, Earth Dikes and Drainage Swales.
  - Place in an area that will be paved.
- Storage of reactive, ignitable, or flammable liquids must comply with the fire codes of your area. Contact the local Fire Marshal to review site materials, quantities, and proposed storage area to determine specific requirements. See the Flammable and Combustible Liquid Code, NFPA30.
- An up to date inventory of materials delivered and stored onsite should be kept.

- Hazardous materials storage onsite should be minimized.
- Hazardous materials should be handled as infrequently as possible.
- Keep ample spill cleanup supplies appropriate for the materials being stored. Ensure that cleanup supplies are in a conspicuous, labeled area.
- Employees and subcontractors should be trained on the proper material delivery and storage practices.
- Employees trained in emergency spill cleanup procedures must be present when dangerous materials or liquid chemicals are unloaded.
- If significant residual materials remain on the ground after construction is complete, properly remove and dispose of materials and any contaminated soil. See WM-7, Contaminated Soil Management. If the area is to be paved, pave as soon as materials are removed to stabilize the soil.

## Material Storage Areas and Practices

- Liquids, petroleum products, and substances listed in 40 CFR Parts 110, 117, or 302 should be stored in approved containers and drums and should not be overfilled. Containers and drums should be placed in temporary containment facilities for storage.
- A temporary containment facility should provide for a spill containment volume able to contain precipitation from a 25 year storm event, plus the greater of 10% of the aggregate volume of all containers or 100% of the capacity of the largest container within its boundary, whichever is greater.
- A temporary containment facility should be impervious to the materials stored therein for a minimum contact time of 72 hours.
- A temporary containment facility should be maintained free of accumulated rainwater and spills. In the event of spills or leaks, accumulated rainwater and spills should be collected and placed into drums. These liquids should be handled as a hazardous waste unless testing determines them to be non-hazardous. All collected liquids or non-hazardous liquids should be sent to an approved disposal site.
- Sufficient separation should be provided between stored containers to allow for spill cleanup and emergency response access.
- Incompatible materials, such as chlorine and ammonia, should not be stored in the same temporary containment facility.
- Materials should be covered prior to, and during rain events.
- Materials should be stored in their original containers and the original product labels should be maintained in place in a legible condition. Damaged or otherwise illegible labels should be replaced immediately.

- Bagged and boxed materials should be stored on pallets and should not be allowed to accumulate on the ground. To provide protection from wind and rain throughout the rainy season, bagged and boxed materials should be covered during non-working days and prior to and during rain events.
- Stockpiles should be protected in accordance with WM-3, Stockpile Management.
- Materials should be stored indoors within existing structures or completely enclosed storage sheds when available.
- Proper storage instructions should be posted at all times in an open and conspicuous location.
- An ample supply of appropriate spill clean up material should be kept near storage areas.
- Also see WM-6, Hazardous Waste Management, for storing of hazardous wastes.

## **Material Delivery Practices**

- Keep an accurate, up-to-date inventory of material delivered and stored onsite.
- Arrange for employees trained in emergency spill cleanup procedures to be present when dangerous materials or liquid chemicals are unloaded.

## Spill Cleanup

- Contain and clean up any spill immediately.
- Properly remove and dispose of any hazardous materials or contaminated soil if significant residual materials remain on the ground after construction is complete. See WM-7, Contaminated Soil Management.
- See WM-4, Spill Prevention and Control, for spills of chemicals and/or hazardous materials.
- If spills or leaks of materials occur that are not contained and could discharge to surface waters, non-visible sampling of site discharge may be required. Refer to the General Permit or to your project specific Construction Site Monitoring Plan to determine if and where sampling is required.

#### Cost

■ The largest cost of implementation may be in the construction of a materials storage area that is covered and provides secondary containment.

#### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Keep storage areas clean and well organized, including a current list of all materials onsite.
- Inspect labels on containers for legibility and accuracy.

 Repair or replace perimeter controls, containment structures, covers, and liners as needed to maintain proper function.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Coastal Nonpoint Pollution Control Program: Program Development and Approval Guidance, Working Group Working Paper; USEPA, April 1992.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



## **Description and Purpose**

Prevent or reduce the discharge of pollutants to the storm drain system or watercourses from material use by using alternative products, minimizing hazardous material use onsite, and training employees and subcontractors.

## **Suitable Applications**

This BMP is suitable for use at all construction projects. These procedures apply when the following materials are used or prepared onsite:

- Pesticides and herbicides
- Fertilizers
- Detergents
- Petroleum products such as fuel, oil, and grease
- Asphalt and other concrete components
- Other hazardous chemicals such as acids, lime, glues, adhesives, paints, solvents, and curing compounds
- Other materials that may be detrimental if released to the environment

## Categories

EC Erosion Control

SE Sediment Control

C Tracking Control

TC Tracking Control
WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

abla

#### Legend:

- Primary Category
- Secondary Category

## **Targeted Constituents**

| Sediment       | $\square$ |
|----------------|-----------|
| Nutrients      | $\square$ |
| Trash          | abla      |
| Metals         | abla      |
| Bacteria       |           |
| Oil and Grease | abla      |
| Organics       | Ī₹        |

#### **Potential Alternatives**



Material Use WM-2

#### Limitations

Safer alternative building and construction products may not be available or suitable in every instance.

## **Implementation**

The following steps should be taken to minimize risk:

- Minimize use of hazardous materials onsite.
- Follow manufacturer instructions regarding uses, protective equipment, ventilation, flammability, and mixing of chemicals.
- Train personnel who use pesticides. The California Department of Pesticide Regulation and county agricultural commissioners license pesticide dealers, certify pesticide applicators, and conduct onsite inspections.
- The preferred method of termiticide application is soil injection near the existing or proposed structure foundation/slab; however, if not feasible, soil drench application of termiticides should follow EPA label guidelines and the following recommendations (most of which are applicable to most pesticide applications):
  - Do not treat soil that is water-saturated or frozen.
  - Application shall not commence within 24-hours of a predicted precipitation event with a 40% or greater probability. Weather tracking must be performed on a daily basis prior to termiticide application and during the period of termiticide application.
  - Do not allow treatment chemicals to runoff from the target area. Apply proper quantity to prevent excess runoff. Provide containment for and divert stormwater from application areas using berms or diversion ditches during application.
  - Dry season: Do not apply within 10 feet of storm drains. Do not apply within 25 feet of aquatic habitats (such as, but not limited to, lakes; reservoirs; rivers; permanent streams; marshes or ponds; estuaries; and commercial fish farm ponds).
  - Wet season: Do not apply within 50 feet of storm drains or aquatic habitats (such as, but not limited to, lakes; reservoirs; rivers; permanent streams; marshes or ponds; estuaries; and commercial fish farm ponds) unless a vegetative buffer is present (if so, refer to dry season requirements).
  - Do not make on-grade applications when sustained wind speeds are above 10 mph (at application site) at nozzle end height.
  - Cover treatment site prior to a rain event in order to prevent run-off of the pesticide into non-target areas. The treated area should be limited to a size that can be backfilled and/or covered by the end of the work shift. Backfilling or covering of the treated area shall be done by the end of the same work shift in which the application is made.
  - The applicator must either cover the soil him/herself or provide written notification of the above requirement to the contractor on site and to the person commissioning the

Material Use WM-2

application (if different than the contractor). If notice is provided to the contractor or the person commissioning the application, then they are responsible under the Federal Insecticide Fungicide, and Rodenticide Act (FIFRA) to ensure that: 1) if the concrete slab cannot be poured over the treated soil within 24 hours of application, the treated soil is covered with a waterproof covering (such as polyethylene sheeting), and 2) the treated soil is covered if precipitation is predicted to occur before the concrete slab is scheduled to be poured.

- Do not over-apply fertilizers, herbicides, and pesticides. Prepare only the amount needed. Follow the recommended usage instructions. Over-application is expensive and environmentally harmful. Unless on steep slopes, till fertilizers into the soil rather than hydraulic application. Apply surface dressings in several smaller applications, as opposed to one large application, to allow time for infiltration and to avoid excess material being carried offsite by runoff. Do not apply these chemicals before predicted rainfall.
- Train employees and subcontractors in proper material use.
- Supply Material Safety Data Sheets (MSDS) for all materials.
- Dispose of latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths, when thoroughly dry and are no longer hazardous, with other construction debris.
- Do not remove the original product label; it contains important safety and disposal information. Use the entire product before disposing of the container.
- Mix paint indoors or in a containment area. Never clean paintbrushes or rinse paint containers into a street, gutter, storm drain, or watercourse. Dispose of any paint thinners, residue, and sludge(s) that cannot be recycled, as hazardous waste.
- For water-based paint, clean brushes to the extent practicable, and rinse to a drain leading to a sanitary sewer where permitted, or contain for proper disposal off site. For oil-based paints, clean brushes to the extent practicable, and filter and reuse thinners and solvents.
- Use recycled and less hazardous products when practical. Recycle residual paints, solvents, non-treated lumber, and other materials.
- Use materials only where and when needed to complete the construction activity. Use safer alternative materials as much as possible. Reduce or eliminate use of hazardous materials onsite when practical.
- Document the location, time, chemicals applied, and applicator's name and qualifications.
- Keep an ample supply of spill clean up material near use areas. Train employees in spill clean up procedures.
- Avoid exposing applied materials to rainfall and runoff unless sufficient time has been allowed for them to dry.
- Discontinue use of erodible landscape material within 2 days prior to a forecasted rain event and materials should be covered and/or bermed.

 Provide containment for material use areas such as masons' areas or paint mixing/preparation areas to prevent materials/pollutants from entering stormwater.

#### Costs

All of the above are low cost measures.

## **Inspection and Maintenance**

- Inspect and verify that activity-based BMPs are in place prior to the commencement of associated activities.
- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Ensure employees and subcontractors throughout the job are using appropriate practices.

#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.


Coastal Nonpoint Pollution Control Program: Program Development and Approval Guidance, Working Group Working Paper; USEPA, April 1992.

Comments on Risk Assessments Risk Reduction Options for Cypermethrin: Docket No. OPP-2005-0293; California Stormwater Quality Association (CASQA) letter to USEPA, 2006. Environmental Hazard and General Labeling for Pyrethroid Non-Agricultural Outdoor Products, EPA-HQ-OPP-2008-0331-0021; USEPA, 2008.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.

 $\checkmark$ 



|    | -94                  |   |
|----|----------------------|---|
| EC | Erosion Control      |   |
| SE | Sediment Control     | × |
| TC | Tracking Control     |   |
| WE | Wind Fresion Control |   |

WE Wind Erosion Control

NS Non-Stormwater
Management Control

WM Waste Management and Materials Pollution Control

#### Legend:

Categories

- ☑ Primary Category
- **☒** Secondary Category

# **Description and Purpose**

Stockpile management procedures and practices are designed to reduce or eliminate air and stormwater pollution from stockpiles of soil, soil amendments, sand, paving materials such as portland cement concrete (PCC) rubble, asphalt concrete (AC), asphalt concrete rubble, aggregate base, aggregate sub base or pre-mixed aggregate, asphalt minder (so called "cold mix" asphalt), and pressure treated wood.

## **Suitable Applications**


Implement in all projects that stockpile soil and other loose materials.

#### Limitations

- Plastic sheeting as a stockpile protection is temporary and hard to manage in windy conditions. Where plastic is used, consider use of plastic tarps with nylon reinforcement which may be more durable than standard sheeting.
- Plastic sheeting can increase runoff volume due to lack of infiltration and potentially cause perimeter control failure.
- Plastic sheeting breaks down faster in sunlight.
- The use of Plastic materials and photodegradable plastics should be avoided.

## **Implementation**

Protection of stockpiles is a year-round requirement. To properly manage stockpiles:



#### **Potential Alternatives**



- On larger sites, a minimum of 50 ft separation from concentrated flows of stormwater, drainage courses, and inlets is recommended.
- All stockpiles are required to be protected immediately if they are not scheduled to be used within 14 days.
- Protect all stockpiles from stormwater runon using temporary perimeter sediment barriers such as compost berms (SE-13), temporary silt dikes (SE-12), fiber rolls (SE-5), silt fences (SE-1), sandbags (SE-8), gravel bags (SE-6), or biofilter bags (SE-14). Refer to the individual fact sheet for each of these controls for installation information.
- Implement wind erosion control practices as appropriate on all stockpiled material. For specific information, see WE-1, Wind Erosion Control.
- Manage stockpiles of contaminated soil in accordance with WM-7, Contaminated Soil Management.
- Place bagged materials on pallets and under cover.
- Ensure that stockpile coverings are installed securely to protect from wind and rain.
- Some plastic covers withstand weather and sunlight better than others. Select cover materials or methods based on anticipated duration of use.

## Protection of Non-Active Stockpiles

Non-active stockpiles of the identified materials should be protected further as follows:

## Soil stockpiles

- Soil stockpiles should be covered or protected with soil stabilization measures and a temporary perimeter sediment barrier at all times.
- Temporary vegetation should be considered for topsoil piles that will be stockpiled for extended periods.

Stockpiles of Portland cement concrete rubble, asphalt concrete, asphalt concrete rubble, aggregate base, or aggregate sub-base

 Stockpiles should be covered and protected with a temporary perimeter sediment barrier at all times.

# Stockpiles of "cold mix"

 Cold mix stockpiles should be placed on and covered with plastic sheeting or comparable material at all times and surrounded by a berm.

Stockpiles of fly ash, stucco, hydrated lime

 Stockpiles of materials that may raise the pH of runoff (i.e., basic materials) should be covered with plastic and surrounded by a berm. Stockpiles/Storage of wood (Pressure treated with chromated copper arsenate or ammoniacal copper zinc arsenate

Treated wood should be covered with plastic sheeting or comparable material at all times and surrounded by a berm.

## Protection of Active Stockpiles

Active stockpiles of the identified materials should be protected as follows:

- All stockpiles should be covered and protected with a temporary linear sediment barrier prior to the onset of precipitation.
- Stockpiles of "cold mix" and treated wood, and basic materials should be placed on and covered with plastic sheeting or comparable material and surrounded by a berm prior to the onset of precipitation.
- The downstream perimeter of an active stockpile should be protected with a linear sediment barrier or berm and runoff should be diverted around or away from the stockpile on the upstream perimeter.

#### Costs

For cost information associated with stockpile protection refer to the individual erosion or sediment control BMP fact sheet considered for implementation (For example, refer to SE-1 Silt Fence for installation of silt fence around the perimeter of a stockpile.)

## **Inspection and Maintenance**


- Stockpiles must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- It may be necessary to inspect stockpiles covered with plastic sheeting more frequently during certain conditions (for example, high winds or extreme heat).
- Repair and/or replace perimeter controls and covers as needed to keep them functioning properly.
- Sediment shall be removed when it reaches one-third of the barrier height.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

111

# **Spill Prevention and Control**



# **Description and Purpose**

Prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees.

This best management practice covers only spill prevention and control. However, WM-1, Materials Delivery and Storage, and WM-2, Material Use, also contain useful information, particularly on spill prevention. For information on wastes, see the waste management BMPs in this section.

## **Suitable Applications**

This BMP is suitable for all construction projects. Spill control procedures are implemented anytime chemicals or hazardous substances are stored on the construction site, including the following materials:

- Soil stabilizers/binders
- **Dust palliatives**
- Herbicides
- Growth inhibitors
- **Fertilizers**
- Deicing/anti-icing chemicals

#### **Categories**

**Erosion Control** 

Sediment Control SE

TC Tracking Control

WE Wind Erosion Control Non-Stormwater

NS Management Control

Waste Management and Materials Pollution Control

 $\square$ 

#### Legend:

☑ Primary Objective

Secondary Objective

## **Targeted Constituents**

| Sediment       | $\square$ |
|----------------|-----------|
| Nutrients      |           |
| Trash          |           |
| Metals         |           |
| Bacteria       |           |
| Oil and Grease | <b></b>   |
| Organics       | abla      |
|                |           |

#### **Potential Alternatives**



- Fuels
- Lubricants
- Other petroleum distillates

#### Limitations

- In some cases it may be necessary to use a private spill cleanup company.
- This BMP applies to spills caused by the contractor and subcontractors.
- Procedures and practices presented in this BMP are general. Contractor should identify appropriate practices for the specific materials used or stored onsite

## **Implementation**

The following steps will help reduce the stormwater impacts of leaks and spills:

#### **Education**

- Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills.
- Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees.
- Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

#### General Measures

- To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and wastes in covered containers and protect from vandalism.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from stormwater runon during rainfall to the extent that it doesn't compromise clean up activities.
- Do not bury or wash spills with water.

- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with WM-10, Liquid Waste Management.
- Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- Place proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- Keep waste storage areas clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

## Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent
  material for larger spills. If the spilled material is hazardous, then the used cleanup
  materials are also hazardous and must be sent to either a certified laundry (rags) or disposed
  of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

#### Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
  - Contain the spread of the spill.
  - Recover spilled materials.
  - Clean the contaminated area and properly dispose of contaminated materials.

## Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

- Spills should be cleaned up immediately:
  - Contain spread of the spill.
  - Notify the project foreman immediately.
  - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
  - If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
  - If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

## Significant/Hazardous Spills

- For significant or hazardous spills that cannot be controlled by personnel in the immediate vicinity, the following steps should be taken:
  - Notify the local emergency response by dialing 911. In addition to 911, the contractor will notify the proper county officials. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
  - Notify the Governor's Office of Emergency Services Warning Center, (916) 845-8911.
  - For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
  - Notification should first be made by telephone and followed up with a written report.
  - The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
  - Other agencies which may need to be consulted include, but are not limited to, the Fire Department, the Public Works Department, the Coast Guard, the Highway Patrol, the City/County Police Department, Department of Toxic Substances, California Division of Oil and Gas, Cal/OSHA, etc.

#### Reporting

- Report significant spills to local agencies, such as the Fire Department; they can assist in cleanup.
- Federal regulations require that any significant oil spill into a water body or onto an adjoining shoreline be reported to the National Response Center (NRC) at 800-424-8802 (24 hours).

Use the following measures related to specific activities:

## Vehicle and Equipment Maintenance

- If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- Place drip pans or absorbent materials under paving equipment when not in use.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
   Remove the absorbent materials promptly and dispose of properly.
- Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around
- Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal.
   Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Vehicle and Equipment Fueling

- If fueling must occur onsite, use designate areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- Discourage "topping off" of fuel tanks.
- Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.

#### Costs

Prevention of leaks and spills is inexpensive. Treatment and/ or disposal of contaminated soil or water can be quite expensive.

#### **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.

- Keep ample supplies of spill control and cleanup materials onsite, near storage, unloading, and maintenance areas.
- Update your spill prevention and control plan and stock cleanup materials as changes occur
  in the types of chemicals onsite.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.

# **Solid Waste Management**



## **Description and Purpose**

Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training employees and subcontractors.

## **Suitable Applications**

This BMP is suitable for construction sites where the following wastes are generated or stored:

- Solid waste generated from trees and shrubs removed during land clearing, demolition of existing structures (rubble), and building construction
- Packaging materials including wood, paper, and plastic
- Scrap or surplus building materials including scrap metals, rubber, plastic, glass pieces and masonry products
- Domestic wastes including food containers such as beverage cans, coffee cups, paper bags, plastic wrappers, and cigarettes
- Construction wastes including brick, mortar, timber, steel and metal scraps, pipe and electrical cuttings, nonhazardous equipment parts, styrofoam and other materials used to transport and package construction materials
- Highway planting wastes, including vegetative material,

## **Categories**

| EC  | Erosion Control                                     |   |
|-----|---|---|
| SE  | Sediment Control                                    |   |
| TC  | Tracking Control                                    |   |
| WE  | Wind Erosion Control                                |   |
| N\$ | Non-Stormwater<br>Management Control                |   |
| WM  | Waste Management and<br>Materials Pollution Control | 囟 |

#### Legend:

- Primary Objective
- Secondary Objective

## Targeted Constituents

|   | rargetta constituent | _              |
|---|----------------------|----------------|
| , | Sediment             | V              |
|   | Nutrients            | $\mathbf{Y}$   |
|   | Trash                | ✓              |
|   | Metals               | abla           |
|   | Bacteria             |                |
|   | Oil and Grease       | abla           |
|   | Organics             | $ \mathbf{V} $ |
|   |                      |                |

#### **Potential Alternatives**



plant containers, and packaging materials

#### Limitations

Temporary stockpiling of certain construction wastes may not necessitate stringent drainage related controls during the non-rainy season or in desert areas with low rainfall.

## **Implementation**

The following steps will help keep a clean site and reduce stormwater pollution:

- Select designated waste collection areas onsite.
- Inform trash-hauling contractors that you will accept only watertight dumpsters for onsite
  use. Inspect dumpsters for leaks and repair any dumpster that is not watertight.
- Locate containers in a covered area or in a secondary containment.
- Provide an adequate number of containers with lids or covers that can be placed over the container to keep rain out or to prevent loss of wastes when it is windy.
- Plan for additional containers and more frequent pickup during the demolition phase of construction.
- Collect site trash daily, especially during rainy and windy conditions.
- Remove this solid waste promptly since erosion and sediment control devices tend to collect litter.
- Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acids, pesticides, additives, curing compounds) are not disposed of in dumpsters designated for construction debris.
- Do not hose out dumpsters on the construction site. Leave dumpster cleaning to the trash hauling contractor.
- Arrange for regular waste collection before containers overflow.
- Clean up immediately if a container does spill.
- Make sure that construction waste is collected, removed, and disposed of only at authorized disposal areas.

#### Education

- Have the contractor's superintendent or representative oversee and enforce proper solid waste management procedures and practices.
- Instruct employees and subcontractors on identification of solid waste and hazardous waste.
- Educate employees and subcontractors on solid waste storage and disposal procedures.
- Hold regular meetings to discuss and reinforce disposal procedures (incorporate into regular safety meetings).

- Require that employees and subcontractors follow solid waste handling and storage procedures.
- Prohibit littering by employees, subcontractors, and visitors.
- Minimize production of solid waste materials wherever possible.

## Collection, Storage, and Disposal

- Littering on the project site should be prohibited.
- To prevent clogging of the storm drainage system, litter and debris removal from drainage grates, trash racks, and ditch lines should be a priority.
- Trash receptacles should be provided in the contractor's yard, field trailer areas, and at locations where workers congregate for lunch and break periods.
- Litter from work areas within the construction limits of the project site should be collected and placed in watertight dumpsters at least weekly, regardless of whether the litter was generated by the contractor, the public, or others. Collected litter and debris should not be placed in or next to drain inlets, stormwater drainage systems, or watercourses.
- Dumpsters of sufficient size and number should be provided to contain the solid waste generated by the project.
- Full dumpsters should be removed from the project site and the contents should be disposed of by the trash hauling contractor.
- Construction debris and waste should be removed from the site biweekly or more frequently as needed.
- Construction material visible to the public should be stored or stacked in an orderly manner.
- Stormwater runon should be prevented from contacting stored solid waste through the use
  of berms, dikes, or other temporary diversion structures or through the use of measures to
  elevate waste from site surfaces.
- Solid waste storage areas should be located at least 50 ft from drainage facilities and watercourses and should not be located in areas prone to flooding or ponding.
- Except during fair weather, construction and highway planting waste not stored in watertight dumpsters should be securely covered from wind and rain by covering the waste with tarps or plastic.
- Segregate potentially hazardous waste from non-hazardous construction site waste.
- Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acids, pesticides, additives, curing compounds) are not disposed of in dumpsters designated for construction debris.
- For disposal of hazardous waste, see WM-6, Hazardous Waste Management. Have hazardous waste hauled to an appropriate disposal and/or recycling facility.

Salvage or recycle useful vegetation debris, packaging and surplus building materials when
practical. For example, trees and shrubs from land clearing can be used as a brush barrier,
or converted into wood chips, then used as mulch on graded areas. Wood pallets, cardboard
boxes, and construction scraps can also be recycled.

#### Costs

All of the above are low cost measures.

## **Inspection and Maintenance**


- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur
- Inspect construction waste area regularly.
- Arrange for regular waste collection.

#### References

Processes, Procedures and Methods to Control Pollution Resulting from All Construction Activity, 430/9-73-007, USEPA, 1973.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



# **Description and Purpose**

Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

# **Suitable Applications**

This best management practice (BMP) applies to all construction projects. Hazardous waste management practices are implemented on construction projects that generate waste from the use of:

| T      | •    | T 1  |      |
|--------|------|------|------|
| Petro? | leum | Prod | ucts |

- Asphalt Products

- Concrete Curing Compounds

- Pesticides

- Palliatives

- Acids

- Septic Wastes

- Paints

Stains

Solvents

Wood Preservatives

- Roofing Tar

Any materials deemed a hazardous waste in California,
 Title 22 Division 4.5, or listed in 40 CFR Parts 110, 117,
 261, or 302

## Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Eroslon Control

Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

 $\square$ 

## Legend:

Primary Objective

☑ Secondary Objective

## **Targeted Constituents**

| Sediment       |   |
|----------------|---|
| Nutrients      | ✓ |
| Trash          | Z |
| Metals         | ₹ |
| Bacteria       | V |
| Oil and Grease | ☑ |
| Organics       | V |
|                |   |

#### **Potential Alternatives**



In addition, sites with existing structures may contain wastes, which must be disposed of in accordance with federal, state, and local regulations. These wastes include:

- Sandblasting grit mixed with lead-, cadmium-, or chromium-based paints
- Asbestos
- PCBs (particularly in older transformers)

#### Limitations

- Hazardous waste that cannot be reused or recycled must be disposed of by a licensed hazardous waste hauler.
- Nothing in this BMP relieves the contractor from responsibility for compliance with federal, state, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.
- This BMP does not cover aerially deposited lead (ADL) soils. For ADL soils refer to WM-7, Contaminated Soil Management.

## **Implementation**

The following steps will help reduce stormwater pollution from hazardous wastes:

#### Material Use

- Wastes should be stored in sealed containers constructed of a suitable material and should be labeled as required by Title 22 CCR, Division 4.5 and 49 CFR Parts 172, 173, 178, and 179.
- All hazardous waste should be stored, transported, and disposed as required in Title 22 CCR, Division 4.5 and 49 CFR 261-263.
- Waste containers should be stored in temporary containment facilities that should comply with the following requirements:
  - Temporary containment facility should provide for a spill containment volume equal to 1.5 times the volume of all containers able to contain precipitation from a 25 year storm event, plus the greater of 10% of the aggregate volume of all containers or 100% of the capacity of the largest tank within its boundary, whichever is greater.
  - Temporary containment facility should be impervious to the materials stored there for a minimum contact time of 72 hours.
  - Temporary containment facilities should be maintained free of accumulated rainwater and spills. In the event of spills or leaks, accumulated rainwater and spills should be placed into drums after each rainfall. These liquids should be handled as a hazardous waste unless testing determines them to be non-hazardous. Non-hazardous liquids should be sent to an approved disposal site.
  - Sufficient separation should be provided between stored containers to allow for spill cleanup and emergency response access.

- Incompatible materials, such as chlorine and ammonia, should not be stored in the same temporary containment facility.
- Throughout the rainy season, temporary containment facilities should be covered during non-working days, and prior to rain events. Covered facilities may include use of plastic tarps for small facilities or constructed roofs with overhangs.
- Drums should not be overfilled and wastes should not be mixed.
- Unless watertight, containers of dry waste should be stored on pallets.
- Do not over-apply herbicides and pesticides. Prepare only the amount needed. Follow the recommended usage instructions. Over application is expensive and environmentally harmful. Apply surface dressings in several smaller applications, as opposed to one large application. Allow time for infiltration and avoid excess material being carried offsite by runoff. Do not apply these chemicals just before it rains. People applying pesticides must be certified in accordance with federal and state regulations.
- Paint brushes and equipment for water and oil based paints should be cleaned within a contained area and should not be allowed to contaminate site soils, watercourses, or drainage systems. Waste paints, thinners, solvents, residues, and sludges that cannot be recycled or reused should be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths should be disposed of as solid waste.
- Do not clean out brushes or rinse paint containers into the dirt, street, gutter, storm drain, or stream. "Paint out" brushes as much as possible. Rinse water-based paints to the sanitary sewer. Filter and reuse thinners and solvents. Dispose of excess oil-based paints and sludge as hazardous waste.
- The following actions should be taken with respect to temporary contaminant:
  - Ensure that adequate hazardous waste storage volume is available.
  - Ensure that hazardous waste collection containers are conveniently located.
  - Designate hazardous waste storage areas onsite away from storm drains or watercourses and away from moving vehicles and equipment to prevent accidental spills.
  - Minimize production or generation of hazardous materials and hazardous waste on the job site.
  - Use containment berms in fueling and maintenance areas and where the potential for spills is high.
  - Segregate potentially hazardous waste from non-hazardous construction site debris.
  - Keep liquid or semi-liquid hazardous waste in appropriate containers (closed drums or similar) and under cover.

- Clearly label all hazardous waste containers with the waste being stored and the date of accumulation.
- Place hazardous waste containers in secondary containment.
- Do not allow potentially hazardous waste materials to accumulate on the ground.
- Do not mix wastes.
- Use all of the product before disposing of the container.
- Do not remove the original product label; it contains important safety and disposal information.

## Waste Recycling Disposal

- Select designated hazardous waste collection areas onsite.
- Hazardous materials and wastes should be stored in covered containers and protected from vandalism.
- Place hazardous waste containers in secondary containment.
- Do not mix wastes, this can cause chemical reactions, making recycling impossible and complicating disposal.
- Recycle any useful materials such as used oil or water-based paint.
- Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acids, pesticides, additives, curing compounds) are not disposed of in dumpsters designated for construction debris.
- Arrange for regular waste collection before containers overflow.
- Make sure that hazardous waste (e.g., excess oil-based paint and sludge) is collected, removed, and disposed of only at authorized disposal areas.

## Disposal Procedures

- Waste should be disposed of by a licensed hazardous waste transporter at an authorized and licensed disposal facility or recycling facility utilizing properly completed Uniform Hazardous Waste Manifest forms.
- A Department of Health Services certified laboratory should sample waste to determine the appropriate disposal facility.
- Properly dispose of rainwater in secondary containment that may have mixed with hazardous waste.
- Attention is directed to "Hazardous Material", "Contaminated Material", and "Aerially Deposited Lead" of the contract documents regarding the handling and disposal of hazardous materials.

# **Hazardous Waste Management**

#### Education

- Educate employees and subcontractors on hazardous waste storage and disposal procedures.
- Educate employees and subcontractors on potential dangers to humans and the environment from hazardous wastes.
- Instruct employees and subcontractors on safety procedures for common construction site hazardous wastes.
  - Instruct employees and subcontractors in identification of hazardous and solid waste.
  - Hold regular meetings to discuss and reinforce hazardous waste management procedures (incorporate into regular safety meetings).
  - The contractor's superintendent or representative should oversee and enforce proper hazardous waste management procedures and practices.
  - Make sure that hazardous waste is collected, removed, and disposed of only at authorized disposal areas.
  - Warning signs should be placed in areas recently treated with chemicals.
  - Place a stockpile of spill cleanup materials where it will be readily accessible.
  - If a container does spill, clean up immediately.

#### Costs

All of the above are low cost measures.

#### Inspection and Maintenance

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur
- Hazardous waste should be regularly collected.
- A foreman or construction supervisor should monitor onsite hazardous waste storage and disposal procedures.
- Waste storage areas should be kept clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored.
- Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.
- Hazardous spills should be cleaned up and reported in conformance with the applicable
   Material Safety Data Sheet (MSDS) and the instructions posted at the project site.

111

- The National Response Center, at (800) 424-8802, should be notified of spills of federal reportable quantities in conformance with the requirements in 40 CFR parts 110, 117, and 302. Also notify the Governors Office of Emergency Services Warning Center at (916) 845-8911.
- A copy of the hazardous waste manifests should be provided.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Processes, Procedures and Methods to Control Pollution Resulting from All Construction Activity, 430/9-73-007, USEPA, 1973.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



## Categories

| EC   | Erosion Control                      |   |
|------|--------------------------------------|---|
| SE   | Sediment Control                     |   |
| TC   | Tracking Control                     |   |
| WE   | Wind Erosion Control                 |   |
| NS   | Non-Stormwater<br>Management Control |   |
| 1484 | Waste Management and                 | - |

Materials Pollution Control

#### Legend:

- ☑ Primary Objective
- ☑ Secondary Objective

# **Description and Purpose**

Prevent or reduce the discharge of pollutants to stormwater from contaminated soil and highly acidic or alkaline soils by conducting pre-construction surveys, inspecting excavations regularly, and remediating contaminated soil promptly.

## Suitable Applications

Contaminated soil management is implemented on construction projects in highly urbanized or industrial areas where soil contamination may have occurred due to spills, illicit discharges, aerial deposition, past use and leaks from underground storage tanks.


#### Limitations

Contaminated soils that cannot be treated onsite must be disposed of offsite by a licensed hazardous waste hauler. The presence of contaminated soil may indicate contaminated water as well. See NS-2, Dewatering Operations, for more information.

The procedures and practices presented in this BMP are general. The contractor should identify appropriate practices and procedures for the specific contaminants known to exist or discovered onsite.

#### **Implementation**

Most owners and developers conduct pre-construction environmental assessments as a matter of routine. Contaminated soils are often identified during project planning and development with known locations identified in the plans, specifications and in the SWPPP. The contractor should review applicable reports and investigate appropriate call-outs in the



#### **Potential Alternatives**



# Contaminated Soil Management W

plans, specifications, and SWPPP. Recent court rulings holding contractors liable for cleanup costs when they unknowingly move contaminated soil highlight the need for contractors to confirm a site assessment is completed before earth moving begins.

The following steps will help reduce stormwater pollution from contaminated soil:

- Conduct thorough, pre-construction inspections of the site and review documents related to the site. If inspection or reviews indicated presence of contaminated soils, develop a plan before starting work.
- Look for contaminated soil as evidenced by discoloration, odors, differences in soil properties, abandoned underground tanks or pipes, or buried debris.
- Prevent leaks and spills. Contaminated soil can be expensive to treat and dispose of properly. However, addressing the problem before construction is much less expensive than after the structures are in place.
- The contractor may further identify contaminated soils by investigating:
  - Past site uses and activities
  - Detected or undetected spills and leaks
  - Acid or alkaline solutions from exposed soil or rock formations high in acid or alkaline forming elements
  - Contaminated soil as evidenced by discoloration, odors, differences in soil properties, abandoned underground tanks or pipes, or buried debris.
  - Suspected soils should be tested at a certified laboratory.

## Education

- Have employees and subcontractors complete a safety training program which meets 29 CFR 1910.120 and 8 CCR 5192 covering the potential hazards as identified, prior to performing any excavation work at the locations containing material classified as hazardous.
- Educate employees and subcontractors in identification of contaminated soil and on contaminated soil handling and disposal procedures.
- Hold regular meetings to discuss and reinforce disposal procedures (incorporate into regular safety meetings).

#### Handling Procedures for Material with Aerially Deposited Lead (ADL)

- Materials from areas designated as containing (ADL) may, if allowed by the contract special provisions, be excavated, transported, and used in the construction of embankments and/or backfill.
- Excavation, transportation, and placement operations should result in no visible dust.
- Caution should be exercised to prevent spillage of lead containing material during transport.

# Contaminated Soil Management WM-7

Quality should be monitored during excavation of soils contaminated with lead.

## Handling Procedures for Contaminated Soils

- Minimize onsite storage. Contaminated soil should be disposed of properly in accordance with all applicable regulations. All hazardous waste storage will comply with the requirements in Title 22, CCR, Sections 66265,250 to 66265,260.
- Test suspected soils at an approved certified laboratory.
- Work with the local regulatory agencies to develop options for treatment or disposal if the soil is contaminated.
- Avoid temporary stockpiling of contaminated soils or hazardous material.
- Take the following precautions if temporary stockpiling is necessary:
  - Cover the stockpile with plastic sheeting or tarps.
  - Install a berm around the stockpile to prevent runoff from leaving the area.
  - Do not stockpile in or near storm drains or watercourses.
- Remove contaminated material and hazardous material on exteriors of transport vehicles and place either into the current transport vehicle or into the excavation prior to the vehicle leaving the exclusion zone.
- Monitor the air quality continuously during excavation operations at all locations containing hazardous material.
- Procure all permits and licenses, pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work, including registration for transporting vehicles carrying the contaminated material and the hazardous material.
- Collect water from decontamination procedures and treat or dispose of it at an appropriate disposal site.
- Collect non-reusable protective equipment, once used by any personnel, and dispose of at an appropriate disposal site.
- Install temporary security fence to surround and secure the exclusion zone. Remove fencing when no longer needed.
- Excavate, transport, and dispose of contaminated material and hazardous material in accordance with the rules and regulations of the following agencies (the specifications of these agencies supersede the procedures outlined in this BMP):
  - United States Department of Transportation (USDOT)
  - United States Environmental Protection Agency (USEPA)
  - California Environmental Protection Agency (CAL-EPA)

13 ...

# **Contaminated Soil Management**

- WM-7
- California Division of Occupation Safety and Health Administration (CAL-OSHA)
- Local regulatory agencies

## Procedures for Underground Storage Tank Removals

- Prior to commencing tank removal operations, obtain the required underground storage tank removal permits and approval from the federal, state, and local agencies that have jurisdiction over such work.
- To determine if it contains hazardous substances, arrange to have tested, any liquid or sludge found in the underground tank prior to its removal.
- Following the tank removal, take soil samples beneath the excavated tank and perform analysis as required by the local agency representative(s).
- The underground storage tank, any liquid or sludge found within the tank, and all contaminated substances and hazardous substances removed during the tank removal and transported to disposal facilities permitted to accept such waste.

#### Water Control

- All necessary precautions and preventive measures should be taken to prevent the flow of water, including ground water, from mixing with hazardous substances or underground storage tank excavations. Such preventative measures may consist of, but are not limited to, berms, cofferdams, grout curtains, freeze walls, and seal course concrete or any combination thereof.
- If water does enter an excavation and becomes contaminated, such water, when necessary to proceed with the work, should be discharged to clean, closed top, watertight transportable holding tanks, treated, and disposed of in accordance with federal, state, and local laws.

#### Costs

Prevention of leaks and spills is inexpensive. Treatment or disposal of contaminated soil can be quite expensive.

#### **Inspection and Maintenance**

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Arrange for contractor's Water Pollution Control Manager, foreman, and/or construction supervisor to monitor onsite contaminated soil storage and disposal procedures.
- Monitor air quality continuously during excavation operations at all locations containing hazardous material.
- Coordinate contaminated soils and hazardous substances/waste management with the appropriate federal, state, and local agencies.

# Contaminated Soil Management WM-7

■ Implement WM-4, Spill Prevention and Control, to prevent leaks and spills as much as possible.


#### References

Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Processes, Procedures and Methods to Control Pollution Resulting from All Construction Activity, 430/9-73-007, USEPA, 1973.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



| EC | Erosion Control      |
|----|----------------------|
| SE | Sediment Control     |
| TC | Tracking Control     |
| WE | Wind Erosion Control |
|    |                      |

Non-Stormwater NS X Management Control Waste Management and  $\square$ 

Materials Pollution Control

#### Legend:

Categories

Primary Category

Secondary Category

## **Description and Purpose**

Prevent the discharge of pollutants to stormwater from concrete waste by conducting washout onsite or offsite in a designated area, and by employee and subcontractor training.

The General Permit incorporates Numeric Effluent Limits (NEL) and Numeric Action Levels (NAL) for pH (see Section 2 of this handbook to determine your project's risk level and if you are subject to these requirements).

Many types of construction materials, including mortar, concrete, stucco, cement and block and their associated wastes have basic chemical properties that can raise pH levels outside of the permitted range. Additional care should be taken when managing these materials to prevent them from coming into contact with stormwater flows and raising pH to levels outside the accepted range.

## Suitable Applications

Concrete waste management procedures and practices are implemented on construction projects where:

- Concrete is used as a construction material or where concrete dust and debris result from demolition activities.
- Slurries containing portland cement concrete (PCC) are generated, such as from saw cutting, coring, grinding, grooving, and hydro-concrete demolition.

| _ | Targeted Constituents |           |
|---|-----------------------|-----------|
| _ | Sediment              | Ø         |
|   | Nutrients             |           |
|   | Trash                 |           |
|   | Metals                | $\square$ |
|   | Bacteria              |           |
|   | Oil and Grease        |           |
|   | Organics              |           |

#### **Potential Alternatives**



- Concrete trucks and other concrete-coated equipment are washed onsite.
- Mortar-mixing stations exist.
- Stucco mixing and spraying.
- See also NS-8, Vehicle and Equipment Cleaning.

#### Limitations

- Offsite washout of concrete wastes may not always be possible.
- Multiple washouts may be needed to assure adequate capacity and to allow for evaporation.

## **Implementation**

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Store dry and wet materials under cover, away from drainage areas. Refer to WM-1, Material Delivery and Storage for more information.
- Avoid mixing excess amounts of concrete.
- Perform washout of concrete trucks in designated areas only, where washout will not reach stormwater.
- Do not wash out concrete trucks into storm drains, open ditches, streets, streams or onto the ground. Trucks should always be washed out into designated facilities.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:
  - On larger sites, it is recommended to locate washout areas at least 50 feet from storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
  - Washout wastes into the temporary washout where the concrete can set, be broken up, and then disposed properly.
  - Washout should be lined so there is no discharge into the underlying soil.
- Do not wash sweepings from exposed aggregate concrete into the street or storm drain. Collect and return sweepings to aggregate base stockpile or dispose in the trash.
- See typical concrete washout installation details at the end of this fact sheet.

#### Education

■ Educate employees, subcontractors, and suppliers on the concrete waste management techniques described herein.

- Arrange for contractor's superintendent or representative to oversee and enforce concrete waste management procedures.
- Discuss the concrete management techniques described in this BMP (such as handling of concrete waste and washout) with the ready-mix concrete supplier before any deliveries are made.

### Concrete Demolition Wastes

- Stockpile concrete demolition waste in accordance with BMP WM-3, Stockpile Management.
- Dispose of or recycle hardened concrete waste in accordance with applicable federal, state or local regulations.

### Concrete Slurry Wastes

- PCC and AC waste should not be allowed to enter storm drains or watercourses.
- PCC and AC waste should be collected and disposed of or placed in a temporary concrete washout facility (as described in Onsite Temporary Concrete Washout Facility, Concrete Transit Truck Washout Procedures, below).
- A foreman or construction supervisor should monitor onsite concrete working tasks, such as saw cutting, coring, grinding and grooving to ensure proper methods are implemented.
- Saw-cut concrete slurry should not be allowed to enter storm drains or watercourses. Residue from grinding operations should be picked up by means of a vacuum attachment to the grinding machine or by sweeping. Saw cutting residue should not be allowed to flow across the pavement and should not be left on the surface of the pavement. See also NS-3, Paving and Grinding Operations; and WM-10, Liquid Waste Management.
- Concrete slurry residue should be disposed in a temporary washout facility (as described in Onsite Temporary Concrete Washout Facility, Concrete Transit Truck Washout Procedures, below) and allowed to dry. Dispose of dry slurry residue in accordance with WM-5, Solid Waste Management.

### Onsite Temporary Concrete Washout Facility, Transit Truck Washout Procedures

- Temporary concrete washout facilities should be located a minimum of 50 ft from storm drain inlets, open drainage facilities, and watercourses. Each facility should be located away from construction traffic or access areas to prevent disturbance or tracking.
- A sign should be installed adjacent to each washout facility to inform concrete equipment operators to utilize the proper facilities.
- Temporary concrete washout facilities should be constructed above grade or below grade at the option of the contractor. Temporary concrete washout facilities should be constructed and maintained in sufficient quantity and size to contain all liquid and concrete waste generated by washout operations.

### **Concrete Waste Management**

- Temporary washout facilities should have a temporary pit or bermed areas of sufficient volume to completely contain all liquid and waste concrete materials generated during washout procedures.
- Temporary washout facilities should be lined to prevent discharge to the underlying ground or surrounding area.
- Washout of concrete trucks should be performed in designated areas only.
- Only concrete from mixer truck chutes should be washed into concrete wash out.
- Concrete washout from concrete pumper bins can be washed into concrete pumper trucks and discharged into designated washout area or properly disposed of or recycled offsite.
- Once concrete wastes are washed into the designated area and allowed to harden, the concrete should be broken up, removed, and disposed of per WM-5, Solid Waste Management. Dispose of or recycle hardened concrete on a regular basis.
- Temporary Concrete Washout Facility (Type Above Grade)
  - Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this BMP, with a recommended minimum length and minimum width of 10 ft; however, smaller sites or jobs may only need a smaller washout facility. With any washout, always maintain a sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations.
  - Materials used to construct the washout area should conform to the provisions detailed in their respective BMPs (e.g., SE-8 Sandbag Barrier).
  - Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.
  - Alternatively, portable removable containers can be used as above grade concrete washouts. Also called a "roll-off"; this concrete washout facility should be properly sealed to prevent leakage, and should be removed from the site and replaced when the container reaches 75% capacity.
- Temporary Concrete Washout Facility (Type Below Grade)
  - Temporary concrete washout facilities (type below grade) should be constructed as shown on the details at the end of this BMP, with a recommended minimum length and minimum width of 10 ft. The quantity and volume should be sufficient to contain all liquid and concrete waste generated by washout operations.
  - Lath and flagging should be commercial type.
  - Plastic lining material should be a minimum of 10 mil polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

- The base of a washout facility should be free of rock or debris that may damage a plastic liner.

### Removal of Temporary Concrete Washout Facilities

- When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and properly disposed or recycled in accordance with federal, state or local regulations. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and properly disposed or recycled in accordance with federal, state or local regulations..
- Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.

#### Costs

All of the above are low cost measures. Roll-off concrete washout facilities can be more costly than other measures due to removal and replacement; however, provide a cleaner alternative to traditional washouts. The type of washout facility, size, and availability of materials will determine the cost of the washout.

### **Inspection and Maintenance**


- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Temporary concrete washout facilities should be maintained to provide adequate holding capacity with a minimum freeboard of 4 in. for above grade facilities and 12 in. for below grade facilities. Maintaining temporary concrete washout facilities should include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials should be removed and properly disposed or recycled in accordance with federal, state or local regulations.
- Washout facilities must be cleaned, or new facilities must be constructed and ready for use once the washout is 75% full.
- Inspect washout facilities for damage (e.g. torn liner, evidence of leaks, signage, etc.). Repair all identified damage.


#### References


Blueprint for a Clean Bay: Best Management Practices to Prevent Stormwater Pollution from Construction Related Activities; Santa Clara Valley Nonpoint Source Pollution Control Program, 1995.

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000, Updated March 2003.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.










#### NOTES

- 1. ACTUAL LAYOUT DETERMINED IN FIELD.
- 2. THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 30 FT. OF THE TEMPORARY CONCRETE WASHOUT FACILITY.





### Sanitary/Septic Waste Management WM-9



### **Description and Purpose**

Proper sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and arranging for regular service and disposal.

### **Suitable Applications**

Sanitary septic waste management practices are suitable for use at all construction sites that use temporary or portable sanitary and septic waste systems.

### Limitations

None identified.

### **Implementation**

Sanitary or septic wastes should be treated or disposed of in accordance with state and local requirements. In many cases, one contract with a local facility supplier will be all that it takes to make sure sanitary wastes are properly disposed.

### Storage and Disposal Procedures

Temporary sanitary facilities should be located away from drainage facilities, watercourses, and from traffic circulation. If site conditions allow, place portable facilities a minimum of 50 feet from drainage conveyances and traffic areas. When subjected to high winds or risk of high winds, temporary sanitary facilities should be secured to prevent overturning.

### Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

NS Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

Ø

### Legend:

☑ Primary Category

Secondary Category

### **Targeted Constituents**

Sediment
Nutrients

Trash

Metals

Bacteria

Oil and Grease

Organics

#### **Potential Alternatives**

None



### Sanitary/Septic Waste Management WM-9

- Temporary sanitary facilities must be equipped with containment to prevent discharge of pollutants to the stormwater drainage system of the receiving water.
- Consider safety as well as environmental implications before placing temporary sanitary facilities.
- Wastewater should not be discharged or buried within the project site.
- Sanitary and septic systems that discharge directly into sanitary sewer systems, where permissible, should comply with the local health agency, city, county, and sewer district requirements.
- Only reputable, licensed sanitary and septic waste haulers should be used.
- Sanitary facilities should be located in a convenient location.
- Temporary septic systems should treat wastes to appropriate levels before discharging.
- If using an onsite disposal system (OSDS), such as a septic system, local health agency requirements must be followed.
- Temporary sanitary facilities that discharge to the sanitary sewer system should be properly connected to avoid illicit discharges.
- Sanitary and septic facilities should be maintained in good working order by a licensed service.
- Regular waste collection by a licensed hauler should be arranged before facilities overflow.
- If a spill does occur from a temporary sanitary facility, follow federal, state and local regulations for containment and clean-up.

### Education

- Educate employees, subcontractors, and suppliers on sanitary and septic waste storage and disposal procedures.
- Educate employees, subcontractors, and suppliers of potential dangers to humans and the environment from sanitary and septic wastes.
- Instruct employees, subcontractors, and suppliers in identification of sanitary and septic waste.
- Hold regular meetings to discuss and reinforce the use of sanitary facilities (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees.

### Costs

All of the above are low cost measures.

### Sanitary/Septic Waste Management WM-9


### **Inspection and Maintenance**

- BMPs must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
- Arrange for regular waste collection.
- If high winds are expected, portable sanitary facilities must be secured with spikes or weighed down to prevent over turning.
- If spills or leaks from sanitary or septic facilities occur that are not contained and discharge from the site, non-visible sampling of site discharge may be required. Refer to the General Permit or to your project specific Construction Site Monitoring Plan to determine if and where sampling is required.

#### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.

Stormwater Management for Construction Activities; Developing Pollution Prevention Plans and Best Management Practice, EPA 832-R-92005; USEPA, April 1992.



### **Categories**

| EC | Erosion Control                                     |   |
|----|---|---|
| SE | Sediment Control                                    |   |
| TC | Tracking Control                                    |   |
| WE | Wind Erosion Control                                |   |
| NS | Non-Stormwater<br>Management Control                |   |
| WM | Waste Management and<br>Materials Pollution Control | V |

#### Legend:

| V | Primary | Objective |
|---|---------|-----------|
|   |         |           |

### ■ Secondary Objective

### **Description and Purpose**

Liquid waste management includes procedures and practices to prevent discharge of pollutants to the storm drain system or to watercourses as a result of the creation, collection, and disposal of non-hazardous liquid wastes.

### **Suitable Applications**

Liquid waste management is applicable to construction projects that generate any of the following non-hazardous by-products, residuals, or wastes:

- Drilling slurries and drilling fluids
- Grease-free and oil-free wastewater and rinse water
- **Dredgings**
- Other non-stormwater liquid discharges not permitted by separate permits

### Limitations

- Disposal of some liquid wastes may be subject to specific laws and regulations or to requirements of other permits secured for the construction project (e.g., NPDES permits, Army Corps permits, Coastal Commission permits, etc.).
- Liquid waste management does not apply to dewatering operations (NS-2 Dewatering Operations), solid waste management (WM-5, Solid Waste Management), hazardous wastes (WM-6, Hazardous Waste Management), or concrete slurry residue (WM-8, Concrete Waste

#### Sediment $\square$ $\square$ Nutrients ablaTrash $\square$ Metals Bacteria

 $\square$ 

**Targeted Constituents** 

### **Potential Alternatives**

None

Oil and Grease

**Organics** 



Management).

Typical permitted non-stormwater discharges can include: water line flushing; landscape irrigation; diverted stream flows; rising ground waters; uncontaminated pumped ground water; discharges from potable water sources; foundation drains; irrigation water; springs; water from crawl space pumps; footing drains; lawn watering; flows from riparian habitats and wetlands; and discharges or flows from emergency fire fighting activities.

### **Implementation**

### General Practices

- Instruct employees and subcontractors how to safely differentiate between non-hazardous liquid waste and potential or known hazardous liquid waste.
- Instruct employees, subcontractors, and suppliers that it is unacceptable for any liquid waste to enter any storm drainage device, waterway, or receiving water.
- Educate employees and subcontractors on liquid waste generating activities and liquid waste storage and disposal procedures.
- Hold regular meetings to discuss and reinforce disposal procedures (incorporate into regular safety meetings).
- Verify which non-stormwater discharges are permitted by the statewide NPDES permit;
   different regions might have different requirements not outlined in this permit.
- Apply NS-8, Vehicle and Equipment Cleaning for managing wash water and rinse water from vehicle and equipment cleaning operations.

### Containing Liquid Wastes

- Drilling residue and drilling fluids should not be allowed to enter storm drains and watercourses and should be disposed of.
- If an appropriate location is available, drilling residue and drilling fluids that are exempt under Title 23, CCR § 2511(g) may be dried by infiltration and evaporation in a containment facility constructed in conformance with the provisions concerning the Temporary Concrete Washout Facilities detailed in WM-8, Concrete Waste Management.
- Liquid wastes generated as part of an operational procedure, such as water-laden dredged material and drilling mud, should be contained and not allowed to flow into drainage channels or receiving waters prior to treatment.
- Liquid wastes should be contained in a controlled area such as a holding pit, sediment basin, roll-off bin, or portable tank.
- Containment devices must be structurally sound and leak free.
- Containment devices must be of sufficient quantity or volume to completely contain the liquid wastes generated.

- Precautions should be taken to avoid spills or accidental releases of contained liquid wastes.
   Apply the education measures and spill response procedures outlined in WM-4, Spill Prevention and Control.
- Containment areas or devices should not be located where accidental release of the contained liquid can threaten health or safety or discharge to water bodies, channels, or storm drains.

### Capturing Liquid Wastes

- Capture all liquid wastes that have the potential to affect the storm drainage system (such as wash water and rinse water from cleaning walls or pavement), before they run off a surface.
- Do not allow liquid wastes to flow or discharge uncontrolled. Use temporary dikes or berms to intercept flows and direct them to a containment area or device for capture.
- Use a sediment trap (SE-3, Sediment Trap) for capturing and treating sediment laden liquid waste or capture in a containment device and allow sediment to settle.

### Disposing of Liquid Wastes

- A typical method to handle liquid waste is to dewater the contained liquid waste, using procedures such as described in NS-2, Dewatering Operations, and SE-2, Sediment Basin, and dispose of resulting solids per WM-5, Solid Waste Management.
- Methods of disposal for some liquid wastes may be prescribed in Water Quality Reports, NPDES permits, Environmental Impact Reports, 401 or 404 permits, and local agency discharge permits, etc. Review the SWPPP to see if disposal methods are identified.
- Liquid wastes, such as from dredged material, may require testing and certification whether it is hazardous or not before a disposal method can be determined.
- For disposal of hazardous waste, see WM-6, Hazardous Waste Management.
- If necessary, further treat liquid wastes prior to disposal. Treatment may include, though is not limited to, sedimentation, filtration, and chemical neutralization.

### Costs

Prevention costs for liquid waste management are minimal. Costs increase if cleanup or fines are involved.

#### Inspection and Maintenance

- Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly during the rainy season and of two-week intervals in the non-rainy season to verify continued BMP implementation.
- Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges occur.

- Remove deposited solids in containment areas and capturing devices as needed and at the completion of the task. Dispose of any solids as described in WM-5, Solid Waste Management.
- Inspect containment areas and capturing devices and repair as needed.

### References

Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), November 2000.

# Exhibit A-8.III Construction Inspection Form





# WATER QUALITY PROGRAM CONSTRUCTION SITE INSPECTION FORM

# FOR INSPECTION OF PRIVATE PROJECTS ISSUED GRADING & BUILDING PERMITS AND PUBLIC WORKS PROJECTS

|  |   | SECTION IN PAGE   | ENER                                  | AL  |             |   |               |             |
|--|---|---|---------------------------------------|-----|-------------|---|---------------|-------------|
| PROJECT ID:  | INSPECTOR(S):   |   |                                       |     |             |   |               |             |
| ADDRESS/TRACT:   |   |   |                                       |     |             |   | ·             |             |
| ARRIVAL TIME:  |   | DEPARTURE TIME:   |                                       |     | P           | HOTOGRAPHS TAKEN:                                 | ΠY            | □N          |
| WEATHER CONDITION:   |   |   | INSPEC                                | OIT | N DATE      | :   | <del></del>   | ·           |
| SITE PRIORITY  | HIGH PRIORITY   | H PRIORITY  |                                       |     |             | PRIORITY  |               |             |
| (Check Applicable)   | ☐ LOW PRIORITY  |   |                                       | PR  | IORITY      | UNKNOWN   |               |             |
| SEASON<br>(Check Applicable)   | ☐ WET (OCTOBER  | 1 THROUGH APRIL 30)   |                                       | DR  | Y (MAY      | 1 THROUGH SEPTEMBE                                | R 30)         |             |
| NAME OF SITE REPRESI   | ENTATIVE PRESENT (  | DURING INSPECTION:  | · · · · · · · · · · · · · · · · · · · |     |             | PHONE No:   | · <del></del> |             |
| DEVELOPMENT SIZE:  | ESTIM   | ATED % OF DISTURBED AF  | REA:                                  |     |             | THOMAS BROS. MAP/P                                | G GRID        |             |
| •  |   |   |                                       |     |             |   |               | <del></del> |
| DEVELOPER/CONTRACT   | TOR NAME  | OWI   | NER NAM                               | Æ   |             |   |               |             |
| TYPE OF CONSTRUCTION   | ·='   |   | _                                     |     |             |   | OTD LOT       |             |
|  | SIDENTIAL   | ☐ COMMERCIAL ☐ TRANSPORTATION   | _                                     | OTH | ISTRIA      | L 🔲 INFRA   | SIRUGIU       | IKE         |
|  |   |   |                                       |     |             | 71) <del>- 2</del> V77826322133421231311111313631 | OPEAUGUMUS.   |             |
| The state of the s | SECTION SECTION SECTION CONTROL P   | ON II : RESULTS   | OF IN                                 |     | PECT<br>N/A | COMMEN  | TS            |             |
| Are erosion control and active disturbe etc.), in accordance   | ls being implemented<br>d soil areas (sheetin   | l and maintained on inactiv<br>g, mulch, hay, soil stabilize<br>ediment Control Plans                         | /e                                    |     | .,,,,,      |   |               |             |
| Erosion observed?  If YES, describe the or minor.  |   | sion and whether it is maj  | or                                    |     |             |   |               |             |
|  | iment Control   |   | Y                                     | N   | N/A         | COMMEN  | TS            |             |
| significant slopes (<br>and the downstrea<br>Sediment Control F<br>Ordinance?  | silt fences, fiber rolls<br>m perimeter, in accor<br>Plans (ESCPs) and p                              | ed and maintained on all<br>etc. at the base of slopes<br>rdance with Erosion and<br>rovisions of the Grading | )                                     |     |             |   |               | ,           |
| 4. Sediment discharg  If YES, describe th  major or minor. (If habitat/endangered s  | e evidence of the dis<br>the discharge could im<br>species, an impaired wa<br>"Evaluation of Potentia | ter body (303d listed), ESA o   | r                                     |     |             |   |               |             |

|     | Tracking Controls   | ١          | r N   | N/A          | COMMENTS                                |
|-----|---|------------|-------|--------------|---|
| 5.  | Are the entrances and exits to the construction site adequately protected (tire washout, stabilized entrances, rumble strips)?                          |            |       |              |   |
|     | protected (tire washout, stabilized entrances, runible strips):   |            |       |              |   |
|     | Are roads free of sediment?   |            | -     |              |   |
| 6.  | Are roads free or sediment?   |            |       |              |   |
|     |   |            |       | {            | 1.                                      |
|     | Waste and Disposal Management   |            | / N   | N/A          | COMMENTS                                |
| 7.  | Are activities such as concrete/plastering, painting and fueling  |            | -     |              |   |
|     | resulting in a discharge to the storm drain in violation of provisions of the Water Quality Ordinance?  |            |       |              |   |
|     | If YES, describe the evidence of the discharge and whether it is major or minor.  |            |       |              |   |
| 8.  | Are containers for construction waste and debris being utilized and are they adequate?  |            |       |              |   |
|     |   |            |       |              |   |
| 9.  | Are there potential water quality problems that have been identified  |            |       |              |   |
|     | on the site, which may be in violation of provisions of the Municipal Code and may require further inspection by an Authorized Water Quality Inspector? |            |       |              |   |
| 10. | Are there any discharges or spills of sewage, oil, or toxic/hazardous   |            | +-    |              |   |
|     | materials, which may be in violation of provisions of the Municipal Code?   |            |       |              | ,                                       |
|     | If YES, go to the "Evaluation of Potential Impacts to Human or Environmental Health" form.  |            |       |              |   |
|     | SECTION III : ENFORCEN PRIVATE CONSTRUCTION PROJECTS  | Æ          | IT /  | 24:103888888 | ONS<br>BLIC WORKS PROJECTS              |
| П   | Issued a Notice of Violation  | <b>-</b> 7 | Issue |              | otice of Violation                      |
|     |   | _          |       | rce Co       |   |
|     |   | _ ,        | With  | nold Pa      | ayment                                  |
|     |   | _          | lssue | ed a St      | op Work Order                           |
| П   |   | _          | No A  | ction F      | Required                                |
|     |   |            |       | uest Ins     | spection by an Authorized Water Quality |
|     | Other (Please Explain):   |            | _     |              | se Explain):                            |
|     |   |            |       |              | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, |
|     | HER/COMMENTS  |            |       |              | •                                       |
| ОТ  | TER/QUIVIENTS   |            |       |              |   |
| ОТ  | TERICOMMENTS  |            |       |              |   |
| ОТ  | TERICOMMENTS  |            |       |              |   |
| ОТ  | TENCOMMENTS   |            |       |              |   |
| OT  | TENCOMMENTS   |            |       |              |   |
| OT  | TENCOMMENTS   |            |       |              |   |
| ОТ  | TENCOMMENTS   |            |       |              |   |

# Exhibit A-8.IV

# **Enforcement Forms**



| Citation No. |  |
|--------------|--|
|--------------|--|



# CITY OF LAKE FOREST NOTICE OF VIOLATION/ADMINISTRATIVE COMPLIANCE ORDER

| Date Order Issued:        | Date                         | Violation Observed:                              | Time of Violation   | on: AM / PM   | Day of Week:                                       |
|---------------------------|------------------------------|--|---------------------|---------------|--|
| Location of Violation (A  | address/Point(s)             | of Discharge):                                   |                     |               |  |
| Issuing Officer:          |                              | Department:                                      |                     |               | red by:  mail mail service post on property        |
| Citation Issued to:       | Last                         | First  | Mid                 | _             | Identification/Driver's License:                   |
| Title/Relationship to the | Violation (ex: I             | Property Owner, Tenant, C                        | Contractor):        |               |  |
| Business Name (if applied | cable):                      |  |                     | NPDES         | Permit Number (if applicable):                     |
| Mailing Address (if diffe | erent from above             | e): Ci   | ty/State:           | Zip:          | Phone Number:                                      |
| ☐ FINE: \$                | Failure/refus<br>Municipal ( |  | with information r  | equired by C  | hapter 15.14 of the Lake Forest                    |
| ☐ FINE: \$                | _                            | sal to Implement Best M                          | Management Pract    | ices          |  |
| ☐ FINE: \$                |                              | sal to timely comply wi                          | ith Previously issu | ed Citation # |  |
| ☐ FINE: \$                |                              | Section 15.14.030 of t                           | · ·                 |               |  |
| and you are ordered to    | take the remed               |  | below. Continued    |               | above by//20, ce may result in civil, criminal, or |
|                           |                              | his box is checked, you the area affected by the | •                   | cease any an  | d all activities contributing to the               |
|                           |                              | E ORDER AND PENAL eeting the required cor        |                     |               | you are ordered to pay the fine .                  |
| To correct the viola      | ation(s), you                | must:  |                     |               |  |
|                           |                              |  |                     |               |  |
|                           |                              |  |                     |               |  |
| Without admitting g       | uilt, I acknov               | vledge that I have rec                           | eived this citatio  | n.            |  |
| Signature                 |                              |  |                     | Date          |  |

The law requires that you take steps to either: (1) COMPLY with this citation; or (2) CONTEST the issuance of this citation. To COMPLY with this citation, correct the violation and pay any required fine. To CONTEST this citation, follow the procedures listed on the reverse side of this citation.

**TO PAY THE FINE:** Fines are due on the date the citation is issued. The fine may be mailed or delivered in person to the CITY OF LAKE FOREST, 25550 Commercentre Drive, Suite 100, Lake Forest, CA 92630, ATTN: Finance Department. Payment should be made by check or money order payable to "City of Lake Forest." Do not send cash. **The citation number must be written on the face of the check or money order**. **Important:** The payment of the fine does NOT excuse you from the requirement to correct the violation. Payment of fines also does not bar the City from further enforcement actions regarding violations that are not corrected.

**CONSEQUENCES FOR FAILURE TO PAY FINE.** The amount of any penalties imposed by this order which have remained delinquent for a period of **sixty (60) days** shall constitute a lien against the real property of the person violating Chapter 15.14 of the Lake Forest Municipal Code. This lien may be recorded with the County Recorder and when recorded shall have the force and effect and priority of a judgment lien.

RIGHTS TO APPEAL. You may appeal from the issuance of a Notice of Violation, cease and desist order, or Administrative Compliance Order (collectively, "Order") to a hearing officer in accordance with the appeal procedures set forth in Lake Forest Municipal Code Chapter 1.12, except that any such appeal shall be filed within fifteen (15) days of date of service of the Citation. An appeal must be made in writing, by filing a written Notice of Appeal with the City Clerk, along with a deposit of the full amount of the fine and payment of the relevant fee for appeal, stating the grounds for why the Order is not proper and thus being contested. Any appeal shall be limited to such written grounds. If you are financially unable to make the advance deposit of the full amount of the fine and appeal fee, you may file a request for an advance deposit hardship waiver form, available from the Finance Department within five (5) days of the date of the issuance of the Order. The requirement of depositing the full amount of the fine and appeal fee shall be stayed until the Finance Director makes a determination on the advance deposit hardship waiver. If the Finance Director determines not to issue an advance deposit hardship waiver, you must remit the fine and appeal fee to the City within five (5) days of the date of that decision or fifteen (15) days from the date of issuance of the Order, whichever is later. An appeal of the Citation will result in an administrative hearing. You will be notified of the time, date and place for the appeal hearing at least ten (10) days prior to the date of the hearing. Failure of any person to timely submit the written Notice of Appeal and make the required deposit within fifteen (15) days from service of the Order shall constitute a failure by the person who was entitled to appeal to exhaust his or her administrative remedies.

I REQUEST A HEARING TO REVIEW THIS ORDER. THE GROUNDS FOR THIS REQUEST ARE (please use a separate sheet

of paper if more space is needed): No violation occurred. The violation was corrected within the correction period. The person who received the citation is not responsible for the violation. Explain: Print Name Date Signature **Office Use Only** Date Request Received: [Stamp Here] Administrative Review Hearing to be held: Date: Time:\_\_\_ Location:

### Exhibit A-8.V

# Form for Evaluating Threat to Human or Environmental Health





### WATER QUALITY PROGRAM

| PROJECT ID:   | N                                       |   |            |     | SPECTOR(S): |        |                       |         |          |  |  |  |
|---|---|---|------------|-----|-------------|--------|-----------------------|---------|----------|--|--|--|
| ADDRESS/TRACT:  | · · · · · · · · · · · · · · · · · · ·   |   |            |     |             |        |                       |         |          |  |  |  |
| ARRIVAL TIME:   |   | DEPARTURE TIME:   |            |     |             | F      | PHOTOGRAPHS TAKEN:    | ПΥ      | □N       |  |  |  |
| WEATHER CONDITION:                                      | INSPECTION DATE:                        |   |            |     |             |        |                       |         |          |  |  |  |
| SITE PRIORITY   | HIGH PRIORI                             | ГҮ  |            |     | ME          | DIUM I | PRIORITY              |         |          |  |  |  |
| (Check Applicable)                                      | LOW PRIORIT                             | ·Y  |            |     | PR          | IORITY | UNKNOWN               |         |          |  |  |  |
| SEASON<br>(Check Applicable)                            | RAINY (OCTO                             | BER 1 THROUGH APRIL 30)   |            |     | NO          | N-RAII | NY (MAY 1 THROUGH SEI | PTEMBER | R 30)    |  |  |  |
| NAME OF SITE REPRESI                                    | ENTATIVE PRESEN                         | T DURING INSPECTION:  |            |     |             |        | PHONE No:             |         |          |  |  |  |
| DEVELOPMENT SIZE: _                                     | EST                                     | IMATED % OF DISTURBED A   | AREA:      |     |             |        | _ THOMAS BROS. MAP/F  | G GRID  |          |  |  |  |
| DEVELOPER/CONTRACT                                      | FOR NAME                                | . <u> </u>  | WNER N     | IAM | E           |        |                       |         | <u>.</u> |  |  |  |
| TYPE OF CONSTRUCTION                                    | N:<br>SIDENTIAL                         | COMMERCIAL  | <u> </u>   | NDU | STF         | RIAL   | ☐ INFRASTRU           | CTURE   |          |  |  |  |
| ☐ REG   | CONSTRUCTION                            | TRANSPORTATION  |            | тні | ER          |        | •                     |         |          |  |  |  |
|   |   |   | l :        |     |             |        | T                     |         |          |  |  |  |
| habitat/endangered spe<br>ESA or an ASBS area?          | ecies, an impaired  e evidence of the   | mpact wildlife, sensitive water body (303d listed), and discharge (turbidity, TSS), a | •          | Y   | N           | N/A    | COMMEN                | ITS     |          |  |  |  |
|   | bserved (to a storr                     | m drain or water body) that   | could<br>, |     |             |        |                       |         |          |  |  |  |
| If YES, describe th<br>quantity discharge               |   | sewer spill and estimate the  | Ð          |     |             |        |                       |         |          |  |  |  |
| Oil spill discharge obse<br>impact wildlife?            | rved (to a stormdra                     | ain or water body) that coul  | d          |     |             |        |                       |         |          |  |  |  |
| If YES, describe th<br>discharged from th               |   | oil spill and estimate the qu   | antity     |     |             |        |                       |         | •        |  |  |  |
| Toxic materials or haza evacuation of residents         |   | discharged from the site ar   | nd         | -   |             |        |                       |         |          |  |  |  |
| If YES, describe th<br>discharged from th<br>evacuated. | e evidence of the<br>e site and the num | discharge, estimate the vol<br>aber of residents that were                            | ите        |     |             |        |                       |         |          |  |  |  |

### Evaluation Form for Potential Impacts to Human or Environmental Health

| CRITERIA   |                          | Y     | I N/A         | COMMENTS                  |
|--|--------------------------|-------|---------------|---------------------------|
| Is the site near a public water supply (well head, monitoring wells could the discharge affect the water supply?   | ) and                    |       |               |                           |
| IF THE ANSWER IS YES TO ANY OF THE QUESTION  | ONS IN SE                | CTI   | ON I, F       | OLLOW THE STEPS BELOW.    |
| Issued a Notice of Violation and/or contacted Water  | er Quality F             | rog   | ram Ma        | anager                    |
| Siam od:   |                          |       |               | Date:                     |
| Signed:Inspector   |                          |       |               | Date,                     |
| Secti<br>FOR WATER QUALITY PR  | alabian kan balan bari K |       |               | ED ANI V                  |
| 1. Contact the RWQCB by telephone within 24-hours  | of the dis               | cove  | ery of n      | on-compliance             |
| <ol> <li>Fax a copy of this form to the RWQCB within 5 da<br/>Santa Ana Regional Water Quality Control Board<br/>San Diego Regional Water Quality Control Board</li> </ol> | Fax Numb                 | er: ( | 951)32        | 1-4580 (Attn: Aaron Buck) |
| Date Notice of Violation Issued  |                          |       |               |                           |
| Date RWQCB Contacted by Phone  |                          |       |               |                           |
| Name and Telephone Number of RWQCB Contact   |                          |       |               |                           |
| Date written report faxed to RWQCB   |                          |       | <del></del> . | ·                         |
|  |                          |       |               |                           |
| Signed:  |                          |       |               | Date:                     |

City of Lake Forest 25550 Commercentre Drive, Suite 100 Lake Forest, CA 92630 949-461-3400